

Amendment 1

**STATEMENT OF WORK
FOR
REPLACEMENT OF B3201 GREASE TRAP AND
KITCHEN CABINETS**



January FY 26

PREPARED BY:

**17TH CIVIL ENGINEER SQUADRON
(AETC)
460 E. KEARNEY BOULEVARD
GOODFELLOW AIR FORCE BASE
(AFB), TX 76908-4104**

BLANK PAGE

Table of Contents

PART 1.0– SCOPE OF WORK.....	4
PART 2.0 - PRODUCTS	12
PART 3.0 - EXECUTION	13
PART 4.0 – ENVIRONMENTAL REQUIREMENTS.....	14

ATTACHMENT 1: TECHNICAL EXHIBIT

TE-1: GREASE TRAP IMAGES AND LOCATION

ATTACHMENT 2: DOD CONTRACTORS GUIDE

STATEMENT OF WORK

PART 1 – SCOPE OF WORK:

1.1 GENERAL: The work to be performed under this contract and in accordance with this Statement of Work (SOW) shall consist of furnishing all necessary plant, labor, tools, transportation, supplies, supervision, equipment, materials, and incidentals necessary for providing all work shown on the drawings (See TE-1) and in this Statement of Work (SOW), and all applicable codes, regulations, standards, and criteria in effect at the date of solicitation. This work shall consist of, but not be limited to the following:

1.2 PROJECT DESCRIPTION: The existing grease trap at B3201 Crossroads Dining Facility is undersized and unserviceable, which is causing frequent backups. This poses risks of foul odors and health code violations. The Contractor is to remove, relocate, and replace with new 90-gallon static holding capacity, 75 GPM, stainless steel grease interceptor or approved equal. The new installed grease interceptor is to be relocated to exterior of facility. The Contractor is to demolish and replace all bottom cabinetry in the kitchen area to match existing. The Contractor shall field verify all dimensions, utility lines locations, and site conditions prior to performance of work.

1.3 LOCATION: Goodfellow AFB is in Tom Green County, on the southeast side of San Angelo, Texas and is bounded to the north by Highway #388 (Paint Rock Rd.), to the west by Fort McKavitt Rd and Bell Street/Christoval Road, to the south by South Chadbourne St (Hwy. 1223) and to the east by the eastern city limits. The physical location of the worksite is 220 E Kearney Blvd., Goodfellow AFB, Texas 76908-3218

1.4 WORK AND MECHANICS: The work for this project shall be executed in the best and most workmanlike manner. Individual trade work for this project shall be performed and quality maintained by the applicable trade only. The Contractor shall assure that all trades coordinate their work with that of other trades. The Contractor shall coordinate and perform all operations in a manner that will result in a professional and expeditiously completed project. The work shall be in strict accordance with prevailing industry standards and manufacturer's instructions. Work and materials shall comply with this SOW and the editions in effect at the time of this solicitation for all applicable criteria, regulations, guidelines, and codes, all of which are made a part thereof.

1.5 WORKING CONDITIONS: The Contractor shall have one hundred twenty (120) calendar days to perform all work after signing the Notice to Proceed (NTP). The Contractor shall submit product specifications for all new materials. The Contracting Officer must approve materials before the Contractor makes any purchase. All Contractor operated/owned vehicles, equipment, tools, etc., shall be stored as prescribed in paragraph (1.13) DELIVERY, STORAGE, AND PARKING. Applicable traffic control signage where required by the contract shall remain overnight. Parking on turf shall not be permitted without prior Government Approval (GA).

1.5.1 Work Schedule: Working hours for the Contractor will normally be between the hours of 7:30 a.m. and 4:30 p.m. excluding Saturdays, Sundays, Federal Holidays, AETC Family Days.

	<u>2026</u>	
<u>Federal Holiday</u>	<u>Holiday</u>	<u>Family</u>
<u>New Year's Day</u>	<u>01 Jan</u>	<u>02 Jan</u>
<u>Martin Luther King's B-day</u>	<u>19 Jan</u>	
<u>Washington's Birthday</u>	<u>16 Feb</u>	
<u>Memorial Day</u>	<u>25 May</u>	<u>22 May</u>
<u>Juneteenth</u>	<u>19 Jun</u>	<u>22 Jun</u>
<u>Independence Day</u>	<u>03 Jun</u>	<u>06 Jul</u>
<u>Labor Day</u>	<u>07 Sep</u>	<u>04 Sep</u>
<u>Columbus Day</u>	<u>12 Oct</u>	
<u>Veterans Day</u>	<u>11 Nov</u>	
<u>Thanksgiving Day</u>	<u>26 Nov</u>	<u>27 Nov</u>
<u>Christmas Day</u>	<u>25 Dec</u>	<u>24 & 31 Dec</u>

The work to be performed on this project will include work in an occupied facility. The Contractor shall coordinate the work of all activities whereby both the Government and the Contractor can continue operations with the least possible interference and inconvenience. The Contractor shall conduct all work such that means of facility ingress and egress are maintained at all times. The Contractor shall be responsible for providing suitable, approved signs, barricades, roped barriers, etc., to warn occupants of hazardous areas at the job site for the duration of the contract at no additional cost to the Government. If personnel are reasonably available, the Contracting Officer may authorize the Contractor to perform work during periods other than normal duty hours/days. If such work is required Contractor shall submit request in writing to Contracting Officer a minimum of seventy-two (72) hours in advance for GA.

1.5.2 Work Area Access: Government personnel escorts are not needed for this SOW.

1.6 PHASING REQUIREMENTS: Not Required.

1.7 SAFETY: All Contractor operations shall be conducted and performed in accordance with Department of Labor, Occupational Safety and Health Standards (OSHA) requirements found in Title 29 Volume 5 Subtitle B Chapter XVII 1910.120 and Volume 8 Subtitle B Chapter XVII 1926, and Air Force Occupational Safety & Health (AFOSH) standards including AFMAN 91-203. The Contractor shall also ensure that all work is performed in accordance with project identified Environmental Protection Agency (EPA), national standards, military manuals, instructions, pamphlets, standards, and handbooks, and with the latest edition in effect on the date of this solicitation of the Corps of Engineers (COE) Safety & Health Manual EM 385-1-1. All job sites are subject to inspections by the Government, Department of Labor, and State of Texas. In the event of conflicts between the OSHA standards and these requirements, the most stringent shall apply.

1.7.1 All companies who conduct business within the State of Texas must, in accordance with Texas Worker's Compensation laws have an approved company safety policy and an Accident Prevention Plan. The plan, approved by the Texas Worker's Compensation Commission (TWCC), shall be submitted For Information Only (FIO) in accordance with paragraph, SUBMITALS (1.11). In addition to meeting the TWCC requirements, the plan must also include the requirements of COE Safety & Health Manual EM 385-1-1.

1.7.2 Resolution of Department of Labor citations for violations of OSHA is a Contractor responsibility and shall provide for no basis of a claim against the Government.

1.8 PROTECTION OF GOVERNMENT PROPERTY: The Contractor shall use reasonable care to avoid damaging existing trees, troop walk, sidewalk, valve boxes, light poles, signs, curb & gutter, concrete pavement, and exterior of buildings, and equipment on the Government installation. If the Contractor fails to use reasonable care and causes damage to any property, the Contractor shall replace or repair the damage at no expense to the Government as recommended by Civil Engineering and approved by the Contracting Officer. If the Contractor fails or refuses to make such repair or replacement, the Contractor shall be liable for the cost, which may be deducted from the contract price.

1.9 SITE MAINTENANCE AND CLEANUP:

1.9.1 Site Maintenance: The Contractor shall protect adjacent property, buildings, and their contents from dust, dirt or other materials. Work areas shall be maintained in a neat, clean, and safe condition and shall, at a minimum, be cleaned at the end of each shift. All streets and roadways in/or adjacent to the site shall remain free of project generated dust, rock, dirt, trash and debris at all times.

1.9.2 Daily Cleaning: The Contractor shall always keep the site free from debris and shall perform daily cleaning of all areas.

1.9.3 Cleanup: The Contractor shall collect all trash, debris, refuse, garbage, etc., that is generated and place it in appropriate containers with lids or approved covers on a periodic basis or as directed by the Contracting Officer. The Contractor is not permitted to use installation dumpsters and other trash receptacles. The materials shall be hauled from the site by appropriate means on a daily basis, unless otherwise approved by the Contracting Officer. Disposal shall be outside the limits of Government property. Disposal shall be by sanitary landfill or recycled and shall conform to all local, State, and Federal guidelines, EPA criteria, and regulations. Upon completion of the work, the Contractor shall leave the work site and storage area(s) in a clean, neat, and workmanlike condition satisfactory to the Government.

1.9.4 Contractor Dumpsters: Should the Contractor require a dumpster it shall be at the Contractor's own expense. The location of the dumpster shall be submitted for approval to the Contracting Officer and will be maintained to prevent overflow and spreading of construction debris caused by wind and other factors.

1.10 REFERENCES: The Contractor shall identify and comply with all applicable federal, state, and local laws; statutes; Executive Orders; Department of Defense/Air Force Manuals, handbooks, regulations, guidance, and policies. The Contractor shall comply with the National Institute of Building Sciences' Whole Building Design Guide Construction Criteria Base Unified Facility Criteria (UFC) and all related libraries. It is the Contractor's responsibility to identify and comply with all applicable requirements. In addition to the documents referenced above, all publications listed herein shall be the most current editions in effect at the time of solicitation and form a part of this SOW. The publications are referred to in the text by basic designation only and include the following:

INTERNATIONAL PLUMBING CODE (IPC) CHAPTER 10

UNIFIED FACILITIES CODE (UFC) 3-240-03 – OPERATION AND MAINTENANCE (O&M):
WASTEWATER TREATMENT

US ARMY CORPS OF ENGINEERS (COE) SAFETY & HEALTH MANUAL EM 385-1-1

GOODFELLOW AIR FORCE BASE INSTALLATIONS FACILITIES STANDARDS (IFS)

CODE OF FEDERAL REGULATIONS (CFR)

ENVIRONMENTAL PROTECTION AGENCY PUBLICATION (EPA)

TEXAS COMMISSION OF ENVIRONMENTAL QUALITY (TCEQ)

AFMAN 32-7001

AFMAN 91-203

CLEAN AIR ACT (CWA) AND ALL AMENDMENTS

CLEAN WATER ACT (CWA) AS AMENDED

COMPREHENSIVE ENVIRONMENTAL RESPONSE, COMPENSATION, AND LIABILITY
ACT (CERCLA)

EMERGENCY PLANNING AND COMMUNITY RIGHT – TO – KNOW ACT (EPCRA)

FEDERAL WATER POLLUTION CONTROL ACT (FWPCA)

NATIONAL OIL AND HAZARDOUS SUBSTANCES CONTINGENCY PLAN (NCP)
OCCUPATIONAL HEALTH AND SAFETY ACT (OSHA)

AFI 32-7086 HAZARDOUS MATERIALS MANAGEMENT

OIL POLLUTION ACT (OPA)

POLLUTION PREVENTION ACT (PPA)

RESOURCES CONSERVATION AND RECOVERY ACT (RCRA)

SAFE DRINKING WATER ACT (SDWA), AS AMENDED

AIR FORCE OCCUPATIONAL SAFETY & HEALTH (AFOSH)

1.11 SUBMITTALS: The Contractor shall provide submittals in the form of manufacturer's data, certificates of compliance, and samples for all items provided and installed. The Contractor will not be permitted to perform any work on site without approved submittals. The submittals listed in this SOW shall be required and shall be submitted for GA or For Information Only (FIO) and submit four copies of submittals to Contracting Officer for approval/disapproval.

1.12 WARRANTY: The Contractor shall identify all items being installed that are guaranteed or under an extended warranty for more than a one (1) year period and provide validated copies of the manufacturer's warranty. All warranty information shall be filed by the Contractor in the Government's name. All warranties shall be identified by product with a listing of the name and address of the company and the expiration date of the guarantee or warranty. Warranty documentation shall be submitted to the Contracting Officer for GA.

1.13 DELIVERY, STORAGE AND PARKING: All equipment and materials delivered or stored shall be protected from the weather, humidity, and temperature variation, dirt and dust, and any other contaminants.

1.13.1 Contractor Parking & Storage: The Contractor shall submit a material and equipment storage area and for contractor parking layout for GA before commencing of any work.

1.13.2 Storage Areas: The Contractor shall not work or store materials in a manner that would hinder or otherwise block pedestrian circulation to exit corridors and exit doors in the event of an emergency or fire. If space allows, materials may be stored at the job site as coordinated with and approved by the Contracting Officer before commencing of any work. Otherwise, materials shall be stored off Government property until ready for installation at no additional cost to the Government. In instances where on site storage is not available, the Contractor shall be responsible for storing and preparing materials in the manner specified herein, or by the manufacturer's instructions, so that materials are properly suited for installation. Off-site acclimatization of materials shall be at no additional cost to the Government. All project storage areas shall be kept free of debris, leaks, stains, or splashes and kept in a neat, clean, and safe condition. Any contamination of the storage area by a hazardous substance shall be immediately remediated by the Contractor, in accordance with PART 2.0 below at no additional expense to the Government. All other hazardous materials shall be secured when not in use.

1.14 UTILITY OUTAGES AND SPECIAL CONDITIONS:

1.14.1 PERMITS:

1.14.1.1 Base Civil Engineer Work Clearance Request: The Contracting Officer shall obtain and process AF Form IMT 103 for approval prior to commencement of work for this project.

1.14.2 Utility Outages: When a utility outage is necessary to perform the contract work in a landscaped area, regardless of whether the work area is occupied, the outage shall be performed by the Contractor during non-duty hours at no additional cost to the Government, unless otherwise approved by the Contracting Officer. The Contractor shall notify 17th CES Service Call (325-654-3436) of outage requirements to include buildings affected; length of outage; and reasons for the outage. The Contractor is also required to provide the Contracting Officer written notification of the requested outage for GA.

1.14.3 Utilities Conservation: The Contractor shall instruct employees in utilities conservation practices. The Contractor shall be responsible for operating under conditions that preclude the waste of utilities, which shall include Lights shall be used only in areas where and when work is being performed. The Contractor shall not adjust mechanical equipment controls for heating, ventilation, and air conditioning systems. Water faucets or valves shall be turned off after the required usage has been accomplished. The Contractor shall not abuse the use of base telephones. Telephones shall be used for contract-related issues only. The Contractor shall use good judgment in the conservation of Government utilities. Prevailing energy conservation practices shall be adhered to and enforced by the Contractor.

1.14.4 Air Force Fire Regulations: The Contractor shall comply with Air Force Fire Regulations as set forth in the latest edition of AFI 32-2001. The Contractor shall use no explosives in performing the work. All work shall be in strict compliance with NFPA-101.

1.14.4.1 Welding, Cutting, and Brazing: The Contractor shall contact 17 CES/CEFP (Fire Prevention) for a complete inspection of all welding, cutting, and brazing operations prior to any operation. The Contractor shall provide an appropriate operable fire extinguisher. Contractor shall comply with OSHA Standard 29 CFR 1910.252 Welding, Cutting, and Brazing (General Requirements) and AFOSH 91-5 Welding, Cutting, and Brazing. An AF Form 592 USAF Welding, Cutting and Brazing permit will be issued prior to any operation and shall be kept on site until completion of operation or permit expires. Contact Fire Prevention at (325) 654-3532/33/34 for issuance of permit.

1.15 DISPOSAL: Items to be included in the disposal shall consist of but not limited to the careful removal and disposition of materials. The Contractor shall recycle or divert wastes from landfill disposal to the maximum extent practicable. The Contractor shall track recycling and waste disposal and submit the report on the Waste Management Form provided for GA at the end of the project, and prior to final acceptance of the work. The Contractor shall, before commencement of any work, carefully survey the existing site to determine the extent of the work. The Contractor shall be responsible for the proper disposal of all materials meeting all rules pertaining to disposal. Rubbish

and debris shall be removed from Government property daily, unless otherwise directed, to avoid accumulation at the site. Materials that cannot be removed daily shall be stored in areas specified by the Contracting Officer. In the interest of conservation, salvage shall be pursued to the maximum extent possible; salvaged items and materials shall be disposed of as specified. The use of Government dumpsters and trash collection is not permitted.

1.16 SECURITY REQUIREMENTS:

1.16.1 Goodfellow AFB is a closed/controlled access base. In an effort to minimize peak traffic flows at the entry gates, the Contractor, contractor employees, and Subcontractors are highly encouraged to avoid scheduling deliveries through the entry control gates from 7:00 A.M. to 8:00

A.M. Monday through Friday as there could be significant delays. Security requirements will be briefed at the pre-construction conference and handouts outlining specific requirements will be provided. Screening measures are in place and suitability for employees to access the installation will be determined during the conference. Requirements are subject to change dependent upon current world situations and potential threats. Contractor should anticipate certain notification and reporting requirements, preparation of forms and lists for pass and identification of employees and their vehicles, entry restrictions, key/lock control, and compliance with all base traffic rules and regulations.

1.16.2 Goodfellow AFB security may be viewed as being one of two broad levels, the level in effect being dependent on the location or area of project.

- a. The lowest level of security exists in restricted access areas. These areas are all of Goodfellow AFB outside of the "USAF Controlled" areas.
- b. "USAF Controlled" access areas are the higher-level security areas. Presence within these controlled access areas is by authorization, and/or escort. The movement of authorized personnel in and out of these areas may be limited. Contractor personnel are permitted access to these areas on a need basis only. Access to controlled areas will require the Contractor to coordinate all requests through the Government organization occupying the project site. The Contractor is advised there may be delays gaining access to controlled areas. No delay less than one (1) hour in duration will be considered for down time, nor will delays of less than one (1) hour be cumulative over several time periods.

1.16.3 Contractors shall comply at all times with base law enforcement and security requirements to include base pass requirements.

- a. Contractor Installation Access Pass. Before arrival, a government identification card-holding person from base contracting office will submit a request for base access using the wing's Base Access List (BAL) memorandum as a form of registration for each credential applicant. The Contracting Officer/Administrator and the Contractor should establish an accountability process to account for each applicant, to oversee the BAL process, and to retrieve installation passes when access is no longer required. The Contracting Officer/Administrator will ensure

the BAL is accurate, signed, and forwarded to the 17 SFS Pass & Registration section for completion of the vetting and fitness determination processes.

- b. Contractor Initial (and Periodic) Installation Access Screening. Contractors will provide Pass and Registration with two (2) forms of identification. One of which, will be a state issued photo identification and must be the actual cards, no photocopies accepted. Driver's License and Identification Cards cannot contain the markings "Not Valid for Federal Purposes," "Not For Use as Federal Identification," "Federal Limits May Apply," or any other similar phrase. Employees with a Permanent Resident Card or Work Authorization Card must have the card in their possession. Photocopies will not be accepted. Prior to being allowed access, a minimum of a background/National Crime Information Center (NCIC) check will be completed on all contractors, requesting unescorted access for official business. The Contractor, then will be issued a temporary Defense Biometric Identification System (DBIDS) pass or AF Form 75A through the expiration date on the BAL request. Possession of an authorized access pass does not automatically authorize or guarantee access to the installation. The individual must still have a valid purpose to be on the installation and be properly sponsored, as applicable.
- c. Access Denial. If it is determined a Contractor requesting access has been convicted of a felony or pled guilty to a felony charge within the past ten (10) years or is considered not fit to obtain authorized access based on the information obtained during the identity vetting, or criminal history indicates the individual may present a threat to the good order, discipline, and morale of the installation, Security Forces personnel will deny entry. The contractor will be informed of the access denial, issued an Access Denial Letter, which will inform them on how to appeal this order.
- d. For installation access on non-duty hours or down days:
 - 1. Identify which workers require access on weekends, Federal holidays/Family days, and down days.
 - 2. Ensure only workers that are already vetted are on the Extended-Hours request (no new personnel, new personnel requiring a new BAL, and formal vetting).
 - 3. The Contracting Officer/Administrator will complete the "After Hours" BAL for workers requiring down day access to the installation.
 - 4. The Contractor will identify any after-hours special vehicle requirements. If operations cannot support the search procedures for large vehicles/special purpose equipment, the request may be declined unless arrangements are made to deliver the vehicle/equipment prior, during normal duty hours.

1.16.4 ANTI-TERRORISM

1.16.4.1 Goodfellow Air Force Base (GAFB) has an anti-terrorism program that is responsible for helping secure and protect the base and its personnel from terrorist attacks.

1.16.4.2 Contractor must obey all orders from Security Forces and adhere to all security measures implemented because of Force Protection Condition changes (security posture changes)

1.16.4.3 Contractors must report to base security forces any suspicious activities, packages, or items observed while conducting work on GAFB. Suspicious activities could include personnel conducting surveillance of the installation, unauthorized personnel requesting access to the installation, or somebody asking a lot of questions about the base.

1.16.4.4 All personnel are subject to spot checks and inspections while on the installation. Entry into restricted/controlled areas is prohibited unless otherwise authorized. In the event of a situation on base, the Emergency Mass Warning Notification system may be activated. Personnel must follow the directions given.

1.16.4.5 To help familiarize contractors with antiterrorism, all contractors possessing a valid Temporary DBIDS Pass or a DoD issues CAC Credential are required to complete Antiterrorism Level 1 Training (initially and annually thereafter). Goodfellow AFB Unit Antiterrorism Representatives have an antiterrorism binder with all pertinent information for awareness training. Also, if needed, the installation Antiterrorism Program Manager (ATPM) may be contacted at 325-654-3527.

PART 2 – PRODUCTS:

2.1 REFERENCES TO MATERIALS, MANUFACTURERS AND PRODUCTS: Materials and equipment shall be the standard products of a manufacturer or supplier regularly engaged in the manufacture of the products and shall essentially duplicate items that have been in satisfactory use for at least two (2) years prior.

2.2 VERIFICATION OF DIMENSIONS AND CONDITIONS: The Contractor is highly encouraged to visit the premises to become thoroughly familiar with details of the work and working conditions. The Contractor shall field verify all dimensions/information and advise the Contracting Officer of any discrepancies prior to the work commencement.

2.3 GOVERNMENT FURNISHED EQUIPMENT (GFE): There is no Government Furnished Equipment.

2.4 CONTRACTOR PROVIDED MATERIALS (CPM): The Contractor shall provide all materials and shall comply with Goodfellow AFB Standards. Contractor shall submit all material manufacture specifications for GA.

2.4.1 Grease Trap: Provide new one (1) Rockford welded stainless steel interceptor with 90-gallon static holding capacity for non-traffic applications or approved equal.

2.4.14 TRAINING AND MANUALS: The Contractor shall provide operational and maintenance training as recommended by the manufacturer, to train Government craftsmen and provide all

operating, maintenance, and parts manuals instructions to include parts listings of equipment and other materials installed.

2.4.15 MATERIALS: The contractor shall provide all equipment, tools, hardware/software and materials necessary to provide complete electrical, mechanical, and physical connections from the new equipment to the existing equipment and connections.

PART 3 – EXECUTION:

3.1 GENERAL: All work shall be installed as shown and in accordance with the manufacturer's diagrams and instructions, unless otherwise specified. All dimensions are shown for information only. Contractor shall field verify all dimensions and site conditions before ordering new equipment and beginning on site project execution.

3.2 INSTALLATION:

3.2.1 Field verify the existing grease trap, underground utilities, along with all gas and sewer piping sizes before ordering new equipment and beginning on site project execution.

3.2.2 Prior to removal of existing grease trap the Contractor must ensure that water supply to all fixtures draining into the grease trap is shut off.

3.2.3 The Contractor shall pump and empty out all contents of the old grease trap. Grease trap shall be disposed by a licensed waste management company to an appropriate and approved disposal facility.

3.2.4 The Contractor shall disconnect all plumbing associated with the old grease trap.

3.2.5 The contractor shall provide pea gravel bedding material, for the grease trap stability installation.

3.2.6 The Contractor is to install new grease trap underground at the exterior of the building (see technical exhibits for proposed location)

3.2.7 Provide new dual inflow and outflow clean outs with accompanying cleanout covers set to match concrete pad elevation.

3.2.8 The Contractor shall install concrete pad covering proportionate in size to cover new grease trap and house new clean outs.

Concrete pad specifications: Concrete pad dimensions are to be 10' x 9' proportionate to housed grease trap. Concrete pad will be four inches (4") thick, with height matching manhole cover. #3 rebar placed to conform to the size and dimension of the concrete pad at 18" on center grid pattern or equivalent welded wire mesh. Allow for 2" cover/clearance. Provide 2" compacted base course material to facilitate laying concrete. (See attached image for reference pad)

3.2.9 The Contractor shall provide new bollards housed within the new concrete pad, one at each corner. Bollards are to be in compliance with Goodfellow Installation Facility Standards.

Bollards: Install 4 bollards at each corner, each bollard will set 36" above the surface elevation with 1' depth. Fill each bollard with concrete and paint each bollard with bronze slate colored paint conforming with installation standards being 4" in diameter. Each bollard is to be one foot – six inches (1' – 6") on center. Use short side of pad for dimensions.

3.2.10 The Contractor shall position new grease trap in designed location, ensuring correct orientation for connections.

3.2.11 The Contractor shall connect all plumbing connections (inlet, outlet, and vent).

3.2.12 The Contractor shall demolish all cabinetry shown in the attached technical exhibits.

3.2.13 The Contractor shall install new cabinetry to replace existing.

Cabinet Specifications: All cabinetries shall match existing. Existing cabinetries are as specified: MinWax-Classic Gray Weathered Oak stain color. HiMacs solid surface color selection shall be M201 Terni. As-built drawings will be provided at award, A-102 would give existing cabinetry dimensions.

3.2.14 The Contractor shall conduct testing and commissioning of the newly installed grease trap. The testing is to consist of initial fill of grease trap with water, leak check of all connections. Tighten fittings if needed. The overall functionality of installed grease trap system is to be tested.

3.3 FINAL INSPECTION: Final inspection will include system operation, submission of certified warranty documentation, drawings, and equipment specifications. The Contractor shall advise the Contracting Officer in writing of the Contractor's desired final inspection date seven (7) calendar days in advance of that desired date to permit proper coordination. The date selected shall provide adequate time for Contractor performed corrections of final inspection deficiencies within the contract performance time. The Contracting Officer will be the final authority for determining whether or not the Contractor's performance is sufficiently advanced to warrant a final inspection.

PART 4 – ENVIRONMENTAL REQUIREMENTS:

4.1 COMPLIANCE WITH LAWS: Construction activities are NOT exempt from air emission, storm water, hazardous waste, and other environmental compliance rules and regulations. The Contractor shall read Attachment 3: DoD Contractor's Guide and fully comply and ensure that all Sub-Contractors comply with all applicable Federal, State, and Local laws, regulations, ordinances, and standards related to environmental matters. The Contractor shall also comply and ensure that all Sub-Contractors comply with all specific instructions or directions given to the Contractor by Goodfellow AFB regarding environmental matters.

4.2 HAZARDOUS AND SPECIAL WASTES GENERATED BY THE CONTRACTOR: The Contractor shall identify, characterize, containerize, store, and dispose of hazardous waste in strict accordance with Federal guidelines found in the CFR, Title 40 Volume 26 and 27 parts 260-270, State regulation 30 TAC 335, all local guidelines, and as specified. A Uniform Hazardous Waste Manifest shall be used by the Contractor to document all parties and locations involved in the transportation, storage and disposal of all hazardous and special waste.

This form shall be provided to the Government by the Contractor and signed by the Base Environmental Engineer (17 CES/CEIE) before the waste is transported from the limits of Government property. A copy of the manifest shall be signed by the receiver of the waste and submitted to the Contracting Officer not later than forty-five (45) days after disposal has taken place. Hazardous waste treatment, storage and disposal facility shall be located within the State of 14 Texas, permitted by the U.S. EPA, and approved by CEIE.

4.3 CONTRACTOR ENCOUNTERED HAZARDOUS WASTE: The Contractor shall notify the Contracting Officer and 17 CES/CEIE upon encountering any material not identified in this SOW

thought to be hazardous that could jeopardize the safety of workers or personnel in the area. The Government will be responsible for characterization, transportation, storage, and disposal of the waste if necessary.

4.4 ASBESTOS: To the best of the Government's knowledge, no asbestos-containing material (ACM) will be encountered during this project. Should the Contractor encounter previously unidentified or suspected ACM which must be disturbed to comply with the contract documents, the Contractor shall cease that work which would disturb the suspect material and shall immediately notify the Contracting Officer.

4.4.1 Asbestos Containing Building Materials: Under no circumstances, under the provisions of this contract, shall the Contractor be allowed to provide asbestos containing building materials, or products containing encapsulated asbestos or mineral fibers as defined in the Title 40 Volume 9 Part 61, National Emission Standards for Hazardous Air Pollutants, to Goodfellow AFB. The Contractor shall provide a signed statement, accompanied by Safety Data Sheet (SDS) for project materials, from a licensed asbestos inspector or the project architect or engineer, proclaiming that no asbestos-containing building materials were used in the construction.

4.5 HAZARDOUS MATERIALS: The Contractor shall provide to the Contracting Officer a Material Approval Submittal listing all materials to be utilized during the contract. If any of the material is classified as hazardous materials in accordance with regulations and AFMAN 32-7002, the Contractor will submit an installation Contractor Hazardous Materials Usage Tracking Form (Attachment 3: DoD Contractor's Guide) for all material items with all supporting information as required for GA. This is to ensure that all hazardous materials used on the installation are tracked at a level sufficient to ensure contractor compliance with local monitoring, determination, authorization, tracking, and to meet environmental reporting requirements and support fire protection, ESOH, and disaster response efforts. The Contractor must obtain authorization from the Contracting Officer prior to bringing or using any hazardous materials on the installation. The Contractor must supply up to date SDS for each requested items, that were listed as a hazardous material, as defined to be delivered under this contract. The hazardous materials shall be properly identified on the required request form and shall include any applicable identification number (such as part numbers, manufacturers name and any other special item number). This information shall also be included on the SDS submitted under this contract. The Contractor must maintain a file of all SDS. The Contractor shall submit for GA to the Contracting Officer on a monthly basis, or at the end of the contract, as determined by the Contracting Officer, a Contractor Hazardous Materials Usage Tracking Form (two (2) copies) on the usage of all HAZMAT materials used within that reporting period. No chemicals, lubricants, oils, liquids or related materials shall be deposited in the refuse containers on base.

4.6 NUISANCE AND POLLUTING ACTIVITY PROHIBITED: Polluting, dumping, or discharging of any harmful, nuisance, or regulated materials (such as but not limited to concrete truck washout, vehicle maintenance fluids, residue from saw cutting operations, solid waste and hazardous substances) into building drains, site drains, streams, waterways, holding ponds or to the ground surface shall not be permitted and the Contractor shall be held responsible for any and all damages which may result. Further, the Contractor shall conduct work activities in such a fashion

as to avoid creating any legal nuisance, including but not limited to, suppression of noise and dust, control of erosion, and implementation of other measures as necessary to minimize offsite impacts of work activities.

4.7 RELEASE OF FLUIDS TO THE SANITARY SEWER SYSTEM: Goodfellow AFB's sanitary sewer system discharges into the Publicly Owned Treatment Works (POTW) operated by the City of San Angelo, Texas. This POTW has established testing requirements for certain constituents as well as discharge limits of those same constituents. Accordingly, any Contractor performing work at Goodfellow AFB and contemplating a release of non-hazardous water into the sanitary sewer system shall meet the pretreatment standards and comply with the testing/release requirements established by the City of San Angelo. Contractor is also responsible for any and all testing, monitoring, measuring, documenting, etc., to prove compliance. Contractor shall not discharge wastewater to installation's sanitary sewer without prior GA.

4.8 AIR EMISSIONS: The Contractor shall submit air emission reports FIO, monthly and upon completion of the project to the 17 CES/CEIE. See Attachment 3: DoD Contractor's Guide for forms or call 654-3299 for any questions.

4.9 CONSTRUCTION WASTE MANAGEMENT: At the end of the project, and prior to final acceptance, the Contractor shall submit a solid waste diversion report FIO by completing the Construction Waste Management Form identifying the materials and weights either recycled or diverted from solid waste disposal to other re-use as well as weights of waste disposed in a landfill. Please see Attachment 3: DoD Contractor's Guide for forms or call 654-3299 for any questions.

4.10 ENVIRONMENTAL MANAGEMENT SYSTEM (EMS): Contractor's on-site supervisory personnel shall complete EMS Awareness Training. The Installation Management Flight system administrator should be contacted at (325) 654-3299 for information and password to complete the thirty (30) minute awareness training within sixty (60) days of contract award or a new contract employee supervisor begins work. The training will be accomplished utilizing a web-based training system called "The Environmental Awareness Course Hub" (TEACH) available through any internet access at <http://usaf.learningbuilder.com>. User will have to register for an account, create a user ID and password, and then take the EMS training. Certificate of completion must then be submitted to the Contracting Officer FIO and then forwarded to 17 CES/CEIE Environmental Management.

4.11 GREEN PURCHASING: Green Purchasing is a mandatory component of the Air Force pollution prevention program. The Under Secretary of Defense issued a policy memorandum "Establishment of the DoD Green Purchasing Program (GPP)" which states: "The DoD goal is to achieve 100% compliance with mandatory Federal GPP programs in all acquisition transactions." This document contains guidelines for implementing the Resource Conservation and Recovery Act, (RCRA) EO, DoD, and Air Force requirements.

4.11.1 Applicable Environmental Regulations and Laws:

The RCRA, Section 6002 (42 U.S.C. 6962) Title 40, Volume 25, Part 247, Comprehensive Procurement Guideline for Products containing Recovered Material. Energy Policy Act. (EPACT)

4.11.2. Exemptions:

4.11.2.1 EPA Recommendations: The U.S. EPA recommends minimum content levels for those items listed in the attached Construction Products Recovered Materials Form. These levels are mandatory for Air Force procurements unless one (1) of the following exemptions applies:

1. The product is not available from a sufficient number of sources to maintain a satisfactory level of competition (i.e., available from two or more sources.)
2. The product is not available within a reasonable period of time.
3. The product does not meet the performance standards in applicable specifications or fails to meet reasonable performance standards of the procuring agency.
4. The product is not available at a reasonable price. For Air Force purposes, “unreasonable price” is defined as follows: If the price of the recycled-content product exceeds the cost of a non-recycled item, then the price is considered unreasonable.

4.11.2.2 Contractor Responsibility: The Contractor shall complete the attached Construction Products - Recovered Materials Determination Form found in Attachment 3: DoD Contractor’s Guide, with respect to the work and products being provided. Contractor shall provide written documentation when items not meeting the minimum content levels are used. This documentation shall be forwarded to the Contracting Officer for GA. In the event the documentation fails to support the Contractor’s findings, the Contracting Officer shall return the documentation to the Contractor citing the reason(s) for disapproval.

4.11.3 EPA Designated Items:

4.11.3.1 A complete listing of the U.S. EPA-designated items can be obtained at the following website: <http://www.epa.gov/greenerproducts/recommendations-specifications-standards-andecolabels-federal-purchasing>. Also see: <https://sftool.gov/greenprocurement>. Not all of these materials may be required in the construction of this project. Please refer to the drawings and specifications. The attached Construction Products Recovered Materials Form shall be used to demonstrate compliance with the stated procurement requirements.

4.11.4 Intent: The intent of this section is to increase the use of GPP by all Contractors involved with this project.

4.11.4.1 The various sections of the specifications contain references to products to be used in the completion of this project. The listed product may or may not be manufactured from or contain recycled materials. Therefore, all Contractors, Sub-Contractors, equipment suppliers, and material suppliers are responsible for compliance with this specification and those items/products listed on the attached form. Recycled products shall be used wherever possible subject to the exemptions as per the paragraph (2.11.2) EXEMPTIONS.

4.11.5 Recycled or Recovered Products: Those materials identified on the form at the end of this section.

4.11.6 Sources of Information: The following is a partial list of sources of information for compliance with GPP requirements:

Select Sources of Supply for Environmentally Preferable Products and Services

- GSA: <http://www.gsa.gov/portal/content/105414>
- DLA: <http://www.dla.mil/WhatDLAOffers/EnvironmentalandSustainablePrograms.aspx>
- Energy Star®: <http://www.energystar.gov/>
- JWOD: http://www.abilityone.gov/procurement_list/product_contractors.html
- UNICOR: http://www.unicor.gov/Shopping/viewCat_m.asp?iStore=UNI&idCategory=1633
- EPA: <https://www.epa.gov/greenerproducts>

Green Procurement Program Product Listings

- CPG: <https://www.epa.gov/greenerproducts>
- Bio based: <http://www.biopreferred.gov/BioPreferred/>
- FEMP: <http://energy.gov/eere/femp/federal-energy-management-program>
- Energy Star: http://www.energystar.gov/index.cfm?fuseaction=find_a_product
- Alternatives to Ozone-Depleting Substances: <https://www.epa.gov/snap>
- For paints, carpet, office supplies, cleaners, and particle board: <http://www.greenseal.org/Home.aspx>
- For construction projects: <https://www.epa.gov/chemicals-under-tsca>

END OF STATEMENT OF WORK

