

DEPARTMENT OF THE NAVY
FDRMC NAPLES

FPO, AE



USS OSCAR AUSTIN (DDG 79)

SPECIFICATIONS FOR WORK TO BE ACCOMPLISHED

SPECIFICATION NUMBER: NAPL-033-26

SHIP CHARACTERISTICS

LENGTH OVERALL	509 FEET	0 INCHES
MAX. BEAM AT DESIGN WATERLINE	59 FEET	0 INCHES
EXTREME BEAM INCLUDING APPENDAGES	0 FEET	0 INCHES
DRAFT (MAX. NAVIGABLE) (FWD.)	21 FEET	9 INCHES
DRAFT (MAX. NAVIGABLE) (AFT.)	22 FEET	2 INCHES
LIGHT DISPLACEMENT	7,018	LONG TON
FULL LOAD DISPLACEMENT	9,211	LONG TON
HEIGHT OF MAST ABOVE DESIGN WATERLINE	150 FEET	1 INCHES

INCLUDES ALL CHANGES THROUGH 5/6/2026

INDEX

ITEMS THAT ARE STRUCK OUT IN THIS INDEX DO NOT APPLY TO THIS CONTRACT.

CATEGORY I. FY-26 STANDARD ITEMS APPLICABLE TO THIS JOB ORDER WITHOUT FURTHER REFERENCE.

<u>ITEM NO.</u>	<u>TITLE</u>	<u>CHANGE DATE</u>	<u>CHANGE</u>
009-001	General Criteria; accomplish	09/04/2024	Original
009-002	Environmental Compliance Report for Material Usage; accomplish	07/22/2024	Original
009-003	Toxic and Hazardous Substance; control	07/22/2024	Original
009-004	Quality Management System; provide	09/16/2024	Original
009-005	Temporary Access; accomplish	11/18/2024	CH-1
009-006	Maintaining Protection and Cleanliness from Non-Radioactive Operations; accomplish	07/22/2024	Original
009-007	Confined Space Entry, and Certification; accomplish	09/04/2024	Original
009-008	Shipboard Fire Protection and Fire Prevention; accomplish	09/30/2024	Original
009-010	Asbestos-Containing Material (ACM); control	09/16/2024	Original
009-018	Mine Warfare Ships Magnetic Material; control	09/04/2024	Original
009-019	Provisioning Technical Documentation (PTD); provide	07/22/2024	Original
009-020	Government Property; control	07/22/2024	Original
009-021	Alteration Verification, Logistic and Technical Data; provide	07/22/2024	Original
009-023	Interference; remove and install	11/18/2024	CH-1
009-024	Authorization, Control, Isolation, Blanking, Tagging, and Cleanliness; accomplish	09/16/2024	Original
009-034	Fire Protection of Unmanned Vessel at Contractor Facility; accomplish	07/22/2024	Original
009-039	Technical Manual Contract Requirement (TMCR) for a New Technical Manual for Commercial Equipment/Component; accomplish	07/22/2024	Original
009-040	Contractor Crane, Multi Purpose Machine and Material Handling Equipment at a Naval Facility; provide	07/22/2024	Original
009-060	Schedule and Associated Report for CNO Availability; provide and manage	09/16/2024	Original
009-061	Shipboard Use of Fluorocarbons; control	09/16/2024	Original
009-067	Integrated Total Ship Testing; manage	09/16/2024	Original
009-068	Availability Work Certification (AWC) Data for Chief of Naval Operations (CNO) Availabilities; provide	09/16/2024	Original
009-069	Heavy Weather/Mooring Plan; provide	09/16/2024	Original
009-070	Confined Space Entry, Certification, Fire Protection, Fire Prevention and Housekeeping for Unmanned Vessels; accomplish	09/16/2024	Original
009-072	Physical Security at a Private Contractor Facility; accomplish	09/16/2024	Original
009-073	Shipboard Electrical/Electronic Cable Procedure; inspect, test, install, remove, and repair	09/16/2024	Original
009-074	Occupational, Safety and Health Plan; accomplish	09/16/2024	Original
009-080	Ship Facility; maintain	09/16/2024	Original
009-081	Compartment Closeout; accomplish	09/16/2024	Original
009-082	Installation of Equal Component Vice Specified Component; report	07/22/2024	Original
009-084	Threaded Fastener Requirement; accomplish	07/22/2024	Original
009-088	Collection, Holding and Transfer (CHT) and Motor Gasoline (MOGAS) Tank, Space, and Piping, including Sewage or MOGAS-Contaminated Tank, Space, and Piping; certify	09/16/2024	Original
009-093	Emergency Planning and Community Right to Know Act (EPCRA) and Pollution Prevention Act (PPA) Information; provide	07/22/2024	Original

INDEX

<u>ITEM NO.</u>	<u>TITLE</u>	<u>CHANGE DATE</u>	<u>CHANGE</u>
009-099	Ship Departure Report; provide	09/16/2024	Original
009-100	Ship's Stability; maintain	09/16/2024	Original
009-101	Ship Transit and Berthing; accomplish	09/16/2024	Original
009-106	Work Authorization Form Coordinator (WAFCOR); provide	09/16/2024	Original
009-109	Non-SUBSAFE Work on SUBSAFE-Certified Vessel; accomplish	07/22/2024	Original
009-110	Non-Nuclear Work on a Nuclear Vessel; accomplish	07/22/2024	Original
009-111	Schedule and Associated Report for Non-CNO Availability; provide and manage	09/16/2024	Original
009-117	Combat Systems, Light Off Support; provide	09/17/2024	Original
009-118	CG Deck Loading; accomplish	07/22/2024	Original
009-120	Fact Finding and Critique of Unplanned Event; manage	09/17/2024	Original
009-122	Temporary Padeye; install and remove	11/18/2024	CH-1
009-125	Boat 65 Feet (20meters) Long and Less; accomplish	11/18/2024	CH-1
009-126	Schedule Model Review (SMR); accomplish	09/17/2024	Original

INDEX

CATEGORY II. FY-26 STANDARD ITEMS WHICH MAY BE INVOKED IN THE WORK ITEMS OF THIS JOB ORDER.

<u>ITEM NO.</u>	<u>TITLE</u>	<u>CHANGE DATE</u>	<u>CHANGE</u>
009-009	Process Control Procedure (PCP); provide and accomplish	09/04/2024	Original
009-011	Insulation and Lagging; accomplish	09/16/2024	Original
009-012	Weld, Fabricate, and Inspect; accomplish	09/16/2024	Original
009-032	Cleaning and Painting Requirements; accomplish	09/25/2024	Original
009-077	Cofferdam Installation; accomplish	09/16/2024	Original

INDEX

<u>ITEM NO.</u>	<u>TITLE</u>
123-11-001	Bilge Crack Temporary Repair; accomplish
256-61-001	Seawater Service Butterfly Valve SW-V-213; replace
508-11-001	Lagging and Insulation; replace
521-21-001	No. 2 Fire Pump Motor; replace
555-11-001	AFFF System Hycheck Valve; replace

SHIP: USS OSCAR AUSTIN (DDG 79) ITEM NO: 123-11-001
COAR: 26 PCN: EM04-L037
CMP: NONE
PLANNER: KRIEGER, DANIEL
ARELLANES-VIDRIO,
ANGEL
JONES, DOUGLAS

1. SCOPE:

- 1.1 Title: Bilge Crack Temporary Repair; accomplish
- 1.2 Location of Work:
 - 1.2.1 Generator Room (3-370-0-E), Approximately Frame 376, Lower Level
- 1.3 Identification:
 - 1.3.1 Not Applicable

2. REFERENCES:

- 2.1 NAVSEA Standard Items, (FY26 CH-1)
- 2.2 S9086-DA-STM-010 Rev 4, Naval Ship's Technical Manual, Chapter 100, Hull Structures
- 2.3 801-7027785 Rev K, DDG51 Class Booklet of General Plans
- 2.4 100-7026704 Rev M, DDG-51 Class, Unit STRL ARR DWG, ASSY Unit 3330
- 2.5 163-6567580 Rev M, DDG51 Class, Location of Sea Connections

3. REQUIREMENTS:

- 3.1 Provide crane and rigging services to assist Navy Divers in waterborne cofferdam installation, as designated by the SUPERVISOR.

(V) (G) "WEIGHT HANDLING EQUIPMENT INSPECTION"

3.1.1 Inspect all rigging gear being utilized and ensure it is certified for use. All rigging equipment shall be within calibration for dates work is to be accomplished. Provide certification and/or calibration records for all rigging gear used on site upon request by the SUPERVISOR.

3.1.2 The crane shall be capable of reaching the top of the mast and the furthest outboard areas of the ship.

3.2 Accomplish a visual inspection with the SUPERVISOR, of the location listed in 1.2 for structural integrity, deterioration, pitting, each crack, and area of damage or distortion as designated by the SUPERVISOR.

3.3 Remove, dispose and clean of each used and excess hazardous material, liquid, and sludge from the area of repair listed in 1.2.

3.4 Remove existing (One EA) temporary polysulfide repair in the location listed in 1.2.

(I) (G) "MAGNETIC PARTICLE INSPECTION"

3.4.1 Accomplish the requirement of 009-012 of 2.1 Table 2, Line 11, Column A or B, for a magnetic particle inspection on equipment listed

in 1.2 to determine extent of defect as directed by the SUPERVISOR.

3.4.1.1 Submit one legible copy, in English, in hard copy or approved transferrable media, of a report listing results of the requirements of 3.3.1 to the SUPERVISOR

3.4.2 Using the results found in paragraph 3.4.1, accomplish each end point drill stop of the identified defect in accordance with paragraph 100-2.8.5.3.3.b.1 of 2.2, using 2.3 through 2.5 as guidance.

(I) (G) "MAGNETIC PARTICLE INSPECTION"

3.4.3 Accomplish the requirement of 009-012 of 2.1, Table 2, Line 11, Column A or B, for a magnetic particle inspection on equipment listed in 1.2 to ensure proper end point drilling of the defect as directed by the SUPERVISOR.

3.4.3.1 Submit one legible copy, in English, in hard copy or approved transferrable media, of a report listing results of the requirements of 3.3.3 to the SUPERVISOR

3.4.4 Install (One EA) polysulfide temporary patch, using a steel plate with rubber to ensure proper installation, in accordance with paragraph 100-2.8.5.3 of 2.2.

3.4.4.1 During the curing process, apply pressure to the plate to ensure proper sealing.

(V) (G) "COMPARTMENT CLOSEOUT"

3.5 Accomplish a joint inspection with the SUPERVISOR and the Commanding Officer's designated representative upon completion, inspection, and acceptance, by the contractor, of work within each compartment. Ensure Attachment A, Work Completion Certification, is completed in accordance with 009 004 of 2.1.

4. NOTES:

4.1 Cofferdam will be installed and verified by Navy Divers to hold properly before work is started.

4.2 Known interference is a 8 inch fire main pipe located above the crack. If removal is required the requirements of 009-023 will apply.

4.3 Rigging services will be required for interference listed in 4.2.

4.4 Cofferdam installation, FWP/PCP generation and approvals, and execution will be accomplished by FDRMC Rota Navy Divers.

5. GOVERNMENT FURNISHED MATERIAL (GFM):

5.1 LLTM:

1. None.

5.2 PUSH MATERIAL:

1. None.

5.3 KITTED MATERIAL:

SHIP: USS OSCAR AUSTIN (DDG 79)

1. None.

SHIP: USS OSCAR AUSTIN (DDG 79) ITEM NO: 256-61-001
COAR: 26 PCN: EM01-5949
CMP: NONE
PLANNER: JONES, DOUGLAS
ARELLANES-VIDRIO,
ANGEL

1. SCOPE:

- 1.1 Title: Seawater Service Butterfly Valve SW-V-213; replace
- 1.2 Location of Work:
 - 1.2.1 Engine Room No. One (4-174-0-E)
- 1.3 Identification:
 - 1.3.1 Quantity (One EA), Butterfly Valve, 10 Inch, 150 PSI, Valve No: SW-V-213/SWC/V0073, Mfr: MCC Holdings, Mfr ID: 10-1WA-5X3XGF-BMG, Service: Seawater Cooling Main Bulkhead Isolation, Shown on Zone 2-D, Sheet 4A5 of 2.2, APL: 882292461

2. REFERENCES:

- 2.1 NAVSEA Standard Items, (FY26 CH-1)
- 2.2 256-6567450 Rev M, Seawater Cooling System Diagram
- 2.3 802-5959353 Rev BT, MIL-STD-777 Modified for DDG-51 Class, Schedule of Piping, Valves, Fittings, and Associated Piping Components for Naval Surface Ships

3. REQUIREMENTS:

- 3.1 Provide crane and rigging services for the equipment identified in 1.3 and located 1.2, as designated by the SUPERVISOR.

(V) (G) "WEIGHT HANDLING EQUIPMENT INSPECTION"

- 3.1.1 Inspect all rigging gear being utilized and ensure it is certified for use. All rigging equipment shall be within calibration for dates work is to be accomplished. Provide certification and/or calibration records for all rigging gear used on site upon request by the SUPERVISOR
- 3.1.2 The crane shall be capable of reaching the top of the mast and the furthest outboard areas of the ship.
- 3.2 Remove existing and install new the valve listed in 1.3 and located in 1.2, in accordance with 2.2.
 - 3.2.1 Align the piping to the valve. Piping must be supported independently and must not impose a strain. Accomplishment of alignment by adjustment of the first adjacent hanger is to be considered within the scope of the work.

(V) (G) "OPERATIONAL TEST"

- 3.3 Accomplish an operational test of the valve listed in 1.3 and located in 1.2, in accordance with 2.2. Allowable leakage: None.
 - 3.3.1 Test each remote valve operator assembly for ease of operation

and proper alignment by opening and closing each valve from its remote operating station through 3 complete cycles. Allowable binding: None.

(V) (G) "COMPARTMENT CLOSEOUT"

3.4 Accomplish a joint inspection with the SUPERVISOR and the Commanding Officer's designated representative upon completion, inspection, and acceptance, by the contractor, of work within each compartment. Ensure Attachment A, Work Completion Certification, is completed in accordance with 009 004 of 2.1.

4. NOTES:

4.1 None.

5. GOVERNMENT FURNISHED MATERIAL (GFM) :

5.1 LLTM:

	TOTAL QUANTITY PROVIDED	NAME Of PART	PIECE NO.	REF NO.	NATIONAL STOCK NO.	REQ PARA NO.
1.	1 EA	Valve, Butterfly 10 Inch		2.2		3.2

5.2 PUSH MATERIAL:

1. None.

5.3 KITTED MATERIAL:

1. None.

SHIP: USS OSCAR AUSTIN (DDG 79) ITEM NO: 508-11-001
COAR: 26 PCN: See Attachment A
CMP: NONE
PLANNER: KRIEGER, DANIEL
ARELLANES-VIDRIO,
ANGEL
JONES, DOUGLAS

1. SCOPE:

1.1 Title: Lagging and Insulation; replace

1.2 Location of Work:

1.2.1 Registered Publications Office, (1-110-3-Q)

1.2.2 Passage Way, Port Side, (2-410-0-L)

1.2.3 Passage Way, Center Line, (2-410-0-L)

1.2.4 Passage Way, Starboard, (2-410-0-L)

1.2.5 Crew Living Space Number 5, Head (3-310-2-L)

1.2.6 Sonar Access Trunk (5-28-0-T)

1.2.7 Fan Room (01-338-4-Q)

1.2.8 CPO Living Space (2-347-1-L)

1.2.9 Athletic Gear Storeroom (4-430-1-A)

1.2.10 Engine Room Number 2 (4-254-0-E)

1.3 Identification:

1.3.1 Quantity (9 Linear Feet), Pipe Insulation, Located in 1.2.1.

1.3.2 Quantity (150 SQFT), Ventilation Insulation, Located in 1.2.2.

1.3.3 Quantity (54 Linear Ft), Fire Main Pipe Insulation, Located in 1.2.2.

1.3.4 Quantity (54 Linear Ft), Chill Water Pipe Insulation, Located in 1.2.2.

1.3.5 Quantity (90 SQFT), Ventilation Insulation, Located in 1.2.3.

1.3.6 Quantity (10 Linear Ft), Hot Potable Water Pipe Insulation, Located in 1.2.3.

1.3.7 Quantity (25 Linear Ft), Fire Main Pipe Insulation, Located in 1.2.3.

1.3.8 Quantity (40 Linear Ft), Fire Main Pipe Insulation, Located in 1.2.4.

1.3.9 Quantity (144 SQFT), Ventilation Insulation, Located in 1.2.4.

1.3.10 Quantity (3 Linear Ft), Potable Water Pipe Insulation, Located in 1.2.5.

1.3.11 Quantity (90 SQFT), Bulkhead Insulation, Located in 1.2.6

1.3.12 Quantity (12 SQFT), Bulkhead Insulation, Located in 1.2.7

1.3.13 Quantity (11 SQFT), Bulkhead Insulation, Located in 1.2.8

1.3.14 Quantity (12 Linear Ft), Fire Main Pipe Insulation, Located in 1.2.9.

1.3.15 Quantity (2 SQFT), GTG Pipe Insulation, Located in 1.2.10.

2. REFERENCES:

2.1 NAVSEA Standard Items, (FY26 CH-1)

2.2 801-7027785 Rev K, DDG51 Class Booklet of General Plans

2.3 MIL-STD-769K CH-1, Insulation Requirements for U.S. Naval Vessels

3. REQUIREMENTS:

3.1 Record and document any compartment designations, equipment labeling, and system markings affected by the accomplishment of this work specification.

3.1.1 Remove and dispose existing, and install new the equipment listed in 1.3, located in 1.2, using 2.2 and 2.3 as guidance, and as designated by the SUPERVISOR.

3.1.2 Accomplish the requirements of 009-011 of 2.1 for the installation of new insulation and lagging removed in 3.1.1 using 2.2 and 2.3 as guidance.

(V) (G) "COMPARTMENT CLOSEOUT INSPECTION"

3.2 Accomplish a joint inspection with the SUPERVISOR and the Commanding Officer's designated representative upon completion, inspection, and acceptance, by the contractor, of work within each compartment. Ensure Attachment A, Work Completion Certification, is completed in accordance with 009 004 of 2.1.

4. NOTES:

4.1 Ships Force will accomplish the painting of new insulation installed 3.1.2; new insulation, lagging, and reusable covers are to match surrounding areas.

5. GOVERNMENT FURNISHED MATERIAL (GFM):

5.1 LLTM:

1. None.

5.2 PUSH MATERIAL:

1. None.

5.3 KITTED MATERIAL:

1. None.

Attachment A
PCN Identification

OD01-3548	3-300-2-L MISSING LAGGING
EM02-3758	STO LAGGING
CG03-2354	MISSING LAGGING
CA01-3826	LAGGING REPLACEMENT
CF03-1641	ATHLETIC GEAR STRM FM PIPE
ER04-3281	DEGRADED LAGGING
CC01-4210	PIPE LAGGING IN THE VAULT
SS02-4440	DEGRADED LAGGING

SHIP: USS OSCAR AUSTIN (DDG 79) ITEM NO: 521-21-001
COAR: 26 PCN: EE02-L034
CMP: NONE
PLANNER: KRIEGER, DANIEL
ARELLANES-VIDRIO,
ANGEL
JONES, DOUGLAS
STAPLES,
MICHAEL.FDRMC

1. SCOPE:

- 1.1 Title: No. 2 Fire Pump Motor; replace
- 1.2 Location of Work:
 - 1.2.1 Auxiliary Machinery Room Number One (4-126-0-E)
- 1.3 Identification:
 - 1.3.1 Quantity (One AY), No. 2 Fire Pump, Close Coupled, Mfr Id: Navy STD Titanium
 - 1.3.1.1 Quantity (One EA), Fire Pump, Mfr: Various, Mfr Dwg: 5773203-24, Mfr ID: Navy Std Titanium Fire Pump, APL 018880296
 - 1.3.1.2 Quantity (One EA), Motor, Mfr: Reliance Electric, MFR P/N 801642-504, APL 174756504

2. REFERENCES:

- 2.1 NAVSEA Standard Items, (FY26 CH-1)
- 2.2 S6225-W6-MMA-010 Rev 8, Navy Standard, Titanium Centrifugal Pump, 1000 GPM (NAVSEA Drawing No. 803-5773203)
- 2.3 802-5959353 Rev BT, MIL-STD-777D Modified for DDG-51 Class, Schedule of Piping, Valves, Fittings, and Associated Piping Components
- 2.4 4C521C100 Rev B, Firemain System Operational Test
- 2.5 521-6567421 Rev U, Firemain System Diagram

3. REQUIREMENTS:

- 3.1 Provide a crane and rigging services for the equipment identified in 1.3.1.2, located in 1.2, as designated by the SUPERVISOR.

(V) (G) "WEIGHT HANDLING EQUIPMENT INSPECTION"

- 3.1.1 Inspect all rigging gear being utilized and ensure it is certified for use. All rigging equipment shall be within calibration for dates work is to be accomplished. Provide certification and/or calibration records for all rigging gear used on site upon request by the SUPERVISOR.
- 3.1.2 The crane shall be capable of reaching the top of the mast and the furthest outboard areas of the ship.
- 3.2 Remove existing and install new the equipment listed in 1.3.1.2 in accordance with 2.2, using 2.3 through 2.5 as guidance.
 - 3.2.1 Matchmark and retain each shim, coupling, and foundation

hardware for reuse.

3.2.2 Clean each exposed part free of foreign matter, leaving no residue or injurious effect.

3.2.3 Chase and tap each exposed threaded area.

3.2.4 Record electrical disconnection data. Retain for installation.

3.2.5 Restore each mating surface exposed by pump removal. Repair by removing each high spot, burr, abrasion, and foreign matter, where removal can be accomplished by hand tool.

(V) (G) "TORQUE VERIFICATION"

3.2.6 Torque each foundation fastener in accordance with 2.2.

(V) (G) "ALIGNMENT VERIFICATION"

3.2.7 Accomplish alignment of the new equipment listed in 1.3.1.2 to the existing pump in accordance with 2.2.

(V) (G) "OPERATIONAL TEST"

3.2.8 Accomplish an operational test of the equipment listed in 1.3 and located in 1.2, in accordance with 2.4, and using 2.2, 2.3 and 2.5 for guidance. Confirm correct rotation of pump assembly. Allowable unusual noise and vibration: None.

(V) (G) "COMPARTMENT CLOSEOUT"

3.3 Accomplish a joint inspection with the SUPERVISOR and the Commanding Officer's designated representative upon completion, inspection, and acceptance, by the contractor, of work within each compartment. Ensure Attachment A, Work Completion Certification, is completed in accordance with 009 004 of 2.1.

4. NOTES:

4.1 None

5. GOVERNMENT FURNISHED MATERIAL (GFM) :

5.1 LLTM:

	TOTAL QUANTITY PROVIDED	NAME Of PART	PIECE NO.	REF NO.	NATIONAL STOCK NO.	REQ PARA NO.
1.	1 EA	Motor		2.2		3.2

5.2 PUSH MATERIAL:

1. None.

5.3 KITTED MATERIAL:

1. None.

SHIP: USS OSCAR AUSTIN (DDG 79) ITEM NO: 555-11-001
COAR: 26 PCN: ER04-3290
CMP: NONE
PLANNER: KRIEGER, DANIEL
ARELLANES-VIDRIO,
ANGEL
JONES, DOUGLAS
STAPLES,
MICHAEL.FDRMC

1. SCOPE:

1.1 Title: AFFF System Hyccheck Valve; replace

1.2 Location of Work:

1.2.1 AFFF Station Number One (1-70-1-A)

1.3 Identification:

1.3.1 Quantity: (One EA), Valve, Diaphragm Control Pilot Operated, 6.00 Inch IPS, 250 PSI, Bronze Body; Mfr.: Griswold Industries Company, Costa Mesa CA; Mfr. ID 25147-03E; Valve Designation Number: AFFF-V-1, Serial No.: 1-77-11, APL: 882192615

2. REFERENCES:

2.1 NAVSEA Standard Items, (FY26 CH-1)

2.2 555-6567409 Rev J, Aqueous Film Forming Foam (AFFF) System Diagram

2.3 801-7027785 Rev K, DDG51 Class Booklet of General Plans

3. REQUIREMENTS:

3.1 Provide crane and rigging services for the equipment identified in 1.3.1, located 1.2.

(V) (G) "WEIGHT HANDLING EQUIPMENT INSPECTION"

3.1.1 Inspect all rigging gear being utilized and ensure it is certified for use. All rigging equipment shall be within calibration for dates work is to be accomplished. Provide certification and/or calibration records for all rigging gear used on site upon request by the SUPERVISOR

3.1.2 The crane shall be capable of reaching the top of the mast and the furthest outboard areas of the ship.

3.2 Remove existing and install new the material identified in 1.3 in location listed in 1.2 using 2.2 and 2.3 as guidance.

3.2.1 Restore piping flange mating surfaces exposed by removals. Repair by removing high spots, burrs, abrasions, and foreign matter, where removal can be accomplished by hand tools. Take precautions to maintain phonographic finish on flanges that have it.

3.2.2 Chase and tap exposed threaded areas.

(V) (G) "OPERATIONAL TEST"

3.3 Accomplish an operational test of the new valve at system operating

conditions. Allowable external leakage: none.

(V) (G) "COMPARTMENT CLOSEOUT"

3.4 Accomplish a joint inspection with the SUPERVISOR and the Commanding Officer's designated representative upon completion, inspection, and acceptance, by the contractor, of work within each compartment. Ensure Attachment A, Work Completion Certification, is completed in accordance with 009 004 of 2.1.

4. NOTES:

4.1 None

5. GOVERNMENT FURNISHED MATERIAL (GFM):

5.1 LLTM:

	TOTAL QUANTITY PROVIDED	NAME Of PART	PIECE NO.	REF NO.	NATIONAL STOCK NO.	REQ PARA NO.
1.	1 EA	AFFF Valve	Hycheck	2.2		3.2

5.2 PUSH MATERIAL:

1. None.

5.3 KITTED MATERIAL:

1. None.