

RFI Responses

1. Is this project tax exempt? If so, will the government provide a tax exempt form to the awarded contractor so that they may provide it to their subcontractors? **This should be coordinated with your Contracting Officer or Contract Specialist. Construction contracts are not sales tax exempt.-CS**
2. Due to the extensive underground utilities and the need for Contractors to bid the same scope requirements, is the GOV requiring all Contractors to excavate by hydrovac instead of traditional excavator? **Hydrovac is required. -DBS**
3. Drawing E-102, Keynote 1, states to weld each joint. Are you wanting this conduit installed underground with each joint welded? **Only the conduits under generator and generator pad. MBT**
4. Drawing E-101, note 1 says to install new 200amp disconnect and Drawing E-501, note 1 says to install 100amp disconnect. What size disconnect needs to be installed in the B821 Trailer area? **200amp disconnect. The drawings have been updated to reflect this. -MT**
5. In order for Contractors to bid the same scope requirement, is the GOV allowing Contractors to saw cut and excavate across the drive for the new conduits then patch back, or are Contractors required to bore under the drive to install the conduits? There is a significant cost difference between boring and trenching across the drive. **Bore under the drive to install the conduits. MBT**
6. Please confirm that there is no design requirements on this project. **Correct. -DBS**
7. The SOW, paragraph 2.8, states that there is ACM and LBP present. Please provide a hazardous materials survey that shows the location and quantities so Contractors can accurately bid this scope. If a survey is not available, please identify an assumed quantity and location that all Contractors can bid so the abatement requirements is equal among all Contractors. **The SOW only indicates the contractor should ASSUME there are ACM/LBP during construction. Neither have been positively identified and are not anticipated. -DBS**
8. The GOV has provided drawings and SOW for Contractors to bid. Will the GOV provide specifications as well? If not, what is the governing document that takes precedence for directing the scope of work: The Drawings or the SOW? **The Tinker Specs are provided on your Contractor CD. SOW paragraph 4.1.2 clearly states the order of precedence. -DBS All documents from the Contractor CD are included as attachments to the solicitation. CS**
9. Phones were not allowed to be taken into the jobsite area (behind the secure fence). Once awarded, will Contractor personnel be able to have company cell phones on them while supervising work? **Phones were and are allowed outside of B820. No photos are allowed. -DBS**  
The SOW, paragraph 9.0, Attachments, stated there were five (5) attached documents provided on  
10.  
a CD. We have not been given a CD, and none of these documents are posted on Sam.GOV. Will the GOV post these documents on Sam.GOV so Contractors can review? **Contracting provides the Contractor CD. -DBS All documents from the Contractor CD are included as attachments to the solicitation. CS**

RFI Responses

11. Please confirm this award is set-aside to a SBA-certified WOSB firm. ~~This question should be directed to your Contracting Officer or Contract Specialist.-DBS~~ This is a SBA- certified WOSB set-aside. CS
12. Please provide Section L and Section M that identifies the submission criteria and evaluation criteria for proposals. ~~This should be coordinated with your Contracting Officer or Contract Specialist.-DBS~~ Sections L and M are included in the solicitation document. CS
13. Will a bid bond be required to submit with Contractor's proposals? ~~This should be coordinated with your Contracting Officer or Contract Specialist.-DBS~~ Yes, a bid bond will be required. CS
14. The submittal register includes submittals from specification sections that Contractors have not been given. Please confirm that these submittals are not required, or please provide the specifications for review with sufficient time to submit any required RFIs if needed after reviewing the specifications. ~~Tinker specifications are provided by Contracting on your Contractor CD.-DBS~~ Included in solicitation. CS
15. The submittal register includes significant number of submittals for 03 30 00 that have significant cost impacts. However, without the specification to review, we can't specifically confirm these requirements just from the submittal register. We ask for an RFI period after the specifications have been provided so Contractors can review the specs completely, and if needed, can submit additional RFIs after the specs were provided. ~~Only your Contracting Officer or Contract Specialist can make that determination. The specifications are provided on your Contractor CD.-DBS~~ Included in solicitation. CS
16. Drawing S-501, Detail 4, is the slab opening a "framed opening" with steel edges/lintels, or simply an opening with concrete edges finished similar to the slab? It is an opening with no steel edges, finish to match slab. -LL
17. The structural drawings indicate enclosure posts, base plates, and anchors provided by others. Please confirm those are all installed by others after our contract is complete. Equipment anchors will be installed with post-installed anchors by generator installers. -LL
18. Please confirm that the 100-gal diesel fuel tank associated with the generator that will be removed, will be emptied of fuel by the GOV prior to Contractor demolishing/removing these items. Yes it will be emptied by the government. MBT
19. Due to the size of the day tank and the location above ground, please confirm that there is no requirement to coordinate closure report with OCC for the 100-gal diesel fuel tank. The OCC coordination will not be required. MBT
20. Drawing E-501, shows a new concrete pad being provided under the new disconnect. There is no detail on how this concrete pad is to be constructed. Please provide a detail, to include size, thickness, reinforcement, etc., and whether or not the new pad is to be dowelled into the adjacent/existing pad. Use thickness and reinforcing on keyed note #1/S-101 & detail 7/S-501. Dowel and epoxy into existing with #3x18" at 12" oc.-LL

Solicitation FA813726R0014

WWYK240148-Install Electrical from FAB-T and OPCON, B820 & B829

RFI Responses

HO.PETER.HA  
O.1123729591



Digitally signed by  
HO.PETER.HAO.1123729591  
Date: 2026.04.14 12:42:47  
-05'00'