

PERFORMANCE WORK STATEMENT

Outdoor Static Model Display

7 May 2026

The United States Air Force, Wright Patterson Air Force Base, has a need for non-personal services to refurbish six (6) outdoor static display models residing outside of Buildings 553 and 556. See Display Photographs detailed in Exhibit I.

1. **BACKGROUND:** The Air Force Base maintains small-scale static display models (commonly referred to as “plastic” or “replica” aircraft) constructed of fiberglass, foam, composite, or light aluminum for permanent outdoor public display. These assets are exposed to harsh outdoor conditions, leading to accelerated degradation such as fading paint, corrosion, structural weakening, and biofouling. Refurbishment is essential to maintain aesthetic integrity, structural safety, and historical accuracy.
2. **SCOPE:** The Contractor shall provide all necessary supervision, labor, materials, equipment, tools, transportation, and quality control to fully refurbish the cosmetic appearance and protective coatings of outdoor, non-flyable replica aircraft made of fiberglass, composite, aluminum, or a combination thereof. The Contractor shall provide a two (2) year warranty against peeling, cracking, or significant fading
3. **MINIMUM REQUIREMENTS:** At a minimum, the contractor shall meet or exceed all of the following:
 - a. Contractor must be able to show past experience refurbishing outdoor aircraft static display models
 - b. Replace or refurbish any missing components back to original condition
 - i. Steps include:
 1. Surface preparation
 2. Structural Reinforcement
 3. Corrosion Repair
 4. Priming
 5. Painting
 6. Marking Reproduction
 7. Application of long-term weather and UV protection
 - c. Reference the following applicable documents, utilizing the latest versions to maintain significance and integrity.
 - i. AFI 84-101, Aerospace Vehicle Histories, Markings, and Preservation

- ii. Federal Standard 595C, Colors Used in Government Procurement
 - iii. ASTM G154, Accelerated UV Weathering
- d. Conduct initial condition assessment with high-resolution photography and written report identifying
 - i. Cracking
 - ii. Delamination
 - iii. Fading
 - iv. chalking
 - v. Impact damage
 - vi. Bird nesting
- e. Fair to original contour. Repair or replace components that are part of the display or missing.
- f. Reproduce all national insignia, squadron tail codes, tail numbers, and special markings
- g. All personnel shall complete base-specific safety, environmental, and security training.

4. DELIVERABLES:

- a. Before, in-progress, and after digital photo package at 25%, 50%, 75% 100% completion of each model for project presentations and updates to senior leadership.
- b. Condition assessment and repair log Within 30 days of contract award
- c. Paint and material technical data sheets and VOC compliance documentation Within 30 days of project completion

5. PERSONNEL QUALIFICATIONS:

- a. **Project Manager:** Experience in composite repair and high-performance exterior coatings and prior military or commercial aviation composite shop experience preferred.
- b. **Painters:** Experience with two-part military or marine polyurethane systems; experience on outdoor static displays highly desirable.

6. PERFORMANCE:

- a. **Period of Performance:** Contractor shall complete all work by 30 Sep 2026.
- b. **Place of Performance:** Off-site. Contractor workspace (displays will need to be reinstalled after refurbishment).

7. QUALITY CONTROL / ACCEPTANCE: Final acceptance walk-through with COR.
8. WARRANTY: Any defects arising during the two (2) year warranty period due to poor workmanship or materials shall be corrected by the Contractor within 30 days after notification, or within an agreed upon time amongst the parties should more than 30 days be necessary.
9. SECURITY: Contractor personnel shall comply with local force protection and badging requirements.

EXHIBIT I

Display Photographs



-Display 1. B-1 Lancer



Display 2. B-2



-Display 3 – B-52 Stratofortress



-Display 4. F-15 Eagle



Display 5. F-16



Display 6. F-22