

[REDACTED]		
[REDACTED]		
ELECTRICAL		CONTRACT NO. XXXXX-XX-X-XXXX
ITEM No. SOR-ASD-26-036	CATEGORY "A"	2024-06-04
VAC Valve automation repairs		PPE

1.0 ABSTRACT:

1.1 This work item describes the requirements for inspection, excursing, and testing of valve actuators.

2.0 REFERENCES:

2.1 MSC Drawing 801-8387023; Docking Plan.

2.2 T/M T6435-CN-MMC-010; T-AKE Motor Operated Valves with Actuators.

3.0 ITEM LOCATION/DESCRIPTION:

3.1 Location/Quantity:

3.1.1 Location:

a. Various, see Sea Valves Table on Sheet 5 of reference 2.1 (for guidance only)

3.1.2 Quantity:

a. Refer to Reference 2.1.

3.2 Item Description/Manufacturer's Data: None additional.

3.3 Place and Period of Performance:

3.3.1 Ship will be available from [REDACTED] and groom may tak [REDACTED] at [REDACTED]

3.3.2 Location will be [REDACTED].

4.0 GOVERNMENT-FURNISHED EQUIPMENT/MATERIAL/SERVICES:

4.1 Government Furnished Equipment:

[REDACTED] FM valves w/actuators - TWENTY-SIX (26) Valves with actuators

Number	Tag Numbers	Valve Part Number	Actuator Part Number	Actuator Job Number
1	FM COV 5-64-2	16JG57Z31X	R7Q6-3C	83623V
3	FM COV 5-64-22	16JG57Z31X	R7Q6-3C	83623V
4	FM COV 5-59-2	16JG57Z31X	R7Q6-3C	83623V
5	FM COV 5-58-8	16JG57Z31X	R7Q6-3C	83623V
6	FM COV 5-48-10	16JG57Z31X	R7Q6-3C	83623V
7	FM COV 5-39-4	16JG57Z31X	R7Q6-3C	83623V
8	FM COV 2-39.5-1	16JG57Z31X	R7Q6-3C	83623V
9	FM COV 2-48-5	16JG57Z31X	R7Q6-3C	83623V
10	FM COV 2-57-7	16JG57Z31X	R7Q6-3C	83623V
11	FM COV 2-64-1	16JG57Z31X	R7Q6-3C	83623V
12	FM COV 2-65-1	14JG57Z31X	Q5N2-3C	83623T
13	FM COV 5-65-16	14JG57Z31X	Q5N2-3C	83623T

ELECTRICAL		CONTRACT NO. XXXXX-XX-X-XXXX	
ITEM No. SOR-ASD-26-036	CATEGORY "A"	2024-06-04	
VAC Valve automation repairs		PPE	

15	FM COV 2-41-2	04JG57Z31X	P2N1-3C	83623D
22	FM COV 5-64-4	10JG57Z31X	Q4N2-3C	83624P
23	FM COV 5-64-8	10JG57Z31X	Q4N2-3C	83623P
24	FM COV 5-64-12	10JG57Z31X	Q4N2-3C	83623P
25	FM COV 5-64-16	10JG57Z31X	Q4N2-3C	83624P
28	FM COV 5-61-4	04KG57731X	P2N1-3C	83624N
29	FM COV 5-36-2	08BG07Z31X	Q4N2-3C	83624M
30	FM COV 4-75-2	08BG07Z31X	Q4N2-3C	83624M
31	FM COV 5-39-3	06JG57Z31X	Q4N2-3C	83623G
32	FM COV 4-75-8	06JG57Z31X	Q4N2-3C	83623G
37	FM COV 1-65-1	08JG57731X	Q4N2-3C	83623K
44	FM COV 5-65-3	24BG67731X	MDN1-3C	83624F
045/345	FM COV 5-65-18	24BG67731X	2JSG-3C	83632A
966	FM COV 2-66-5	14JG57Z31X	Q5N2-3C	118537A

4.2 Government Furnished Material: NONE

4.3 Government Furnished Services: None.

5.0 NOTES:

5.1 The Contractor and all Subcontractors, regardless of tier must consult the General Technical Requirements (GTR) to determine applicability to this work item. In performance of this work item, the Contractor and all Subcontractors regardless of tier must comply with the requirements of all applicable GTR's.

5.2 The Contractor and all Subcontractors, regardless of tier are advised to review other work items under this contract to determine their effect on the work required under this work item. Many of the definitions relating to performance of this work item are found in Work Item 001.

5.3 This ship contains High Voltage (HV) electrical systems. The Contractor and Subcontractors shall obey all posted and verbal instructions regarding safety and exclusion from High Voltage areas. At no time shall a Contractor or Subcontractor approach, work on, or enter a High Voltage area without proper authorization.

5.4 THE T-AKE CLASS ELECTRICAL COLOR CODING DOES NOT FOLLOW CONSISTENT COLOR SCHEME. THE SHIP IS KNOWN TO HAVE CURRENT CARRYING CONDUCTORS COLORED GREEN, BLUE, BLACK AND WHITE. THE CONTRACTOR SHALL ASSUME ALL ELECTRICAL CABLES ARE HOT UNTIL TESTED OTHERWISE. THE CONTRACTOR SHALL TEST ALL ELECTRICAL CABLES TO ENSURE THEY ARE DEAD PRIOR TO WORK ON THE ITEM.

[REDACTED]		
ELECTRICAL		CONTRACT NO. XXXXX-XX-X-XXXX
ITEM No. SOR-ASD-26-036	CATEGORY "A"	2024-06-04
VAC Valve automation repairs		PPE

6.0 QUALITY ASSURANCE REQUIREMENTS: None Additional.

7.0 STATEMENT OF WORK REQUIRED:

7.1 Prior to Any work: a written plan of the Day (POD) is to be submitted. Report to highlight all valves to be exercised/worked/tested.

7.1.1 Three Hardcopies copies are to be supplied daily. ONE (1) to the onsite Port engineer, ONE (1) to Chief Engineer, and ONE (1) to ships master.

7.1.2 One electronic copy to submitted up to 24 hours prior to commencement of work. POD to be submitted via email to Port engineer.

7.2 Exercise ALL actuators, both locally and remotely. Provide a report to the MSCREP detailing conditions found and recommendations.

7.2.1 The following valves have Motor Operators:

FM COV 5-36-2	Butterfly
FM COV 5-61-4	Butterfly
FM V 5-65-3	Butterfly
FM V 5-65-18	Butterfly
FM V 4-75-2	Butterfly
DB-V-02	Butterfly
SW-V-1	Butterfly
SW-V-4	Butterfly
SW-V-33	Butterfly
SW-V-41	Butterfly
MD-V-24	Butterfly
BW-V-07	Butterfly
SW-V-241	Butterfly

7.2.2 The following valves have reach rods:

OW-V-128	Globe Stop Check
MD-V-37	Globe Stop Check
MD-V-86	Globe Stop Check
TV-V-37	Gate
TV-V-39	Gate
TV-V-41	Gate
TV-V-43	Gate
RO-V-28	Gate
WD-V-120	Swing Check W/ Closing Device
WD-V-123	Swing Check W/ Closing Device
DD-V-12	Swing Check W/ Closing Device

ELECTRICAL		CONTRACT NO. XXXXX-XX-X-XXXX
ITEM No. SOR-ASD-26-036	CATEGORY "A"	2024-06-04
VAC Valve automation repairs		PPE

CH-V-52 Swing Check W/ Closing Device

7.2.3 The following valves have Pneumatic Actuators:

FM-V-4-75-12	Ball Valve
FM-V-5-36-4	Ball Valve
SW-V-52	Ball Valve
SW-V-54	Ball Valve
SW-V-57	Ball Valve
SW-V-59	Ball Valve

7.3 Exercise and free up all valve reach rods. Grease all joints and gear boxes. Replace all missing or deteriorated pins. For bidding purposes assume 24 pins will require renewal. Grease to be provided by Chief engineer.

7.3.1 Operational Test: in the presents of Chief Engineer and Port engineer. Perform an operational test of MOV butterfly valves and reach rod operated valves in the central seawater system, ballast system, and fire main system to ensure the motor operator correctly and the valve seats correctly. OEM in section 7.2.3. to be present.

7.4 Test all FM valves with actuators identified above in Government Furnished Equipment (GFE) Section 4.1

7.4.1 Ships force to electrically disconnect and Rig Valve actuator off valve stem for OEM to inspection. Inspection to include Valve stem and Key. OEM to supervise and set valve actuator correctly on re-installation of actuator. Actuators specifically requiring Rigging assistance are:

- a. FM COV-2-39.5-1
- b. FM COV-5-48-4
- c. FM COV-5-58-2
- d. FM COV-5-59-2
- e. FM COV-5-64-2
- f. FM COV-5-64-22

7.4.2 Verify valve actuators open and closed with valves showing the same.

7.4.3 Verify communications with the Master Loop Panels in MCCS.

[REDACTED]		
[REDACTED]		
ELECTRICAL		CONTRACT NO. XXXXX-XX-X-XXXX
ITEM No. SOR-ASD-26-036	CATEGORY "A"	2024-06-04
VAC Valve automation repairs		PPE

7.5 Valve automation and controls OEM to assist with setting MOVs and ensuring the valve network is operational correctly.

7.6 Using References 2.3 Provide all material to Correct discrepancy's noted in report. OEM to Repair all discrepancy's identified in Ref 2.3.

[REDACTED]

[REDACTED]

[REDACTED]

7.8 Reports

7.8.1 When inspection, service and testing reveal any deficiency a condition report is to be submitted to the MSCREP with recommended repairs and parts required. Submit one (1) electronic copy in Portable Document Format (PDF) via condition found report.

7.8.2 Provide a final detailed condition report detailing at a minimum, as found conditions, work accomplished, parts replaced, measurements, recorded data, adjustments performed, testing procedures, any new recommendations to the MSCREP, and as released condition. Submit one (1) electronic copy in Portable Document Format (PDF) via condition found report.

7.9 All reports and checklists are to be completed and signed by the person who carried out the inspection and maintenance work and countersigned by the Company's representative.

8.0 GENERAL REQUIREMENTS: None Additional.