



USCGC ACTIVE (WMEC 618)
SPECIFICATION FOR DOCKSIDE REPAIRS
FY2026

Developed By: Courtney K Brewbaker

(Rev-0, 13 February 2025)

TABLE OF CONTENTS

Revisions Record.....	iii
Consolidated List of References.....	iv
Consolidated List of Government-furnished Property	ix
Consolidated List of Critical Inspection Items.....	xi
Principal Characteristics	xii
General Requirements	1
WORK ITEM 1: Seawater Heat Exchangers, Clean, Inspect And Hydro	13
WORK ITEM 2: Boiler Exhaust Stack Uptakes, Commercial Clean	17
WORK ITEM 3: Chill Water System, Clean and Flush.....	20
WORK ITEM 4: Boilers, Renew	24
WORK ITEM 5: Potable Water Pneumatic Tanks, Clean and Inspect	29
WORK ITEM 6: Hot Water Accumulator Tanks, Clean and Inspect	32
WORK ITEM 7: Steering Gear, General, Overhaul	36
WORK ITEM 8: Single Point Davit, Inspect and Service	43
WORK ITEM 9: Sewage Discharge and Vacuum Pumps, Renew	50
WORK ITEM 10: Grey Water Holding Tanks, Clean and Inspect	53
WORK ITEM 11: Sewage Piping, Clean and Flush	56
WORK ITEM 12: Grey Water Piping, Clean and Flush.....	60
WORK ITEM 13: Tanks, Grey Water Holding, Preserve, Partial – OPTION ITEM	64
WORK ITEM 14: Temporary Services, Heating and Cooling – OPTION ITEM	67
WORK ITEM 15: Whistle Timer, Replace	69
WORK ITEM 16: Fan Room Decks, Preserve.....	72
WORK ITEM 17: Deck and Bulkhead Plating, Renew	74
WORK ITEM 18: Steam System Valves and Piping, Renew	79
WORK ITEM 19: Countermeasure Washdown Piping, Renew	83
WORK ITEM 20: Engine Flywheel Disc Coupling, Renew.....	86
WORK ITEM 21: Deck Covering, Interior, Wet, Renew	90
WORK ITEM 22: Deck Drain Piping, Renew	94
WORK ITEM 23: Compartment(s), Interior, Lead Dust, Clean	97
WORK ITEM 24: Ventilation Systems, Clean and Overhaul.....	102
WORK ITEM 25: Watertight Door, External, Renew	105

REVISIONS RECORD

This page is used to record specification revisions, which may have occurred subsequent to a Revision 0 (Rev-0) package. Information listed is intended to provide contractors and field unit personnel a means to ensure all the current specification revision pages are present when reviewing or utilizing this specification package.

DATE	REV#	WORK ITEM#	CHANGES MADE

NOTE : All work item and paragraph numbers listed above for a given revision correspond to same numbers in the previous revision. This revised specification is self-contained with all of the above listed changes incorporated.

CONSOLIDATED LIST OF REFERENCES

The below-listed documents form a part of this specification to the extent specified herein. Approval/publication dates or revision dates/numbers are also identified, to ensure that same document versions are used at the time of specification writing and during contract execution.

All Coast Guard drawings, technical publications, and standard specifications will be provided to contractors by the Coast Guard at an appropriate time, or upon request, free of charge. Other Government documents may be accessed – free of charge – from links located on the SFLC website. Commercial sites provide access to their respective documents.

COAST GUARD DRAWINGS

Coast Guard Bill of Materials 618 WMEC 8, Rev K, Arr Fireman, Sprink & Washdn Mn Dk & Abv
 Coast Guard Bill of Materials 618 WMEC 11, Rev J, 3rd Dk, 2nd Dk, Main Dk, 02 Dk & Bridge Dk Plt'g & Supports
 Coast Guard Bill of Materials 618 WMEC 61, Rev K, Arr. Stm., Feed & Conds. Sys. Piping
 Coast Guard Bill of Materials 618 WMEC 88, Rev L, Arr of Plumbing Sys & Deck Drains
 Coast Guard Bill of Materials 618 WMEC 97, Rev M, Arr - Aviation Fuel Sys
 Coast Guard Bill of Materials 618 WMEC 327, Rev G, Watertight Doors, Hatches & Scuttles
 Coast Guard Drawing 618 WMEC 85-181, Rev G, Booklet of General Plans
 Coast Guard Drawing 618 WMEC 111-001, Rev G, Shell Expansion Framing & CVK
 Coast Guard Drawing 618 WMEC 120-002, Rev E, Misc Bhds Main Deck
 Coast Guard Drawing 618 WMEC 131-001, Rev M, 2nd & Main Deck Plating & Supports
 Coast Guard Drawing 618 WMEC 136-001, Rev M, 01, 02 & Bridge Deck Plating & Supports
 Coast Guard Drawing 618 WMEC 167-001, Rev M, Schedule of Steel Doors, Hatches, Scuttles & Manholes
 Coast Guard Drawing 618 WMEC 182-002, Rev W, Foundations in Engine Room
 Coast Guard Drawing 618 WMEC 186-002, Rev A, Talon Grid Fdn & Structural Mod 01 Level
 Coast Guard Drawing 618 WMEC 191-001, Rev U, Solid Ballast Arrangement
 Coast Guard Drawing 618 WMEC 201-001, Rev F, Arrangement of Machinery Plans, Sections & Elevations (ACTIVE)
 Coast Guard Drawing 618 WMEC 241-050, Rev F, Lufkin HSQ2724 Marine Gear Plan, Installation – Output & Side Views
 Coast Guard Drawing 618 WMEC 243-052, Rev -, Sectional Assembly Special No. 750 ST Coupling
 Coast Guard Drawing 618 WMEC 259-001, Rev F, Exhaust Piping Arrangement
 Coast Guard Drawing 618 WMEC 314-001, Rev J, Helo 400 Hz & 28.5 VDC Replacement Diagram
 Coast Guard Drawing 618 WMEC 320-001, Rev BD, Major Maintenance Availability 440 & 115 Power One Line Wiring Diagram and Details
 Coast Guard Drawing 618 WMEC 401-001, Rev AP, I.C. & Gyro Room General Arrangement
 Coast Guard Drawing 618 WMEC 401-004, Rev BC, Pilothouse Arrangement
 Coast Guard Drawing 618 WMEC 437-002, Rev D, Windspeed & Direction Ind Sys Elem Wrg Diag IC Ckt "HD&HE"

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

Coast Guard Drawing 618 WMEC 443-001, Rev C, Elementary Wiring Diagram Whistle Control System CKT "W"

Coast Guard Drawing 618 WMEC 443-006, Rev A, Whistle Control System Install/Removal Wiring Diagram

Coast Guard Drawing 618 WMEC 492-002, Rev C, Helicopter Visual Landing Aids Wrg Data

Coast Guard Drawing 618 WMEC 512-001, Rev D, Ventilation Equipment List

Coast Guard Drawing 618 WMEC 512-007, Rev D, Ventilation Diagram Main Deck

Coast Guard Drawing 618 WMEC 512-011, Rev J, Arrangement Ventilation & Air Conditioning Main Deck

Coast Guard Drawing 618 WMEC 514-001, Rev G, Diagram: Heating and Chilled Water System

Coast Guard Drawing 618 WMEC 514-002, Rev G, Arrgt of Chilled & Hot Water System Inside MS

Coast Guard Drawing 618 WMEC 514-003, Rev L, Arrgt of Chilled & Hot Water System Outside of MS

Coast Guard Drawing 618 WMEC 514-004, Rev G; Htg, Vent & A/C Cont Blk W/D & Schematic

Coast Guard Drawing 618 WMEC 521-001, Rev H, Diagram Firemain Sprinkling & Washdown

Coast Guard Drawing 618 WMEC 521-002, Rev M, Arr of Firemain, Sprinkling & Washdown System Main Deck & Above

Coast Guard Drawing 618 WMEC 528-001, Rev L, Arr of Plumbing Sys & Deck Drains

Coast Guard Drawing 618 WMEC 528-002, Rev B, Diagram Of Plumbing System & Deck Drains

Coast Guard Drawing 618 WMEC 533-001, Rev P, Diag Hot & Cold Potable Water

Coast Guard Drawing 618 WMEC 535-001, Rev N, Diagram Steam, Feed and Condensate System Piping

Coast Guard Drawing 618 WMEC 535-002, Rev N, Arr Stm Feed & Condensate System Piping

Coast Guard Drawing 618 WMEC 535-004, Rev-, Split Pipe Drain Duct for Boiler Overboard Disch

Coast Guard Drawing 618 WMEC 536-001, Rev M, Diag Sea Water Piping for Mn Engs, Aux & Emer Gens. & A.C. Condensers

Coast Guard Drawing 618 WMEC 536-003, Rev D, Diagram – F.W. for Machinery Cooling

Coast Guard Drawing 618 WMEC 536-005, Rev B, Installation of JW & LO Coolers

Coast Guard Drawing 618 WMEC 536-052, Rev -, Heat Exchanger

Coast Guard Drawing 618 WMEC 542-001, Rev G, Diagram Aviation Fuel System

Coast Guard Drawing 618 WMEC 542-002, Rev J, Arr -Aviation Fuel System

Coast Guard Drawing 618 WMEC 561-051, Rev -, Hydraulic Cylinder 3/4 Bore Vickers No. 45-103300

Coast Guard Drawing 618 WMEC 583-003, Rev E, Boat Davit Hydraulic Circuit

Coast Guard Drawing 618 WMEC 593-001, Rev C, Diagram-MSD System

Coast Guard Drawing 618 WMEC 593-002, Rev F, Arrg't. MSD System

Coast Guard Drawing 618 WMEC 593-050, Rev A, General Arrangement Marine Sanitation Device Compartment

Coast Guard Drawing 618 WMEC 601-001, Rev J, Outboard Profile

Coast Guard Drawing 618 WMEC 601-002, Rev B, Inboard Profile

Coast Guard Drawing 618 WMEC 601-003, Rev K, General Arrangement – Second and Third Decks

Coast Guard Drawing 618 WMEC 601-004, Rev K, General Arrangement – Main & 01 Deck

Coast Guard Drawing 618 WMEC 613-001, Rev B, Main Mast Rigging Arr & Det

Coast Guard Drawing 618 WMEC 634-001, Rev G, Deck Coverings

Coast Guard Drawing 618 WMEC 635-002, Rev J, Sheathing & Insulation

Coast Guard Drawing 618 WMEC 671-003, Rev D, Helicopter Handling Servicing Eqp't Stowage

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

Coast Guard Drawing 618 WMEC 800-002, Rev A, Strg Sys Hyd Mchry & Ppg Installations

COAST GUARD PUBLICATIONS

Coast Guard Commandant Instruction (COMDTINST) M10360.3, Jun 2006, Coatings and Colors Manual

Coast Guard Technical Publication (TP) 2188, Dec 2024, Steam Heating Boiler - Model 5848-14E

Coast Guard Technical Publication (TP) 2697, May 2018, Main Reduction Gear

Coast Guard Technical Publication (TP) 2699, SWBS 245, Feb 2018, Controllable-Pitch Propeller System

Coast Guard Technical Publication (TP) 2703, Nov 2017, Ship Service Diesel Generator Set

Coast Guard Technical Publication (TP) 2754, SWBS 583, August 2013, Hydraulic Power Unit (HPU)

Coast Guard Technical Publication (TP) 2815, Oct 2017, Reduction Gear

Coast Guard Technical Publication (TP) 2817, SWBS 245, Section A, Feb 2018, Controllable Pitch Propeller System

Coast Guard Technical Publication (TP) 2820A, May 2017, Ship Service Diesel Generator

Coast Guard Technical Publication (TP) 3240B, SWBS 583, May 2010, Hydraulic Power Unit – Motor Controller

Coast Guard Technical Publication (TP) 3241A, SWBS 593, June 2011, Vacuum Sewage System

Coast Guard Technical Publication (TP) 3368, Jun 2020, Talon Helicopter Landing Grid - Type 18-22-01 Multiple Class Cutters

Coast Guard Technical Publication (TP) 3485C, SWBS 583, Sept 2013, Single Point Boat Model D5700CT

Coast Guard Technical Publication (TP) 3965, Apr 2020, Air Conditioning System, R-134A – Model 90RMC025-D-6-D005/MS1

Coast Guard Technical Publication (TP) 4034, Aug 2018, SWBS 561, Electro-Hydraulic Steering System & Alarm System Upgrade

Coast Guard Technical Publication (TP) 4039, SWBS 443, Whistle Timer, Models M-522 and M-411, Installation, operation and Maintenance Instructions

Coast Guard Technical Publication (TP) 4647, Apr 2019, FM/ALCO 251 Engine – Operations and Maintenance Manual

Coast Guard Technical Publication (TP) 4648, Main Propulsion Plant (210' WMEC 'A' Class only), SWBS 233, May 2024

Coast Guard Technical Publication (TP) 5453, Main Diesel Engine (MDE) – Clutch Assembly – Model 28VC1000

Coast Guard Technical Publication (TP) 5490, SWBS 565, Apr 2018, Fin Stabilizer System

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022, General Requirements

Surface Forces Logistics Center Standard Specification 0740 (SFLC Std Spec 0740). 2022, Welding and Allied Processes

Surface Forces Logistics Center Standard Specification 3020 (SFLC Std Spec 3020), 2022, Overhaul AC Electrical Motors

Surface Forces Logistics Center Standard Specification 3041 (SFLC Std Spec 3041), 2022, Shipboard Electrical Cable Test

Surface Forces Logistics Center Standard Specification 3042 (SFLC Std Spec 3042), 2022, Shipboard Electrical Cable Removal, Relocation, Splice, Repair, and Installation

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

Surface Forces Logistics Center Standard Specification 5000 (SFLC Std Spec 5000), 2022, Auxiliary Machine Systems

Surface Forces Logistics Center Standard Specification 6310 (SFLC Std Spec 6310), 2022, Requirements for Preservation of Ship Structures

Surface Forces Logistics Center Standard Specification 6341 (SFLC Std Spec 6341), 2022, Install Interior Deck Covering Systems

Surface Forces Logistics Center Standard Specification 8635 (SFLC Std Spec 8635), 2022, Temporary Services

Surface Forces Logistics Center Standard Specification 8636 (SFLC Std Spec 8636), 2022, Temporary Hull Accesses

OTHER REFERENCES

American National Standards Institute/American Water Works Association (ANSI/AWWA) C652, 2019, Disinfection of Water-Storage Facilities

American Society of Mechanical Engineers (ASME) B16.34, 2004, Valves-Flanged, Threaded, and Welding End

ASTM International (ASTM) 6966, 2008, Standard Practice for Collection of Settled Dust Samples Using Wipe Sampling Methods for Subsequent Determination of Metals

ASTM International (ASTM) D1330, 2015, Standard Specification for Rubber Sheet Gaskets

ASTM International (ASTM) F683, 2014, Standard Practice for Selection and Application of Thermal Insulation for Piping and Machinery

ASTM International (ASTM) F992, 2017, Standard Specification for Valve Label Plates

Code of Federal Regulations (CFR) Title 29, Part 1915, Occupational Safety and Health Standards for Shipyard Employment

Commercial Item Description (CID) A-A-59588, 2013, Rubber Silicone

Manufacturers Standardization Society of the Valve and Fittings Industry (MSS) SP-58, 2018, Pipe Hangers and Supports – Materials, Design, Manufacture, Selection, Application and Installation

Manufacturers Standardization Society of the Valve and Fittings Industry (MSS) SP-61, 2003 Edition, Pressure Testing Of Steel Valves

Manufacturers' Standardization Society of the Valve and Fittings Industry (MSS) SP-80, 2008 Edition, Bronze Gate, Globe, Angle and Check Valves

Military Specification MIL-A-22262B, March 1996, Abrasive Blasting Media Ship Hull Blast Cleaning

MIL-G-21164, Jul 2019, Grease, Molybdenum Disulfide, for Low and High Temperatures, NATO Code Number G-353

MIL-PRF-17672E, Oct 2010, Hydraulic Fluid, Petroleum, Inhibited

MIL-STD-419 E, Aug 2017, Cleaning, Protecting, and Testing Piping, Tubing, and Fittings for Hydraulic Power Transmission Equipment

Naval Air Warfare Center (NAVAIR) Drawing 626348, Rev C, Visual Landing Aids Installation WMEC-210 Class Ships

NAVSEA Drawing 167-7379842, Rev A, Procedure & Welding Sequence for Non-Ballistic, Watertight & Airtight Quick Acting or Individually Dogged Personnel Doors

NAVSEA Drawing 804-5773931, Rev A, Acoustic & Thermal Insulation For Compartments Installation Details

NAVSEA Drawing 804-5959214, Rev-, Piping Insulation - Installation Details

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

- The Society for Protective Coatings (SSPC) Surface Preparation Specification No. 1 (SSPC-SP-1), 2015, Solvent Cleaning
- The Society for Protective Coatings (SSPC) Surface Preparation Specification No. 3, (SSPC-SP-3), 2018, Power Tool Cleaning
- The Society for Protective Coatings (SSPC)/NACE International (NACE) 2007, Joint Surface Preparation Standard SSPC-SP 10/NACE No. 2, Near-White Metal Blast Cleaning
- The Society for Protective Coatings (SSPC) Surface Preparation Specification No.11 (SSPC-SP 11), 2012, Power Tool Cleaning to Bare Metal

CONSOLIDATED LIST OF GOVERNMENT-FURNISHED PROPERTY

The following is a list of property, which the Government will furnish. This list supersedes any other material obligations indicated or implied by referenced drawings.

WORK ITEM	MTI	ITEM DESCRIPTION	NSN/PN	QTY	ESTIMATED COST (\$/UNIT)
1	N	MDE JW Seal Kit	NSN: 2930-01-602-8570 PN: 10-1AEW SEAL	2 ea.	1,250.00
1	Y	**JW Cooler	NSN: 2930-01-698-9297	2 ea.	29,490.00
1	N	**JW Cooler Tube Bundle	NSN: 2930-01-541-2516	2 ea.	2,550.00
4	N	Way-Wolff Boiler Model No. 5848-14E	NSN: 4410-01-230-8024	2 ea.	43,682.00
7	N	**Valve, counterbalance, 1000-4000 psi, 30 gpm, 25 psi check	NSN: 4810-01-353-0586	4 ea.	67.33
7	N	**Valve, safety relief	NSN: 4820-01-241-5464 PN: CS06F50	2 ea.	466.33
7	N	**Valve, check, 25 psi, 32 gpm	NSN: 4820-01-627-7022	4 ea.	58.64
7	N	**Float switch, liquid level	NSN: 6680-01-673-5099	2 ea.	425.00
7	N	**Valve, safety relief	NSN: 4820-01-571-9823 PN: RAH101S30	2 ea.	41.70
7	N	**Coupling half, shaft	NSN: 3010-01-675-1842 PN: RC2-0625-156	2 ea.	25.30
7	N	**Coupling half, shaft	NSN: 3010-01-674-9183 PN: RC2-1375-312	2 ea.	25.30
7	N	**Insert, flexible coupling, pump to motor	NSN: 3010-01-674-8153	2 ea.	11.70
7	N	**Pump, rotary Honor series 2D, CW	NSN: 4320-01-673-6806	2 ea.	536.00
8	N	Rope, wire assembly with swage socket	PN: FL-8201-093 Item 1 NSN: 4010-01-602-8365	1 ea.	250.00
8	Y	Hook, release	PN: APR-356-CBH NSN: 4030-01-467-1005	1 ea.	4,340.00
8	Y	**Davit control console	PN: 60576 NSN: 2030-01- 612-7381	1 ea.	44,000.00
9	N	Sewage Discharge Pump	NSN: 4320-01-273-9350	2 ea.	\$4,719.00
9	N	Sewage Vacuum Transfer Pump	NSN: 4320-01-519-3163	2 ea.	\$4,719.00
15	N	Whistle Timer	NSN: 6645-01-564-0569 PN: M-522	1 ea.	\$1,326.00
15	N	Cable, Power, Electrical, Type DSGU-4 ***	NSN: 6145-01-202-2795 PN: M24643/15-02UN	245 ft.	\$325.85
15	N	Cable, Power, Electrical, Type TSGU-4 ***	NSN: 6145-01-201-9498 PN: M24643/16-02UN	125 ft.	\$207.50
15	N	Cable, Power, Electrical, Type FSGU-4 ***	NSN: 6145-01-210-2344 PN: M24643/17-02UN	30 ft.	\$54.30

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

20	N	***Thomas Disc Coupling	NSN: 3010-01-496-7051	1 ea.	
25	N	QAWTD 1-77-2; 26" x 66" Diameter Quick- Acting Watertight Door, Steel, 8- Dog, Left Hinge (including associated coaming)	NSN: 2040-00-542-0201	1 ea.	8,958.71

****New or refurbished equipment that the Government may provide for installation in place of existing equipment.**

*****Government-furnished property, which is to be supplied by either the vessel or the C4IT ServiceCenter**

CONSOLIDATED LIST OF CRITICAL INSPECTION ITEMS

The following is a list of work items, which contain Critical Inspection reports, which the Contractor must complete within the first 25% of the availability contract period (see SFLC Std Spec 0000, paragraph 3.2.6.1.4 (Inspection report particulars)):

Work Item	Title
8	Single Point Davit, Inspect and Service
17	Deck and Bulkhead Plating, Renew

PRINCIPAL CHARACTERISTICS

210' WMEC (A-CLASS)	
PHYSICAL	
Length overall	210' 6"
Length between perpendiculars	200' 0"
Beam molded	34' 0"
Depth molded, main deck amidships	19' 6"
Full load displacement	1,170 long tons
Draft, full load to baseline amidships *Baseline is 9" below keel amidships	12' 0"
Design drag between perpendiculars	1' 6"
Highest projection above baseline *VHF-FM ADF antenna	90' 0"
Shore tie voltage requirements	400A / 440V
Frame spacing	1' 0"
MACHINERY	
Main propulsion	2 ALCO Model 16-251-CE Diesel Engines, 5,000 BHP total
Ship's service generators	2 Caterpillar Model 3406B Diesel-driven SR4, 250 KW each @ 0.8 power factor, 440VAC, 3 phase, 60 cycle
Emergency generator	Caterpillar Model 3306B Diesel-driven SR4, 180 KW @ 0.8 power factor, 440VAC, 3 phase 60 cycle
Number of propellers	2
Propeller diameter	7' 6"
Number of blades, Each	4
Pitch	Controllable
Shaft RPM	300
Shaft diameter	8.25" at exit of hull
Anchor & chain	Two 2,800 lb Navy Stockless Anchors, 7 shots of chain each
TANK CAPACITIES	
Diesel fuel total (95%)	47,140 gal.
Fresh water total (100%)	11,135 gal.
JP-5 fuel total (95%)	4,717 gal.
Lube oil total (95%)	2,331 gal.

General Requirements

1. SCOPE

1.1 Intent. This standard specification invokes general requirements for conducting vessel repairs performed by commercial contractors at a Coast Guard facility for Coast Guard vessels.

1.2 Term interchangeability. The terms 'Contractor', 'CG Yard', 'NAVSTA EVERETT', 'shipyard', 'Base', and 'Coast Guard Industrial' are used interchangeably in this specification. Where the primary service provider is Coast Guard personnel, references to contractor and other noted descriptors within this specification or within drawings, publications, SFLC Standard Specifications or other commercial and military references are deemed the same as prime service provider.

2. REFERENCES

COAST GUARD DRAWINGS

None

COAST GUARD PUBLICATIONS

Coast Guard Commandant Instruction (COMDTINST) M10360.3 (series), Coatings and Color Manual
Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022, General Requirements

Surface Forces Logistics Center Standard Specification 0740 (SFLC Std Spec 0740), 2022, Welding and Allied Processes

Surface Forces Logistics Center Standard Specification 6310 (SFLC Std Spec 6310), 2022, Requirements for Preservation of Ship Structures

OTHER REFERENCES

Code of Federal Regulations (CFR) Title 29, Part 1915, Occupational Safety and Health Standards for Shipyard Employment

3. REQUIREMENTS

3.1 General. The Contractor must conform to all requirements specified in SFLC Std Spec 0000 and in this item, as applicable, during the performance of this availability. The requirements in this WI applies to all work under the scope of this contract, whether explicitly stated in all following work items or not, and to all other work subsequently authorized by changes, modifications, or extensions to the contract.

3.2 Contractor-provided fire watch personnel. The Contractor must provide fire watch personnel and equipment.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.3 Preservation requirements. The Contractor must accomplish all preservation tasks, including touch-ups, in accordance with SFLC Std Spec 6310.

3.3.1 Brand name approval. Ensure that all contractor-furnished coatings are in accordance with SFLC Std Spec 6310, Appendix C (Authorized Coatings for Use on Cutters and Boats).

3.3.2 Coating colors and system color schemes. The Contractor must obtain a written KO authorization to deviate from any coatings required in SFLC Std Spec 6310 Appendix C before work.

3.3.3 In-process quality control measures. The Contractor must abide by all the safety, preservation, and quality control requirements specified in SFLC Std Spec 0000, paragraph 3.2.4.2 (In-process QC measures for “critical-coated surfaces”).

3.3.3.1 Quality control requirements. The Contractor must abide by the following when performing preservation related inspections. The following measurements must be randomly spaced throughout for the purposes of providing a representation of the entire prepared or coated surface.

3.3.3.1.1 Surface profile measurements. One surface profile measurement must be taken for every 200 square feet for the first 1000 square feet; for each additional 500 square feet or less, one profile measurement must be taken. Profile measurements must be taken in accordance with SFLC Std Spec 6310, paragraph 3.1.8.3 (Surface profile measurements). A “measurement” for surface profile is defined as follows:

- ASTM D4417, Method B: One profile measurement is the average (mean) of 10 individual readings.
- ASTM D4417, Method C: One profile measurement is the average (mean) of 2 individual readings.

3.3.3.1.2 Soluble salt conductivity measurements. 5 conductivity measurements must be taken every 1000 square feet. For submerged (immersed) applications conductivity measurements must not exceed 30 microsiemens/cm. For non-submerged (non-immersed) applications conductivity measurements must not exceed 70 microsiemens/cm. If a conductivity check fails, clean the surface in accordance with SFLC Std Spec 6310, paragraph 3.1.8.5 (Soluble salt removal).

3.3.3.1.3 Coating thickness measurements. Three area measurements must be taken for the first 1000 square feet; for each additional 1000 square feet, perform an additional area measurement. A “measurement” for coating thickness is defined as follows:

- SSPC-PA 2 defines an area measurement as 5 separate spot measurements randomly spaced throughout a 100 square foot area.
- SSPC-PA 2 defines a spot measurement as 3 gage readings and each new gage reading the probe must be moved to a new location within a 1.5-inch diameter circle defining the spot.

3.4 Welding and brazing requirements. The Contractor must perform all welding and allied processes, and NDE in accordance with SFLC Std Spec 0740.

3.5 Environmental protection requirements. The Contractor must adhere to the following environmental protection requirements in accordance with the SFLC Stand Spec 0000:

3.5.1 USCG facilities. The Contractor must provide and maintain environmental protection as defined in SFLC Std Spec 0000 Appendix B, Requirements for Environmental Protection at USCG Facilities, during the performance of this availability. Contractor must plan for and provide environmental protective measures to control pollution that develops during normal practice, as well as plan for and provide environmental protective measures required to correct conditions that develop during the project. Contractor must comply with applicable Federal, state, and local laws, codes, ordinances, and regulations in their entirety. Any reference to a specific

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

portion of a Federal, state, or local law, code, ordinance, or regulation in this or any other item must not be construed to mean that relief is provided from any other sections of the law, code, ordinance, or regulation.

3.5.1.1 USCG Generator status. The activity Generator Status for the Coast Guard Facility is Large Quantity Generator (LQG).

3.5.1.2 Plans and permits. The CG Facility has unit specific permits including the following:

- Spill Prevention Control and Countermeasures (SPCC) Plan: Unit has a SPCC Plan which requires certain unit-specific procedures be followed for the storage, inspection, and transfer of petroleum products in containers 55 gallons or greater.
- National Pollutant Discharge Elimination System (NPDES) Storm Water (SW) Permit: Unit has an NPDES SW permit which requires unit-specific procedures be followed for the storage and inspection of equipment and materials which may contribute contaminants to storm water discharges.
- Air Emission Permit: Unit has an Air Emission Permit which requires unit-specific procedures be followed for the emissions of VOCs and hazardous air pollutants.

3.5.2 Test and procedures. The Contractor is required to promptly conduct tests and procedures for the purpose of assessing whether operations are in compliance with applicable Environmental Laws. Analytical work must be done by qualified laboratories; and where required by law, the laboratories must be certified.

3.5.3 Regulatory notifications. The Contractor is responsible for all regulatory notification requirements in accordance with Federal, State and local regulations. In cases where the Coast Guard must also provide public notification, such as storm water permitting, the Contractor must coordinate with the Contracting Officer or COR, and if work is being performed at a USCG Facility, the local Facility Engineer or Engineering Officer. The Contractor must submit copies of all regulatory notifications to the Contracting Officer and the local Facility Engineer or Engineering Officer prior to commencement of work activities. Regulatory notifications must be provided for including but not limited to demolition, renovation, National Pollutant Discharge Elimination System (NPDES) defined site work, and remediation of controlled substances such as asbestos, hazardous waste, and lead paint.

3.5.4 Environmental manager. The Contractor must appoint in writing an Environmental Manager for the project, who is responsible for coordinating Contractor compliance with Federal, State, local, and station environmental requirements. The Environmental Manager must ensure compliance with Hazardous Waste Program requirements, including hazardous waste handling, storage, manifesting, and disposal; implement the Contractors' Environmental Management Plan; ensure that all environmental permits are obtained, maintained, and closed out; ensure compliance with Storm Water Program Management requirements; ensure compliance with Hazardous Materials including storage, handling, and reporting requirements; as well as coordinate any remediation of regulated substances such as lead, asbestos, and polychlorinated biphenyl (PCB). This may be a collateral position; however the individual must be trained to accomplish the following duties; ensure waste segregation and storage compatibility requirements are met; inspect and manage Satellite Accumulation areas; ensure only authorized personnel add wastes to containers; ensure all Contractor personnel are trained in 40 CFR requirements and individual position requirements; coordinate removal of waste containers; and maintain the Environmental Records binder and required documentation, including environmental permits compliance and close-out.

3.5.5 HW disposal. Contractor must comply with SFLC Std Spec 0000 Appendix B, Requirements For Environmental Protection At USCG Facilities for HW disposal, and ensure that waste removals are conducted during normal business hours (0800-1600) on Monday through Friday (excluding holidays).

3.5.6 Additional Requirements. The Contractor must be aware of the following:

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.5.6.1 No Contractor or Subcontractor must have the authority to sign a Hazardous Waste Manifest using the Coast Guard facility's EPA Generator ID Number or remove contract generated hazardous waste from the Coast Guard facility without COR or KO-approval.

3.5.6.2 Local environmental regulations at the Government facilities may be more stringent. As with all environmental regulations, the Contractor must prepare for and comply with local and state regulations.

3.5.6.3 Coast Guard facilities do not maintain Facilities Response Plans (FRPs) per 33 CFR 154. Contractor must furnish the FRP when required for over-the-water liquids transfers to and from vessels, and is required for oil/fuel transfers to/from vessels for 250 barrels (10,500 gallons) or more.

3.6 Local Policy. The Contractor must refer to site (e.g., Base) Regulations and Instructions for details regarding local policies (e.g., crane services, parking, or facility usage).

3.6.1 All work items involving crane work or general movement of supplies will require a barge crane due to weight restrictions on pier. Weight restrictions include a 40 psf live load, 3,000 lb wheel load, 6000 lb axle load, and 12,00 lb max total.

3.7 SFLC Standard Specification approved changes. Approved updates to the 2022 SFLC Standard Specifications will appear here.

3.7.1 None.

4. NOTES

4.1 QA inspection forms. QA inspection forms (QA-1 thru QA-5), required in SFLC Std Spec 6310 to be completed and submitted during preservation of "critical-coated surfaces", are provided at the end of this document.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

**QA-1 - QUALITY ASSURANCE INSPECTION FORM
(PRESERVATION CHECKLIST)**

VESSEL NAME	HULL #	WORK ITEM #	WORK ITEM TITLE
LOCATION OF WORK (INCL. FRAME #'S)			AREA (SQFT)

CHECKPOINT 1 – COATING SYSTEM COMPLIANCE				
Ensure all coatings are in compliance with SFLC Std Spec 6310, Appendix C.				
CHECKPOINT 2 - PAINT STORAGE				
Ensure all coatings are kept at a temperature of 65 to 85°F at all times, unless otherwise specified by the coating mfg.				
CHECKPOINT 3 - AMBIENT CONDITIONS				
Ensure surface and surrounding temperatures are each between 50 and 90°F for water-containing coatings, and 35 and 95°F for other coatings, unless otherwise specified by the coating manufacturer(s).				
Ensure maximum relative humidity (RH) is as follows, from surface preparations through final curing of topcoat: 50% for tanks, voids, and vent plenum; and 85% for all other areas, unless otherwise specified by manufacturer(s).				
Ensure surface temperature is at least 5°F above the dew point, unless otherwise specified by the coating mfg.				
CHECKPOINT 4 - PRE-SURFACE PREPARATION				
Remove surface contaminants (soluble salts, loose rust, mud, and marine growth) with low pressure fresh water wash down (maximum 5,000 psi). If oil and grease are present, perform solvent cleaning, as per SSPC SP-1.				
Verify equipment setup, blast media, and surface preparation methods match designated test coupon.				
CHECKPOINT 5 - SURFACE PREPARATION				
Verify environmental conditions (see CHECKPOINT 3).				
Ensure cleanliness of prepared surface is as per specification (i.e.: SSPC SP-11, SP-10, SP WJ-2...).				
Verify surface anchor profile using ASTM D4417-Methods B or C against SFLC Std Spec 6310. Conduct profile readings at a minimum of 5 locations for the first 1000-sqft area, and 2 locations for each succeeding 1000-sqft area.				
Measure soluble salt conductivity in accordance with SSPC-Guide 15. Conduct 5 measurements per each 1000-sqft area (max. threshold: 70 microsiemens/cm for non-submerged surfaces, 30 microsiemens/cm for submerged surfaces).				
CHECKPOINT 6 - PRIMER COAT APPLICATION				
Verify environmental conditions (see CHECKPOINT 3).				
Verify proper mixing and stand-in (induction) times.				
Ensure no paint is applied when the temperature is expected to drop to freezing before the paint has dried.				
Ensure surfaces are completely dry, unless otherwise allowed by the coating manufacturer(s).				
Verify wet film thickness (WFT) at random, to prevent under or over application. Verify final DFT.				
Brush out all runs, sags, drips, and puddles.				
Perform visual inspection for holidays and other defects.				
CHECKPOINT 7 – STRIPE COAT APPLICATION				
Verify environmental conditions (see CHECKPOINT 3).				
Ensure overcoating window is as per manufacturer's instructions.				
After primer coat (mist coat after inorganic zinc), brush-apply un-thinned coat of same primer paint over edges, weld seams, cut-outs, and areas of complex geometries @ 3-4 mils wet film thickness (WFT).				
CHECKPOINT 8 – TOP COAT APPLICATION				
Verify environmental conditions (see CHECKPOINT 3).				
Ensure overcoating window is as per manufacturer's instructions.				
Verify proper mixing and stand-in (induction) times, as applicable.				
Verify wet film thickness at random, to prevent under or over application.				
Brush out all runs, sags, drips, and puddles.				
CHECKPOINT 9 – FINAL INSPECTION				
Verify final system dry film thickness. Conduct 5 sets of 3 readings for each of the first 3 100-sqft areas, followed by 5 sets of 3 readings for each succeeding 1000-sqft area.				
Ensure that system cure is in accordance with manufacturer's recommendation for intended service.				
Ensure potable water tank exhaust ventilation is maintained continuously from and during coating application through final system cure, to exhaust all solvent to the atmosphere and to prevent solvent entrapment.				
For immersion coatings (including tank U/W body), record date and time of the following events: Final coat application: / ; Return to service or removal from environment controls: /				
CHECKPOINT 10 – RECORD KEEPING				
Complete, sign, and submit all provided QA Inspection Forms.				
NAME OF QP-1/AMPP INSPECTOR		SIGNATURE	CERT. #	DATE / TIME
NAME OF CG REPRESENTATIVE		SIGNATURE	UNIT	DATE/TIME

VESSEL NAME	HULL #	WORK ITEM #	WORK ITEM TITLE

[illegible]

DATE / TIME

DATE/TIME

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026
QA-3a - QUALITY ASSURANCE INSPECTION FORM
(SURFACE PROFILE LOG FOR PROFILE MEASUREMENTS IAW ASTM D4417-METHOD-C)

VESSEL NAME	HULL #	WORK ITEM #	WORK ITEM TITLE
LOCATION OF WORK (FRAME REFERENCES)			AREA (SQFT)

SURFACE PREPARATION METHOD		PROFILE ACHIEVED (MILS)		
		MIN	MAX	MEAN
SSPC-SP-10/AMPP No. 2	☐			
SSPC-SP WJ-2/AMPP WJ-2	☐			
SSPC-SP-3	☐			
SSPC-SP-11	☐			
SSPC-SP-11 (inaccessible area)	☐			
Brush-blasting (non-metallic substrate)	☐			
ABRASIVE MANUFACTURER:		ABRASIVE SIEVE SIZE:		

PLACE SURFACE PROFILE REPLICA TAPES IN THE SPACES PROVIDED BELOW, TO SERVE AS PERMANENT QA RECORD. MAINTAIN A SEPARATE LOG FOR EACH LOCATION. WHEN AN AREA IS DIVIDED INTO SEPARATE SECTIONS, MAINTAIN A SEPARATE LOG FOR EACH SECTION.					
Place Surface Profile Replica Tape Here		Place Surface Profile Replica Tape Here		Place Surface Profile Replica Tape Here	
Reading (mils):		Reading (mils):		Reading (mils):	
Place Surface Profile Replica Tape Here		Place Surface Profile Replica Tape Here		Place Surface Profile Replica Tape Here	
Reading (mils):		Reading (mils):		Reading (mils):	
Place Surface Profile Replica Tape Here		Place Surface Profile Replica Tape Here		Place Surface Profile Replica Tape Here	
Reading (mils):		Reading (mils):		Reading (mils):	
Place Surface Profile Replica Tape Here		Place Surface Profile Replica Tape Here		Place Surface Profile Replica Tape Here	
Reading (mils):		Reading (mils):		Reading (mils):	
Place Surface Profile Replica Tape Here		Place Surface Profile Replica Tape Here		Place Surface Profile Replica Tape Here	
Reading (mils):		Reading (mils):		Reading (mils):	
MEAN MIL READING (IAW ASTM D4417-METHOD C) FOR ABOVE 15 READINGS:					

NAME OF QP-1/AMPP INSPECTOR	SIGNATURE	CERT. #	DATE / TIME
NAME OF CG REPRESENTATIVE	SIGNATURE	UNIT	DATE/TIME

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026
QA-3b - QUALITY ASSURANCE INSPECTION FORM
(SURFACE PROFILE LOG FOR PROFILE MEASUREMENTS IAW ASTM D4417-METHOD-B)

VESSEL NAME	HULL #	WORK ITEM #	WORK ITEM TITLE
LOCATION OF WORK (INCL. FRAME #'S)			AREA (SQFT)

SURFACE PREPARATION METHOD		PROFILE ACHIEVED (MILS)		
		MIN	MAX	MEAN
SSPC-SP-10/AMPP No. 2	☐			
SSPC-SP WJ-2/AMPP WJ-2	☐			
SSPC-SP-3	☐			
SSPC-SP-11	☐			
SSPC-SP-11 (inaccessible area)	☐			
Brush-blasting (non-metallic substrate)	☐			
ABRASIVE MANUFACTURER:		ABRASIVE SIEVE SIZE:		

RECORD MEASUREMENTS TAKEN IN THE SPACES PROVIDED BELOW, TO SERVE AS PERMANENT QA RECORD. MAINTAIN SEPARATE LOG FOR EACH LOCATION. WHEN AN AREA IS DIVIDED INTO SEPARATE SECTIONS, MAINTAIN A SEPARATE LOG FOR EACH SECTION.

Reading (mils):					
Reading (mils):					
Reading (mils):					
Reading (mils):					
Reading (mils):					
Reading (mils):					
Reading (mils):					
Reading (mils):					
Reading (mils):					
Reading (mils):					
Mean Mils Reading (IAW ASTM D4417-Method B for above 10 readings (by column):					
Mean Reading (mils)					

NAME OF QP-1/AMPP INSPECTOR	SIGNATURE	CERT. #	DATE / TIME
NAME OF CG REPRESENTATIVE	SIGNATURE	UNIT	DATE/TIME

VESSEL NAME	HULL #	WORK ITEM #	WORK ITEM TITLE
LOCATION OF WORK (INCL. FRAME #'S)			AREA (SQFT)

(Rev-0)

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026
QA-5 - QUALITY ASSURANCE DATA FORM
(COATING THICKNESS)

(Use one sheet for each sequence)

VESSEL NAME	HULL #	WORK ITEM #	WORK ITEM TITLE

COATING MFG	PRODUCT NAME	BATCH #	INDUCTION TIME	COATING SYSTEM SEQUENCE (PRIMER/TOUCHUP/3RD COAT, ETC.)

DRY FILM THICKNESS (DFT) MEASUREMENTS IAW SSPC-PA 2.						
SPOT	1	2	3	4	5	AVERAGE VALUE
*BASE METAL READING (BMR)						
*Required, If Magnetic Pull-Off (Type I/Banana) Gauge Is Used.						

LOCATION (FRAME REFERENCE):						
SPOT	1	2	3	4	5	OVERALL AVG. DFT
1						OVERALL AVG. DFT
2						
3						
AVG.						

LOCATION (FRAME REFERENCE):						
SPOT	1	2	3	4	5	OVERALL AVG. DFT
1						OVERALL AVG. DFT
2						
3						
AVG.						

LOCATION (FRAME REFERENCE):						
SPOT	1	2	3	4	5	OVERALL AVG. DFT
1						OVERALL AVG. DFT
2						
3						
AVG.						

APPLICATION METHOD (AIRLESS, CONVENTIONAL SPRAY, ROLLED)	AVERAGE DFT

NAME OF QP-1/AMPP INSPECTOR	SIGNATURE	CERT. #	DATE / TIME
NAME OF CG REPRESENTATIVE	SIGNATURE	UNIT	DATE/TIME

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

4.2 Tank and Void Assessment form.

SFLC-ESD-25		TANK AND VOID ASSESSMENT FORM	
PRINT	RESET		
GENERAL DATA Note: Use SFLC-ESD-29 for Compartments other than Tanks & Voids.			
Inspector's Name:		Organization:	Contact Info:
Cutter Name:		Cutter Class:	Hull:
Tank:	Service:	Tank Area:	Gallons:
Solid Balast:	Access Compt:	Date:	Assessment Reason:
ACCESS DATA			
Manhole and cover condition:		Tank Penetration Condition:	
VENT OVERFLOW DATA			
Present: ☐ Yes ☐ No		Check Valve Installed: ☐ Yes ☐ No	Check Valve Operates Properly: ☐ Yes ☐ No
LADDER DATA			
NR of Ladder(s) Present: ☐ Yes ☐ No		Ladder Damaged: ☐ Yes ☐ No	Ladder Material:
TANK LEVEL INDICATOR (TLI) DATA			
TLI Present in Tank: ☐ Yes ☐ No		TLI Damaged: ☐ Yes ☐ No	TLI Type:
SOUNDING TUBE DATA			
Sounding Tube Present in Tank: ☐ Yes ☐ No		Sounding Tube Damaged: ☐ Yes ☐ No	
Striker Plate Damaged (>50%): ☐ Yes ☐ No			
CATHODIC PROTECTION DATA			
Cathodic Protection in Tank: ☐ Yes ☐ No		Total Zincs:	Number of Zincs > 50% Depleted:
1-6 Cleanliness & Housekeeping			
Clean to light layer or residue		1-2 (G)	Comments:
Loose accumulation scale		3-4 (Y)	
Impending residue and sediments		5-6 (R)	
% 1-6 Coating Systems			
All Painted Surfaces		1-2 (G)	Comments:
		3-4 (Y)	
		5-6 (R)	
% 1-6 Structural			
Corrosion		1-2 (G)	Comments:
		3-4 (Y)	
		5-6 (R)	
Pitting & Grooving		1-2 (G)	Comments:
		3-4 (Y)	
		5-6 (R)	

SFLC-ESD-25	TANK AND VOID ASSESSMENT SHEET
PRINT	

Structural Integrity Data			
Estimated Total Linear Feet of Structure Requiring Repair:		Estimated Total Square Feet of Plating Requiring Repair:	
Cracks/ Fractures Present:	☐ Yes ☐ No	Buckling/Deflections/ Distortions Present:	☐ Yes ☐ No
Holes Present:	☐ Yes ☐ No	Material Wastage Present:	☐ Yes ☐ No
All Welds Intact:	☐ Yes ☐ No	Structural Evaluation Recommended:	☐ Yes ☐ No
PHOTOGRAPHS			
Pictures Taken (enter quantity):			
Note: To add pictures to this form, Work Station must have Adobe Acrobat (not Reader) installed. Add all photos and photo comments to a word document and save file. Open this form and click "Combine Files". Add the document with photos you've just saved and save as a new combined .pdf files.			
Additional Comments:			

WORK ITEM 1: Seawater Heat Exchangers, Clean, Inspect And Hydro

1. SCOPE

1.1 Intent. This work item describes the requirements for the Contractor to clean and inspect the following heat exchanger(s):

TABLE 1 – HEAT EXCHANGERS

DESCRIPTION	LOCATION	OEM / MODEL	QTY
MDE Jacket Water	Engine Room	American Precision, p/n 70A87A10096	2

1.2 Government-furnished property.

MTI	ITEM DESCRIPTION	NSN/PN	QTY	ESTIMATED COST (\$/UNIT)
N	MDE JW Seal Kit	NSN: 2930-01-602-8570 PN: 10-1AEW SEAL	2 ea.	1,250.00
Y	**JW Cooler	NSN: 2930-01-698-9297	2 ea.	29,490.00
N	**JW Cooler Tube Bundle	NSN: 2930-01-541-2516	2 ea.	2,550.00

**New or refurbished equipment that the Government may provide for installation in place of existing equipment.

2. REFERENCES

COAST GUARD DRAWINGS

Coast Guard Drawing 618 WMEC 201-001, Rev F, Arrangement of Machinery Plans, Sections & Elevations (ACTIVE)

Coast Guard Drawing 618 WMEC 536-001, Rev M, Diag Sea Water Piping for Mn Engs, Aux & Emer Gens. & A.C. Condensers

Coast Guard Drawing 618 WMEC 536-003, Rev D, Diagram – F.W. for Machinery Cooling

Coast Guard Drawing 618 WMEC 536-005, Rev B, Installation of JW & LO Coolers

Coast Guard Drawing 618 WMEC 536-052, Rev -, Heat Exchanger

COAST GUARD PUBLICATIONS

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022, General Requirements

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

Surface Forces Logistics Center Standard Specification 5000 (SFLC Std Spec 5000), 2022,
Auxiliary Machine Systems

Surface Forces Logistics Center Standard Specification 6310 (SFLC Std Spec 6310), 2022,
Requirements for Preservation of Ship Structures

Surface Forces Logistics Center Standard Specification 8636 (SFLC Std Spec 8636), 2022,
Temporary Hull Accesses

OTHER REFERENCES

Commercial Item Description (CID) A-A-59588, 2013, Rubber Silicone

3. REQUIREMENTS

3.1 General.

3.1.1 CIR.

None.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include, but are not limited to the following:

- Piping and hoses
- Filters
- Deck plating and associated framing
- Electrical cables
- Thermal insulation.

3.2 Temporary access openings. With express permission of the KO via submission of a CFR and in accordance with SFLC Std Spec 8636, the Contractor may perform all work required to cut open and close temporary access openings to facilitate accomplishment of the work specified herein.

3.3 Fluid disposition, disposal. Dispose of all removed fluids in accordance with all applicable Federal, state, and local regulations.

3.4 Disassemble. The Contractor must drain and remove the designated heat exchangers (see paragraph 1.1 (Intent)) to a suitable repair facility and disassemble to the extent necessary to perform all work specified herein. Refer to Coast Guard Drawings 618 WMEC 201-001, 618 WMEC 536-001, 618 WMEC 536-003, 618 WMEC 536-005 and 618 WMEC 536-052 for guidance. Perform all disassembly and reassembly in accordance with manufacturer-recommended procedures using manufacturer-recommended tooling to ensure parts are reinstalled in proper sequence and configuration.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.5 Inspection. Before cleaning is begun, the Contractor must visually inspect all heat exchanger surfaces for excessive deterioration and any other defects. Submit a CFR.

3.6 Cleaning requirements. The Contractor must clean all interior and exterior heat transfer surfaces to a state free of all debris, scale and surface contaminants in accordance with the heat exchanger manufacturer's recommendations, and in compliance with all Federal, state, and local environmental regulations. Ensure that chemical cleaners do not damage the environment, heat exchanger or the vessel.

NOTE

Historically, chemical cleaning has been necessary to thoroughly clean most heat exchanger tubes.

3.7 Reassembly. After authorized repairs, if any, the Contractor must reassemble each heat exchanger.

3.7.1 Renew all software (seals, gaskets, O-rings, lantern rings).

3.7.2 Renew isolation fittings/mounts and fasteners if disturbed. Apply silicone rubber sealant conforming to CID A-A-59588 around all fasteners, nozzles or gaskets that penetrate the hull.

3.7.3 Renew all hoses, thermostats and anodes as applicable.

3.8 Reinstallation. After completion of testing and all authorized repairs, if any, the Contractor must reinstall each cooler (if previously removed). Where applicable, renew all zinc electrode plates, gaskets, and recessed hex-head bolts in accordance with the manufacturer's specifications. Apply a copper-based anti-seize compound on all bolts, and torque in accordance with manufacturer's specifications.

3.9 Touch-up preservation. The Contractor must prepare and coat all new and disturbed surfaces to match existing adjacent surfaces in accordance with SFLC Std Spec 6310, (Touch-ups and minor coating repairs.)

3.10 Cleanliness requirement. The Contractor must visually inspect and ensure that all cleaned surfaces are completely free of debris and surface contaminants. Submit a CFR.

CAUTION

Extreme caution must be taken to not exceed manufacturer's recommended test pressure during hydrostatic testing.

3.11 Pressure test. After all authorized work is complete and prior to reconnecting the heat exchanger(s), the Contractor must pressure test each heat exchanger in accordance with SFLC Std Spec 5000, Appendix C paragraph C2.7 (Heat exchangers and fluid coolers) using test pressures shown in Table(s) below. Ensure no leakage from or permanent deformation of pressure-containing parts by repairing all leaks and discrepancies. Submit a CFR.

COMPONENT	SHELL SIDE TEST PRESSURE (PSI)	TUBE SIDE TEST PRESSURE (PSI)
Main Diesel Engine	50	50

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.12 Label plates. The Contractor must attach an anodized aluminum test data plate to each heat exchanger using epoxy resin cement. Ensure that each plate is engraved with ¼-inch high letters, stating the following:

- Test pressure.
- Test date.
- Testing facility.

NOTE

If the heat exchanger design makes mounting a test data plate impractical, the Government reserves the right to request written documentation of the above-listed testing data in lieu of a test data plate, at no additional cost to the Government.

3.13 Leak test. After completing all authorized mechanical (i.e. threaded, bolted, etc.) joint repairs, the Contractor must test the heat exchanger system's operation using the system fluid at normal operating pressure. Ensure zero visible leakage from or deformation of mechanical parts by repairing all leaks and discrepancies. Submit a CFR.

3.14 Government's right for change out. The Contractor must be aware that the Government reserves the right to furnish a new Jacket Water Cooler or Jacket Water Cooler Tube Bundle for installation in place of the existing. If the Government exercises this right, the Contractor must dispose of the removed Lube Oil Cooler and/or Tube Bundle in accordance with all applicable Federal, state, and local regulations OR return to the Coast Guard PA as an MTI item, as applicable.

4. NOTES

4.1 System refill. The ship will refill the Jacket Water Cooler at the conclusion of repairs.

WORK ITEM 2: Boiler Exhaust Stack Uptakes, Commercial Clean

1. SCOPE

1.1 Intent. This work item describes the requirements for the Contractor to clean the Boiler exhaust stack uptakes.

1.2 Government-furnished property.

None.

2. REFERENCES

COAST GUARD DRAWINGS

Coast Guard Drawing 618 WMEC 259-001, Rev F, Exhaust Piping Arrangement

COAST GUARD PUBLICATIONS

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022,
General Requirements

Surface Forces Logistics Center Standard Specification 6310 (SFLC Std Spec 6310), 2022,
Requirements for Preservation of Ship Structures

OTHER REFERENCES

None

3. REQUIREMENTS

3.1 General.

3.1.1 CIR.

None.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include, but are not limited to following:

- Access covers.
- Exhaust stack.
- Boiler.
- Exhaust pipe expansion joints.
- Exhaust insulation blankets.

3.2 Safety precaution. The Contractor must rig suitable safety netting, to protect workers during possible falls, and to protect the Engine Room and machinery from falling tools.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.3 Operational test, initial. Prior to commencement of work, the Contractor must witness Coast Guard personnel perform an initial operational test of all items or shipboard devices to be disturbed, used, repaired, or altered, to demonstrate existing operational condition. Submit a CFR.

3.4 Cleaning. The Contractor must clean the interior surfaces of the exhaust piping to the Boiler, shown on Coast Guard Drawing(s) 618 WMEC 259-001, to a condition free from soot, tar, and any other foreign matter as follows:

3.4.1 Disconnect the exhaust piping as necessary to facilitate cleaning.

3.4.2 Thoroughly sweep, mechanically clean, and vacuum the interior of each exhaust pipe system, including the mufflers, from the exhaust outlet to the topmost location outside the vessel. Ensure that all tar deposits, soot deposits, and all other surface contaminants are completely removed.

3.4.3 Upon completion of cleaning, do the following:

3.4.3.1 Remove all debris from the pipe surfaces, stack deck, and Engine Room areas by vacuuming. Dispose of all cleaning materials and generated debris in accordance with all applicable Federal, state, and local regulations.

3.4.3.2 Reassemble exhaust piping; renew all flange connection gaskets with suitable high temperature, non-asbestos-containing gasket materials; and renew all fasteners.

3.5 Inspection and report. The Contractor must perform a visual inspection of the following components; submit a CFR:

- Exhaust stack access hatches, including all associated studs and nuts.
- All cleaned exhaust stack surfaces.
- All exhaust expansion joints, including associated bolts.

3.5.1 Following cleaning of the interior of each uptake, the Contractor must demonstrate completeness of the cleaning process to the Coast Guard Inspector, showing that the entire length of uptake has been satisfactorily cleaned according to the work plan.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.6 Touch-up preservation. The Contractor must prepare and coat all new and disturbed surfaces to match existing adjacent surfaces in accordance with SFLC Std Spec 6310, (Touch-ups and minor coating repairs.)

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.7 Operational test, post repairs. After completion of work, the Contractor must thoroughly test, in the presence of the Coast Guard Inspector and demonstrate all items or shipboard devices that have been disturbed, used, repaired, altered, or installed to be in satisfactory operating condition. Submit a CFR.

4. NOTES

This section is not applicable to this work item.

WORK ITEM 3: Chill Water System, Clean and Flush

1. SCOPE

1.1 Intent. This work item describes the requirements for the Contractor to clean and flush the Chill Water and Heat System.

1.2 Government-furnished property.

None.

2. REFERENCES

COAST GUARD DRAWINGS

Coast Guard Drawing 618 WMEC 512-007, Rev D, Ventilation Diagram Main Deck

Coast Guard Drawing 618 WMEC 514-001, Rev G, Diagram: Heating and Chilled Water System

Coast Guard Drawing 618 WMEC 514-002, Rev G, Arrgt of Chilled & Hot Water System Inside MS

Coast Guard Drawing 618 WMEC 514-003, Rev L, Arrgt of Chilled & Hot Water System Outside of MS

Coast Guard Drawing 618 WMEC 514-004, Rev G; Htg, Vent & A/C Cont Blk W/D & Schematic

COAST GUARD PUBLICATIONS

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022, General Requirements

Coast Guard Technical Publication (TP) 3965, Apr 2020, Air Conditioning System, R-134A – Model 90RMC025-D-6-D005/MS1

OTHER REFERENCES

None

3. REQUIREMENTS

3.1 General.

3.1.1 CIR.

None.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include, but are not limited to the following:

- Piping and hoses
- FCU Flow Control valve(s) (remove prior to clean and flush)
- Bulkheads
- Deck plating and associated framing
- Heat exchangers
- Electrical cables
- Thermal insulation.

3.2 Operational test, initial. Prior to commencement of work, the Contractor must witness Coast Guard personnel perform an initial operational test of all items or shipboard devices to be disturbed, used, repaired, or altered, to demonstrate existing operational condition. Submit a CFR.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.3 System draining. The Contractor must drain all existing fluid from the Chill Water and Heat System. System must be drained, at a minimum, from a low point in the system. Locations of system low points include, but may not be limited to, Small Arms Magazine (Compartment 4-52-1-M), Armory & Workshop (4-52-0-M), and Magazine (Compartment 4-62-1-M). Identify locations of system low point drains on the Cleaning Plan (see paragraph 3.5). Dispose of removed fluids in accordance with all Federal, state, and local regulations.

3.4 Coil unit line-up. Prior to commencement of system flushing, the Contractor must ensure that all fan coil units are lined-up to the system, with the assistance of the Coast Guard Inspector.

3.5 Cleaning plan. The Contractor must establish a plan for cleaning the Chill Water and Heat Piping System using Coast Guard Drawings 618 WMEC 512-007, 618 WMEC 514-001, 618 WMEC 514-002, 618 WMEC 514-003, and 618 WMEC 514-004 as guidance. List the step by step procedures necessary to ensure that all foreign debris is removed from the piping system while simultaneously protecting all installed equipment.

CAUTION!

Ensure evaporator plate cooler is isolated from all flushing procedures aboard 210 Cutters!

3.5.1 Procedure requirements. Ensure that the procedure includes the following:

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

- Methods of cleaning.
- All safety precautions required during cleaning operations.
- List of qualified personnel who will operate machinery or handle chemicals.
- Locations in the chill water piping where cleaning will take place, and any additional fittings necessary.
- Sequence of each location that ensures all piping sections will be cleaned and all foreign debris removed.

3.5.2 Plan submittal. Submit the written plan to the COR for approval at least 48 hours prior to commencing cleaning operations.

3.6 Flushing operations. Upon approval of the plan, the Contractor must proceed with the flushing of the piping system, as follows:

3.6.1 Clean all system strainers and valves.

3.6.2 Flush all chill/hot water piping, to include both 5 and 25 ton loops, with a system manufacturer recommended flushing fluid until all visible dirt, grit, flux and other contaminants are removed from the system. Ensure that flushing fluid is directed to move scale and foreign debris away from installed machinery to prevent possible damage upon operational testing. Submit a CFR documenting date and time of flushing process, and verification of piping and FCU cleanliness.

3.6.3 Dispose of flushing fluid in accordance with all applicable Federal, state, and local regulations.

WARNING!

Do not drain ANY Fluids (including fresh water) into any space, bilge, or exterior location.

3.7 System refilling. Upon completion of all cleaning and flushing operations, the Contractor must refill the system with clean water using above-referenced Coast Guard drawings (see Section 2) as guidance and in accordance with Coast Guard Tech Pub 3965. The Contractor must ensure that the renewed system water quality is equivalent to the cutter's potable water system. The Contractor must measure the system pH value. Submit a CFR documenting that the pH value is not conducive to corrosion (7.4 nominal, and not less than 7.0 or higher than 8.0).

3.8 Flushing media requirements. The Contractor must ensure that the cleaning and flushing media does not cause any damage to the Chill Water and Heat System.

3.9 Operational test, post repairs. After completion of work, the Contractor must thoroughly test, in the presence of the Coast Guard Inspector, and demonstrate all items or shipboard devices that have been disturbed, used, repaired, altered, or installed to be in satisfactory operating condition. Submit a CFR.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

4. NOTES

This section is not applicable to this work item.

WORK ITEM 4: Boilers, Renew

1. SCOPE

1.1 Intent. This work item describes the requirements for the Contractor to renew both ship's service boiler assemblies; including shell, tubes, associated valves and burner assembly located in the Engine Room.

1.2 Government-furnished property.

MTI	ITEM DESCRIPTION	NSN/PN	QTY	ESTIMATED COST (\$/UNIT)
N	Way-Wolff Boiler Model No. 5848-14E	NSN: 4410-01-230-8024	2 ea.	43,682.00

2. REFERENCES

COAST GUARD DRAWINGS

Coast Guard Bill of Materials 618 WMEC 11, Rev J, 3rd Dk, 2nd Dk, Main Dk, 02 Dk & Bridge Dk Plt g & Supports
 Coast Guard Bill of Materials 618 WMEC 61, Rev K, Arr. Stm., Feed & Conds. Sys. Piping
 Coast Guard Drawing 618 WMEC 131-001, Rev M, 2nd & Main Deck Plating & Supports
 Coast Guard Drawing 618 WMEC 182-002, Rev W, Foundations in Engine Room
 Coast Guard Drawing 618 WMEC 535-001, Rev N, Diagram Steam, Feed & Condensate System Piping
 Coast Guard Drawing 618 WMEC 535-002, Rev N, Arr. Stm., Feed & Condensate System Piping
 Coast Guard Drawing 618 WMEC 535-004, Rev-, Split Pipe Drain Duct for Boiler Overboard Disch
 Coast Guard Drawing 618 WMEC 601-001, Rev J, Outboard Profile
 Coast Guard Drawing 618 WMEC 601-002, Rev B, Inboard Profile
 Coast Guard Drawing 618 WMEC 601-003, Rev K, General Arrangement - Second and Third Decks
 Coast Guard Drawing 618 WMEC 601-004, Rev K, General Arrangement Main & 01 Deck

COAST GUARD PUBLICATIONS

Coast Guard Technical Publication (TP) 2188, Dec 2024, Steam Heating Boiler - Model 5848-14E
 Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022, General Requirements

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

Surface Forces Logistics Center Standard Specification 0740 (SFLC Std Spec 0740), 2022,
Welding and Allied Processes

Surface Forces Logistics Center Standard Specification 6310 (SFLC Std Spec 6310), 2022,
Requirements for Preservation of Ship Structures

Surface Forces Logistics Center Standard Specification 8636 (SFLC Std Spec 8636), 2022,
Temporary Hull Accesses

OTHER REFERENCES

ASTM International (ASTM) F683, 2014, Standard Practice for Selection and Application of
Thermal Insulation for Piping and Machinery

ASTM International (ASTM) F992, 2017, Standard Specification for Valve Label Plates

NAVSEA Drawing 804-5959214, Rev-, Piping Insulation - Installation Details

3. REQUIREMENTS

3.1 General. The Contractor must renew designated ship's service boiler assembly(s) (including shell, tubes, associated valves (including blow-down valve) and burner assembly (Way-Wolff steam boiler, Model 5848-14E) with a Government-furnished Way-Wolff boiler assembly. Refer to TP 2188 and the applicable Coast Guard drawing(s) listed in Section 2 (References) for guidance.

3.1.1 CIR.

None.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include, but are not limited to the following:

- Fuel oil piping
- Steam piping
- Condensate piping
- Insulation
- Metal sheathing
- Handrail
- Stanchions
- Deck frames and grating
- Wiring brackets
- Ducting
- Transformers

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

- Demineralizer
- System fluids, steam and chemical additives
- Bilge piping
- Bilges

3.1.4.1 Fluid removal. Remove up to 2,500 gallons of oily water to facilitate gas-freeing.

3.1.4.2 Bilge cleaning. Clean (e.g. pressure wash, hand wash, wipe down, etc.) all bilge surfaces in the Engine Room free of all foreign materials, such as dirt, oil, sediment or sludge to facilitate gas-freeing. Remove all persistent residues, taking care not to damage the coating system or to allow any contamination to enter the machinery. Remove fluids, cleaning media, and residues continuously during the washing process. Remove any residual wash media and wipe up residual moisture with clean, lint-free cloths. Collect, contain, and dispose of all fluids, wash media, residues, and cleaning materials in accordance with all Federal, state, and local regulations.

3.1.4.3 Fluid disposition, disposal. Dispose of all removed fluids in accordance with all applicable Federal, state, and local regulations. Refer to paragraph 4.1 (Tank content restoration).

3.2 Temporary access openings. With express permission of the KO via submission of a CFR and in accordance with SFLC Std Spec 8636, the Contractor may perform all work required to cut open and close temporary access openings to facilitate accomplishment of the work specified herein.

3.3 Additional structural supports. When ship's structure is removed as an interference or is otherwise temporarily modified to facilitate repairs, the Contractor must maintain existing structural integrity of the ship by installing temporary supports equivalent to those temporarily modified or removed. These temporary supports must be approved by the COR prior to removing or modifying ship's structure via CFR. Pay particular attention to structure supporting the Ship Service generators. Restore to original configuration after completion of work.

3.4 Boiler removal. The Contractor must accomplish the following for the designated boiler assembly(s):

3.4.1 Disconnect all piping, insulation, sheet metal wrap, exhaust ductwork, and accessories in way of boiler removal.

3.4.2 Crop out, remove, and dispose of the existing boiler assembly, including shell, tubes and burners.

3.5 Inspection. The Contractor must visually inspect the associated ship's service boiler piping, foundations, exhaust ductwork, and electrical wiring for corrosion and deterioration. Submit CFR.

3.6 Foundation surface preservation. The Contractor must prepare and coat the boiler foundation surfaces, including all adjacent structural members, in accordance with SFLC Std Spec 0000 and SFLC Std Spec 6310; using the coating system specified for "Machinery, Interior (Machinery, Steel, Operating Temperatures Over 200°F Surfaces)" in SFLC Std Spec 6310, Appendix B (Cutters and Boats Interior Painting Systems). Select finish/top coat color to match existing adjacent surfaces.

3.7 New boiler installation. The Contractor must accomplish the following for the designated boiler assembly:

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.7.1 Rig in the new Government-furnished Way-Wolff boiler assembly through the same route used for removing the old boiler.

3.7.2 Assemble and install the Government-furnished Way-Wolff boiler and accessories to original configuration using TP 2188 as guidance. Weld the new boiler shell onto its foundation in accordance with the requirements of SFLC Std Spec 0740.

3.7.3 Fabricate and install new flanges to suit the existing exhaust duct flange. Minor modifications to the exhaust port may be required to facilitate a proper fit in the machinery space. Submit a CFR.

3.7.4 Prior to shipboard installation and again after installation, hydrostatically test the new boiler and associated piping in accordance with SFLC Std Spec 0740 in the presence of the Coast Guard Inspector. Plug all external holes on the boiler; hydrostatically test the water side with clean fresh water for 15 minutes. Notify the Coast Guard Inspector 24 hours prior to testing. Be aware that no leakage or permanent deformation of pressure-containing parts is permissible. Repair all leaks and discrepancies found. Submit a CFR for each test.

CAUTION

Historically, it has been necessary for Contractors to provide and weld install three 4-inch to varying size reducer fittings into each boiler to accomplish the hydrostatic test.

-Base the test pressure and relief settings on the designated boiler's pressure rating for 15 psi steam and 30 psi water. The operating and relief settings for steam service relief valves has been downgraded from 30 PSI to 15 PSI, which will be the case for all newly installed boilers, however some boilers in the fleet are still rated at 30 psi for steam.

NOTE

Boiler burner assembly igniter gaps are not preset from the factory, and must be set and verified in accordance with TP 2188 prior to attempting any operational tests.

Excessive igniter gaps can result in soot damage to the diffuser cone and poor boiler performance.

NOTE

Wiring arrangements may vary between vessels.

3.7.5 Accomplish all piping installation and restoration in accordance with the welding and testing requirements of SFLC Std Spec 0740.

3.7.5.1 Reconnect/reinstall all piping.

3.7.5.2 Renew boiler shell insulation. Install outer sheet metal wrap and exhaust ductwork to their original configuration. Renew all disturbed piping insulation and thermal blankets.

3.7.5.3 Renew all disturbed gaskets and fasteners. Verify that boiler relief valve is set at 2 psi above max operating pressure (per boiler dataplate). Renew the following associated valves for each designated boiler:

- 1 ¼" gate valve

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

- 1 ¼" solenoid valve
- 1 ¼" check valve.

3.7.5.4 If a Change Request is released and approved by the KO, the Contractor must install new insulation material over the exposed designated steam piping surfaces, including associated pipe hangers, valves, fittings, and flanges, in accordance with details in NAVSEA Drawing 804-5959214; select appropriate insulation materials and thicknesses for the application and temperature ranges specified in ASTM F683, Tables S1.1, S1.2, and S1.4. Paint the newly installed insulation system, in accordance with SFLC Std Spec 6310, using the system specified for "Insulation Surfaces, Fiberglass Sheet/Closed Cell PVC Foam" in Appendix B (Cutter and Boat Interior Paint Systems).

3.8 Touch-up preservation. The Contractor must prepare and coat all new and disturbed surfaces to match existing adjacent surfaces in accordance with SFLC Std Spec 6310, (Touch-ups and minor coating repairs.)

NOTE

The Contractor must not drain any fluids into the bilges during the performance of this work item. All fluids must be drained and disposed of in accordance with all applicable Federal, state, and local regulations.

Coast Guard personnel will operate all shipboard machinery and equipment.

3.9 Operational test, post repairs. After completion of work and in the presence of the Coast Guard Inspector, the Contractor must thoroughly test and demonstrate the equipment listed below to be in satisfactory operating condition. Submit a CFR.

- New boiler system including all associated valves
- New burners properly adjusted in accordance with manufacturer's instructions
- All new and disturbed components.

3.10 Label nameplate, installation. The Contractor must furnish and install a nameplate label onto the valves and pressure vessel; and must ensure each nameplate is made of the melamine type material with either engraved black letters on white background or white letters on black background, or metal photo type material with black letters photographically sealed onto an aluminum surface.

4. NOTES

4.1 Ship check. Due to numerous interferences and limited accessibility for the removal and installation of the boilers, all prospective bidders are strongly encouraged to perform a ship check prior to submitting bids.

4.2 Removal access. Historically, this work has been facilitated by cutting accesses through the deck.

4.3 Boiler feedwater. Ship's Force will verify the water quality (cleanliness and chemistry) of the boiler system prior to resuming boiler operations.

WORK ITEM 5: Potable Water Pneumatic Tanks, Clean and Inspect**1. SCOPE**

1.1 Intent. This work item describes the requirements for the Contractor to clean and inspect the following potable water pneumatic tank(s):

TABLE 1 – TANKS

SERVICE	LOCATION	CAPACITY (GALLONS)	PRESSURE (PSIG)
Hydro-Pneumatic	3-108-0-E	120	70

1.2 Government-furnished property.

None.

2. REFERENCES**COAST GUARD DRAWINGS**

Coast Guard Drawing 618 WMEC 533-001, Rev P, Diag. Hot & Cold Potable Water

COAST GUARD PUBLICATIONS

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022,
General Requirements

Surface Forces Logistics Center Standard Specification 6310 (SFLC Std Spec 6310), 2022,
Requirements for Preservation of Ship Structures

OTHER REFERENCES

ASTM International (ASTM) D1330, 2015, Standard Specification for Rubber Sheet Gaskets

American National Standards Institute/American Water Works Association (ANSI/AWWA)
C652, 2019, Disinfection of Water-Storage Facilities

3. REQUIREMENTS

3.1 General.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.1.1 CIR.

None.

3.1.2 Tech rep.

None.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, Paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.3.1 Plug all inlet and outlet piping in the tank(s) to prevent contaminants from entering. Use plugs with an attached lanyard, ring or other system that will ensure plugs are not lost in the pipe openings.

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include, but are not limited to the following:

- Piping.

3.1.5 Plug log. The Contractor must keep a written record of all plugs put in any tanks vents. A separate list must be kept for each tank being entered.

3.1.5.1 Ensure that all plugs are removed from each tank upon completion of work in the tank.

3.1.5.2 The plug log must be available to the Coast Guard inspector when the inspector is performing his close-out inspection on each tank.

3.2 Preparation. The Contractor must depressurize and drain the designated tank(s) (see paragraph 1.1 (Intent)) before performing any work on them. Dispose of all fluids in accordance with all applicable Federal, state, and local environmental regulations.

NOTE

Do not drain any fluids (including fresh water) into any space, bilge or exterior location.

3.3 Cleaning requirements. For all tanks designated in paragraph 1.1 (Intent), the Contractor must clean all tank interior surfaces free of all foreign materials, sediment, and sludge. Remove all persistent residues, taking care not to damage the tank coating system, where present. Remove cleaning media and residues continuously from the tank during the washing process. Remove any residual wash media and wipe up residual moisture with clean lint-free cloths. Collect, contain, and dispose of all wash media, residues, and cleaning materials in accordance with all Federal, state, and local regulations.

3.4 Inspection. The Contractor must, using Coast Guard Drawing 618 WMEC 533-001 for guidance, accomplish the following for all designated tank(s) (see paragraph 1.1 (Intent)):

3.4.1 Visual inspection. Clean and visually inspect the internal and external surfaces of each tank for signs of corrosion, pitting, and other damage. If required by the pneumatic tank's construction, the Contractor must provide and use a borescope during the visual inspection. Submit a CFR.

3.5 Surface preservation. If a Change Request has been authorized and released, the Contractor must prepare and coat each tank's interior surfaces using the system specified for "Tanks and Voids (Potable

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

Water Tanks)” in SFLC Std Spec 6310, Appendix B (Cutter and Boat Interior Painting Systems). If preservation is for less than 100 percent of tank interior surfaces, power tool clean all affected surfaces to “bare metal” in lieu of using abrasive blasting, and feather edges of existing intact coating to the prepared areas in order to provide a smooth transition with the new paint.

3.6 Tank closing. The Contractor must notify the COR at least 24 hours prior to closing the tank(s) and ensure tank closure is accomplished in the presence of the Coast Guard Inspector. After satisfactory inspection by the Coast Guard Inspector, and completion of all authorized repairs, close the manhole cover(s) with new gasket material conforming to ASTM D1330.

3.6.1 Renew 100% of nylon insert/nylock nuts and washers.

3.7 Leak test. After tank reinstallation and completing all authorized mechanical (i.e. threaded, bolted, etc.) connections, the Contractor must test the potable water system's operation using the system fluid at normal operating pressure. Ensure zero visible leakage from or deformation of mechanical parts by repairing all leaks and discrepancies. Submit a CFR.

3.8 Tank disinfecting. After all other work involving the potable water system and tank closing have been completed, the Contractor must disinfect and treat the affected potable water tank(s), as necessary to meet or exceed the requirements of AWWA C652. After tank disinfecting, remove and dispose of all treated water in accordance with all Federal, state and local regulations. Ensure that no one enters the tanks once disinfection is completed. Submit CFR providing confirmation that disinfection of tank(s) and associated potable water system disturbed piping and components has been completed and certifying that all sampling and testing is negative for coliform organisms.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.9 Operational test, post repairs. After completion of work, the Contractor must thoroughly test, in the presence of the Coast Guard Inspector and demonstrate all items or shipboard devices that have been disturbed, used, repaired, altered, or installed to be in satisfactory operating condition. Submit a CFR.

4. NOTES

This section is not applicable to this work item.

WORK ITEM 6: Hot Water Accumulator Tanks, Clean and Inspect**1. SCOPE**

1.1 Intent. This work item describes the requirements for the Contractor to clean and inspect the following hot water tank(s):

TABLE 1 - TANKS

SERVICE	LOCATION	CAPACITY (GALLONS)	PRESSURE (PSIG)
Hot Water Storage	3-108-0-E	200	70

1.2 Government-furnished property.

None.

2. REFERENCES**COAST GUARD DRAWINGS**

Coast Guard Drawing 618 WMEC 533-001, Rev P, Diag Hot & Cold Potable Water

COAST GUARD PUBLICATIONS

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022,
General Requirements

Surface Forces Logistics Center Standard Specification 0740 (SFLC Std Spec 0740), 2022,
Welding and Allied Processes

Surface Forces Logistics Center Standard Specification 6310 (SFLC Std Spec 6310), 2022,
Requirements for Preservation of Ship Structures

OTHER REFERENCES

ASTM International (ASTM) D1330, 2015, Standard Specification for Rubber Sheet Gaskets

American National Standards Institute/American Water Works Association (ANSI/AWWA)
C652, 2019, Disinfection of Water-Storage Facilities

3. REQUIREMENTS

3.1 General.

3.1.1 CIR.

None.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.3.1 Plug all inlet and outlet piping in the tank(s) to prevent contaminants from entering. Use plugs with an attached lanyard, ring or other system that will ensure plugs are not lost in the pipe openings.

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include, but are not limited to the following:

- Piping

3.2 Plug log. The Contractor must keep a written record of all plugs put in any tanks vents. A separate list must be kept for each tank being entered.

3.2.1.1 Ensure that all plugs are removed from each tank upon completion of work in the tank.

3.2.1.2 The plug log must be available to the Coast Guard inspector when the inspector is performing his close-out inspection on each tank.

3.3 Preparation. The Contractor must depressurize and drain the designated tank(s) (see paragraph 1.1 (Intent)) before performing any work on them. Dispose of all fluids in accordance with federal, state, and local environmental regulations.

NOTE:

Do not drain any fluids (including fresh water) into any space, bilge or exterior location.

3.4 Operational test, initial. Prior to commencement of work, the Contractor must witness Coast Guard personnel perform an initial operational test of the equipment listed below to demonstrate existing operational condition. Submit a CFR.

- Hot Water Tank (electronic controls and heating elements)

3.5 Cleaning requirements. For all tanks designated in paragraph 1.1 (Intent), the Contractor must clean all tank interior surfaces free of all foreign materials, sediment, and sludge. Remove all persistent residues, taking care not to damage the tank coating system, where present. Remove cleaning media and residues continuously from the tank during the washing process. Remove any residual wash media and wipe up residual moisture with clean lint-free cloths. Collect, contain, and dispose of all wash media, residues, and cleaning materials in accordance with all Federal, state, and local regulations.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.6 Inspection. The Contractor must accomplish the following for the designated tank(s) (see paragraph 1.1 (Intent)) and associated heaters, using Coast Guard Drawing 618 WMEC 533-001 for guidance:

3.6.1 Visual inspection. Visually inspect the internal and external surfaces of each tank for signs of corrosion, pitting, and other damage. Submit a CFR.

3.6.2 Tanks with steam heater tubes. Remove the hot water accumulator tank heaters from the vessel to a suitable repair facility.

3.6.2.1 Clean and visually inspect all heater surfaces.

3.6.2.2 Hydrostatically test steam heater tubes to 135% of the system design pressure in accordance with manufacturer's instructions and SFLC Std Spec 0740, Appendix C, (Hydrostatic Test). Hold test for 15 minutes using clean, fresh water and inspect for leaks. Ensure zero leakage from or permanent deformation of pressure-containing parts by repairing all leaks, deformations, and discrepancies. Submit a CFR. Do not exceed manufacturer's recommended test pressure.

3.6.2 Tanks with electrical heating elements. Clean and visually inspect the hot water accumulator tank heaters. Test the electrical resistance and heat conductivity of the heaters. Submit a CFR.

3.7 Tank preservation. If a Change Request has been authorized and released, prepare and coat each tank's interior surfaces using the system specified for "Tanks and Voids (Potable Water Tanks)" in SFLC Std Spec 6310, Appendix B (Cutter and Boat Interior Painting Systems). If preservation is for less than 100 percent of tank interior surfaces, power tool clean all affected surfaces to "bare metal" in lieu of using abrasive blasting, and feather edges of existing intact coating to the prepared areas in order to provide a smooth transition with the new paint. Do not drain any fluids (including fresh water) into any space, bilge or exterior location.

3.8 Tank closing. The Contractor must notify the COR at least 24 hours prior to closing the tank(s) and ensure tank closure is accomplished in the presence of the Coast Guard Inspector. After satisfactory inspection by the Coast Guard Inspector, and completion of all authorized repairs, close the manhole cover(s) with new gasket material conforming to ASTM D1330.

3.8.1 Renew 100% of nylon insert/nylock nuts and washers.

3.9 Leak test. After tank reinstallation and completing all authorized mechanical (i.e. threaded, bolted, etc.) connections, the Contractor must test the potable water system's operation using the system fluid at normal operating pressure. Ensure zero visible leakage from or deformation of mechanical parts by repairing all leaks and discrepancies. Submit a CFR.

3.10 Tank disinfecting. After all other work involving the potable water system and tank closing have been completed, the Contractor must disinfect and treat the affected potable water tank(s), as necessary to meet or exceed the requirements of AWWA C652. After tank disinfecting, remove and dispose of all treated water in accordance with all Federal, state and local regulations. Ensure that no one enters the tanks once disinfection is completed. Submit CFR providing confirmation that disinfection of tank(s) and associated potable water system disturbed piping and components has been completed and certifying that all sampling and testing is negative for coliform organisms.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.11 Operational test, post repairs. After completion of work, the Contractor must thoroughly test, in the presence of the Coast Guard Inspector and demonstrate all items or shipboard devices that have been disturbed, used, repaired, altered, or installed to be in satisfactory operating condition. Submit a CFR.

4. NOTES

This section is not applicable to this work item.

WORK ITEM 7: Steering Gear, General, Overhaul**1. SCOPE**

1.1 Intent. This work item describes the requirements for the Contractor to overhaul the port and starboard steering system assemblies, located in the Steering Gear Room.

1.2 Government-furnished property.

MTI	ITEM DESCRIPTION	NSN/PN	QTY	ESTIMATED COST (\$/UNIT)
N	**Valve, counterbalance, 1000-4000 psi, 30 gpm, 25 psi check	NSN: 4810-01-353-0586	4 ea.	67.33
N	**Valve, safety relief	NSN: 4820-01-241-5464 PN: CS06F50	2 ea.	466.33
N	**Valve, check, 25 psi, 32 gpm	NSN: 4820-01-627-7022	4 ea.	58.64
N	**Float switch, liquid level	NSN: 6680-01-673-5099	2 ea.	425.00
N	**Valve, safety relief	NSN: 4820-01-571-9823 PN: RAH101S30	2 ea.	41.70
N	**Coupling half, shaft	NSN: 3010-01-675-1842 PN: RC2-0625-156	2 ea.	25.30
N	**Coupling half, shaft	NSN: 3010-01-674-9183 PN: RC2-1375-312	2 ea.	25.30
N	**Insert, flexible coupling, pump to motor	NSN: 3010-01-674-8153	2 ea.	11.70
N	**Pump, rotary Honor series 2D, CW	NSN: 4320-01-673-6806	2 ea.	536.00

**New or refurbished equipment that the Government may provide for installation in place of existing equipment.

2. REFERENCES**COAST GUARD DRAWINGS**

Coast Guard Drawing 618 WMEC 561-051, Rev -, Hydraulic Cylinder 3/4 Bore Vickers No. 45-103300

Coast Guard Drawing 618 WMEC 800-002, Rev A, Strg Sys Hyd Mchry & Ppg Installations

COAST GUARD PUBLICATIONS

Coast Guard Technical Publication (TP) 4034, Aug 2018, SWBS 561, Electro-Hydraulic Steering System & Alarm System Upgrade

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022, General Requirements

Surface Forces Logistics Center Standard Specification 3020 (SFLC Std Spec 3020), 2022, Overhaul AC Electrical Motors

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

Surface Forces Logistics Center Standard Specification 5000 (SFLC Std Spec 5000), 2022,
Auxiliary Machine Systems

OTHER REFERENCES

MIL-G-21164, Jul 2019, Grease, Molybdenum Disulfide, for Low and High Temperatures,
NATO Code Number G-353

MIL-STD-419 E, Aug 2017, Cleaning, Protecting, and Testing Piping, Tubing, and Fittings for
Hydraulic Power Transmission Equipment

3. REQUIREMENTS

3.1 General.

3.1.1 CIR.

None.

3.1.2 Tech Rep.

None.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.3.1 Protection of fine surfaces. The Contractor must protect all fine surfaces in accordance with SFLC Std. Spec 5000.

3.1.3.2 Hydraulic system contamination protection. The Contractor must maintain existing hydraulic cleanliness in accordance with SFLC Std. Spec 5000.

3.1.3.3. Immediately after disconnecting or removing components from the hydraulic system, seal all openings to the rest of the system using caps for externally threaded connection points, bolt-on blanks, or taped-on discs/covers made of durable plastic or sheet-metal that is no less than 1/16-inch thick.

NOTE

Be aware that plastic bags may be used only when arrangement or configuration prevents the use of the other sealing methods specified above.

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include, but are not limited to the following:

- Piping
- Controls
- System Fluids
- Wiring

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.1.4.1 The Contractor must drain the hydraulic fluid (up to 150 gallons) to a suitable container and dispose of in accordance with Federal, state and local regulations.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.2 Operational test, initial. Prior to commencement of work, the Contractor must witness Coast Guard personnel perform an initial operational test of the steering system to demonstrate existing operational condition. Submit a CFR.

NOTE

Local steering control in Non-Follow Up (NFU) mode from the Emergency Switch and Steering Box (ESSB) may not be sufficient to achieve speed requirements due to internal bypasses in the HPU. System operation from the Bridge in either Follow Up (FU) or NFU modes may be necessary.

3.2.1 Record the time it takes to run the rudders hard over from 35 deg right rudder to 35 deg left rudder, then repeat in the other direction. Verify that the rudder hard over time is not greater than 20 seconds for single HPU operation, or 10 seconds when operating both HPU's. Record the maximum pressure observed during rudder swing.

3.2.2 Record accuracy of helm commands and rudder angle indicators to actual tiller position at amidships, 5, 15, 25, and 35 degrees (left and right rudder). Verify that the error does not exceed 1/4 degree for rudder angles of 5 degrees and less and 1/2 degree for larger rudder angles.

3.2.3 Use an ammeter to record the amperage at startup and during rudder swing to three different positions - hard over port, amidships, and hard over starboard.

WARNING

Take all necessary precautions to prevent injury due to electric shock and potential arc-flash from energized equipment. Only necessary personnel (contracted or Ship's Force) may be present in the compartment while energized panels are open.

3.2.4 Submit a list of readings to the Coast Guard Inspector for the pump and motor units, including speeds, accuracy readings, discharge pressures, and motor current draw.

3.3 Removal/disassembly. The Contractor must remove/disassemble the steering system assembly to the extent necessary to accomplish overhaul procedures.

3.3.1 Securing rudders from uncontrolled movement. Prior to disassembly of steering gear machinery, the Contractor must use suitable means to secure the rudder stocks and blades from uncontrolled movement or rotation during repairs. Suitable means may include, for example, chain falls with chafing gear or blocking. Remove equipment prior to re-energizing the system.

3.4 Overhaul specifics. The Contractor must accomplish the following overhaul tasks in accordance with SFLC Std Spec 5000 Appendix C, using Coast Guard drawings and tech pubs listed in Section 2 (References) and MIL-STD-419 as guidance. Submit a CFR.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.4.1 Motor and pump couplings. Remove, clean, inspect, and reinstall the couplings for the motors and pumps. Renew all keys, set screws, gaskets, and seals. Ensure alignment.

3.4.2 Dual pump. Remove, disassemble, clean, inspect, reassemble, and reinstall both pump assemblies. Clean and visually inspect all disassembled components for wear and deterioration. Renew the bearings, shaft seals, springs and gaskets.

3.4.2.1 Government's right for change out. The Contractor must be aware that the Government reserves the right to furnish a new dual rotary pump for installation in place of an existing dual rotary pump. If the Government exercises this right, the Contractor must dispose of the removed dual rotary pump in accordance with all applicable Federal, state, and local regulations.

3.4.3 Electric motors. Remove both pump motors to a suitable repair facility for overhaul. Completely disassemble, overhaul, test, and reassemble the motors in accordance with SFLC Std Spec 3020 and using TP 4034 as guidance. Renew the bearings and lubricate in accordance with manufacturer's instructions.

3.4.4 Valves, switches, and sensors. Perform the following for hydraulic valves, switches, sensors, and gauges.

DESCRIPTION	QTY
HPU Check Valves	4
Directional Control Valves	2
HPU Relief Valves*	2
Counterbalance Valves**	4
Sequence Valves***	2
Blocking Valves	2
Level/Temperature Sensors	2
Pressure Switches	2
Pressure Gauges	2
Cylinder Relief Valves*	2
System Ball Valves	11
System Check Valves	2

*Reset HPU and cylinder relief valve to lift at 2000 psi

** Reset counterbalance valves to 2000psi (1-1/4 turns CCW)

*** Sequence valves are set at the factory to prevent motor from exceeding max rated amps at full load conditions, DO NOT ADJUST.

3.4.4.1 HPU valve manifold assemblies. Disassemble, clean, inspect, bench test, and reassemble the Hydraulic Power Unit (HPU) valve manifold assemblies in accordance with SFLC Std Spec 5000, Appendix C, paragraph C2.4, consisting of the following components.

- Directional control valves
- HPU relief valves
- HPU check valves
- Counterbalance valves
- Sequence valves
- Blocking valves

3.4.4.2 Cylinder relief valves. Remove and test each cylinder relief valve to the designated lifting pressure in accordance with SFLC Std Spec 5000, Appendix C, and manufacturer's instructions. Ensure that each valve seats cleanly after pressure relief, and with no leakage. Adjust the relief pressure as necessary to obtain the lifting pressure. After adjustment, perform a final test to confirm each relief valve's lifting

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

pressure with the Coast Guard Inspector present. After successful testing, install the relief valves. Renew all O-rings and gaskets.

NOTE

For valve renewals, a separate lifting pressure test is not required provided the valve is supplied with all necessary documentation showing evidence of testing (shop set records from the manufacturer) at the correct lifting pressure.

3.4.4.2.1 Written certification. After completion of testing (and after any authorized repairs), submit written documentation listing each relief valve tested, the date of test, and testing facility to the COR.

3.4.4.2.2 Data plates. Affix to relief valve body an anodized aluminum test data plate using lock wire to lanyard to the valve body. Engrave the data plate with ¼-inch high letters stating the following:

- Vessel name and hull number.
- Valve identification number.
- Valve lifting pressure or set pressure.
- Date of test and set.
- Name of testing facility.

3.4.4.3 System ball and check valves. Remove, inspect, bench test, and reinstall ball valves and check valves. Valves must be tested to 1,775 psi as stated in Coast Guard Drawing 618 WMEC 800-002. Ensure that each check valve seats cleanly after pressure applied, and with no leakage. Ball valves must be pressure tested on both sides of the valve to ensure no leakage from the outlet side.

3.4.4.4 Pressure gauges. Remove, calibrate, and reinstall pressure gauges in accordance with SFLC Std Spec 5000, Appendix C, Paragraph C2.5.

3.4.4.5 Switches and sensors. Remove, test, and reinstall switches and sensors in accordance with SFLC Std Spec 5000, Appendix C, Paragraph C2.4.4.2.

3.4.4.6 Government's right for change out. The Contractor must be aware that the Government reserves the right to furnish new hydraulic valves, sensors, gauges and switches for installation in place of the existing. If the Government exercises this right, the Contractor must dispose of the removed valve(s), sensor(s), gauge(s) or switch(s) in accordance with all applicable Federal, state, and local regulations.

3.4.4.6.1 In the event the pressure gauge(s) are furnished new, the Contractor must ensure they are calibrated in accordance with SFLC Std Spec 5000, Appendix C, Paragraph C2.5.

3.4.5 Filters, strainers and magnetic plugs. Renew all hydraulic power unit filters and clean and inspect all strainers and magnetic plugs in accordance with TP 4034.

3.4.6 Hand pump assembly/fluid motor. Remove, disassemble, clean, inspect, reassemble, and reinstall the emergency hand pump assembly/fluid motor, including integral check valve assembly.

3.4.7 Hydraulic actuators. Disassemble, clean, inspect, and reassemble hydraulic cylinders or ram assembly, including spherical bearings, pins, connecting links, and retainers, as applicable, in accordance with TP 4034. Visually inspect all the components for wear and deterioration. Remove all burrs, nicks and scratches from sliding surfaces with emery cloth.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.4.7.1 Submit CFR with repair recommendations for any damage to ram or cylinder surfaces that cannot be corrected by minor dressing. Any resurfacing must be accomplished using WSC-1 Tungsten Carbide.

3.4.7.2 Reassemble with new gaskets, seals and o-rings.

3.4.8 Hydraulic reservoir cleaning. Clean the hydraulic reservoirs with a lint-free cloth to remove all foreign debris.

3.4.9 Mechanical linkages. Inspect all mechanical linkages for excessive play.

3.5 Reassembly/reinstallation. The Contractor must reassemble the steering system assemblies with new seals, O-rings, and gaskets, and restore the system to its original configuration as shown on Coast Guard drawings and tech pubs listed in Section 2 (References). Properly lubricate the system in accordance with manufacturer's recommendations, with lubricant conforming to MIL-G-21164, Symbol GMD.

3.6 Hydraulic fluid renewal. The Contractor must renew the system hydraulic fluid in accordance with TP 4034 and SFLC Std Spec 5000, Appendix C, Paragraph C2.1 (Fluids).

3.7 Alignment. The Contractor must accomplish alignment procedures for the steering system in accordance with TP 4034.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.8 Leak test. After completing all authorized mechanical (i.e. threaded, bolted, etc.) joint repairs, the Contractor shall test the steering system's operation using the system fluid at normal operating pressure. Ensure zero visible leakage from or deformation of mechanical parts by repairing all leaks and discrepancies. Submit a CFR.

3.9 Operational test, post repairs. After completion of work, the Contractor must thoroughly test, in the presence of the Coast Guard Inspector and demonstrate the steering gear to be in satisfactory operating condition. Submit a CFR.

NOTE

Local steering control in Non-Follow Up (NFU) mode from the Emergency Switch and Steering Box (ESSB) may not be sufficient to achieve speed requirements due to internal bypasses in the HPU. System operation from the Bridge in either Follow Up (FU) or NFU modes may be necessary.

3.9.1 Record the time it takes to run the rudders hard over from 35 deg right rudder to 35 deg left rudder, then repeat in the other direction. Verify that the rudder hard over time is not greater than 20 seconds for single HPU operation, or 10 seconds when operating both HPU's. Record the maximum pressure observed during rudder swing.

3.9.2 Record accuracy of helm commands and rudder angle indicators to actual tiller position at amidships, 5, 15, 25, and 35 degrees (left and right rudder). Verify that the error does not exceed 1/4 degree for rudder angles of 5 degrees and less and 1/2 degree for larger rudder angles.

3.9.3 Use an ammeter to record the amperage at startup and during rudder swing to three different positions - hard over port, amidships, and hard over starboard.

WARNING

Take all necessary precautions to prevent injury due to electric shock and potential arc-flash from energized equipment. Only necessary personnel (contracted or Ship's Force) may be present in the compartment while energized panels are open.

3.9.4 Submit a list of readings to the Coast Guard Inspector for the pump and motor units, including speeds, accuracy readings, discharge pressures, and motor current draw.

3.10 Dock trial. Ensure that the rudders travel a total of a 70-degree arc (35 degrees to port and to starboard) without chattering or binding. Document and fix all leaks detected.

4. NOTES

This section is not applicable to this work item.

WORK ITEM 8: Single Point Davit, Inspect and Service**1. SCOPE**

1.1 Intent. This work item describes the requirements for the Contractor to inspect and service the Single Point Davit system.

1.2 Government-furnished property.

MTI	ITEM DESCRIPTION	NSN/PN	QTY	ESTIMATED COST (\$/UNIT)
N	Rope, wire assembly with swage socket	PN: FL-8201-093 Item 1 NSN: 4010-01-602-8365	1 ea.	250.00
Y	Hook, release	PN: APR-356-CBH NSN: 4030-01-467-1005	1 ea.	4,340.00
Y	**Davit control console	PN: 60576 NSN: 2030-01-612-7381	1 ea.	44,000.00

**New or refurbished equipment that the Government may provide for installation in place of existing equipment.

2. REFERENCES**COAST GUARD DRAWINGS**

Coast Guard Drawing 618 WMEC 583-003, Rev E, Boat Davit Hydraulic Circuit

Coast Guard Drawing 627 WMEC 583-007, Rev D, D5700 CT SPD/RHI Arrg't & Dets. Port Side

COAST GUARD PUBLICATIONS

Coast Guard Technical Publication (TP) 2754, SWBS 583, August 2013, Hydraulic Power Unit (HPU)

Coast Guard Technical Publication (TP) 3240B, SWBS 583, May 2010, Hydraulic Power Unit – Motor Controller

Coast Guard Technical Publication (TP) 3485C, SWBS 583, Sept 2013, Single Point Boat Model D5700CT

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022, General Requirements

Surface Forces Logistics Center Standard Specification 0740 (SFLC Std Spec 0740). 2022, Welding and Allied Processes

Surface Forces Logistics Center Standard Specification 3020 (SFLC Std Spec 3020), 2022, Overhaul AC Electrical Motors

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

Surface Forces Logistics Center Standard Specification 5000 (SFLC Std Spec 5000), 2022,
Auxiliary Machine Systems

Surface Forces Logistics Center Standard Specification 6310 (SFLC Std Spec 6310), 2022,
Requirements for Preservation of Ship Structures

OTHER REFERENCES

MIL-PRF-17672E, Oct 2010, Hydraulic Fluid, Petroleum, Inhibited

3. REQUIREMENTS

3.1 General.

3.1.1 CIR. The Contractor must submit a CIR for the inspections listed in the following paragraph:

- 3.2 Maintenance particulars, Task 1 – Operate and Inspect, Initial
- 3.3 Operational and Weight Test Plan

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.3.1 Protection of fine surfaces. The Contractor must protect all fine surfaces in accordance with SFLC Std. Spec 5000.

3.1.3.2 Hydraulic system contamination protection. The Contractor must maintain existing hydraulic cleanliness in accordance with SFLC Std. Spec 5000.

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences).

3.1.5 Fluid handling. The Contractor shall remove and dispose of removed fluids from the affected piping system, in accordance with all applicable Federal, state, and local regulations.

WARNING

Do not drain ANY fluids, including fresh water, into any space, bilge, or exterior location.

3.2 Maintenance particulars. The Contractor must use Coast Guard Drawings 618 WMEC 583-003 and 627 WMEC 583-007, TP 3485C, TP 3240B, TP 2754, and SFLC Std Spec 5000 as guidance to accomplish the following tasks in Table 1 below. Unless otherwise specified in Other column, submit a CFR for all tasks.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

TABLE 1 - TASKS

#	TASK TYPE	QTY	COMPONENT OR ASSEMBLY	ADDITIONAL REQUIREMENTS	
				APPENDIX/PARA. FROM SFLC STD SPEC 5000	OTHER
1	Operate and Inspect, Initial	1	Single Point Davit	3.2.1 <u>Operate and Inspect</u>	Accomplish prior to repairs. Submit a CIR. See paragraph 3.1.1 in Std Spec 5000.
2	Sample and Test, Initial	1	Hydraulic fluid	C2.1.3 <u>Sample and test</u>	N/A
3	Op and Weight Test	1	Single Point Davit	B2.7 <u>Davits</u> The following tests are required: B2.7.1.1 <u>No Load Test</u> B2.7.1.2 <u>Static Load Test</u> (Conditional, see paragraph 3.3.1 of this Work Item) B2.7.1.3 <u>Winch Brake/Modified Static Load Test</u> B2.7.1.4 <u>Dynamic Overload Test</u> B2.7.1.5 <u>Rated Load Test</u>	Accomplish after repairs. See paragraphs 3.1.1, 3.2.8 and 3.1.11 in Std Spec 5000, and see paragraph 3.3 of this Work Item for amplifying information. <u>Test loads:</u> Static load - 11,400 lbs (if required) Winch brake/modified static load – 8,550 lbs at maximum jib outreach (14 ft-6 in) Dynamic overload – 7,125 lbs Rated load – 5,700 lbs
4	Service and Inspect	1	Boom tip sheave assembly	3.2.2 <u>Service and inspect</u> A2.3 <u>Mechanical load bearing and mechanical power transmission component inspections</u>	N/A
5	Service and Inspect	1	Rope tension switch assembly	3.2.2 <u>Service and inspect</u>	N/A
6	Service and Inspect	1	Anti-2-block assembly	3.2.2 <u>Service and inspect</u>	N/A
7	Service and Inspect	1	Constant tension winch assembly, including • Manifold assembly • Load hydraulic motor • Winch brake • Winch gear reducer • CT hydraulic motor	3.2.2 <u>Service and inspect</u> A2.3 <u>Mechanical load bearing and mechanical power transmission component inspections</u> C2.4 <u>Valves and manifolds</u> and applicable sub-paragraphs	Maintain Grade A cleanliness. See paragraph 3.1.7 in Std Spec 5000. Set the following valves in accordance with TP 3485C (hydraulic fluid must be at operating temperature): • Winch Counterbalance Valve – 830 psi pilot pressure (3,000 psi relief pressure) • Winch Sequence Valve – 1,200 psi

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

#	TASK TYPE	QTY	COMPONENT OR ASSEMBLY	ADDITIONAL REQUIREMENTS	
				APPENDIX/PARA. FROM SFLC STD SPEC 5000	OTHER
					CT Clutch Pressure Reducing Valve – 800 psi Renew CT winch gear oil (CAT 8T9572)
8	Service and Inspect	1	Winch down stop assembly	3.2.2 <u>Service and inspect</u>	N/A
9	Renew	1	Hook assembly	N/A	Submit all certification documentation supplied with hook assembly to COR. NOTE: If certification documentation is missing, a static load or pull test of the hook is required.
10	Service and Inspect	1	Jib boom assembly	3.2.2 <u>Service and inspect</u> A2.3 <u>Mechanical load bearing and mechanical power transmission component inspections</u>	Set the following valves in accordance with TP 3485C (hydraulic fluid must be at operating temperature): Boom Counterbalance Valve – 875 psi pilot pressure
11	Service and Inspect	1	Jib boom hinge pin assembly	3.2.2 <u>Service and inspect</u> A2.3 <u>Mechanical load bearing and mechanical power transmission component inspections</u>	N/A
12	Service and Inspect	1	Hydraulic cylinder assembly	3.2.2 <u>Service and inspect</u> A2.3 <u>Mechanical load bearing and mechanical power transmission component inspections</u> A2.4 <u>Fine surface inspections</u>	Maintain Grade A cleanliness. See paragraph 3.1.7 in Std Spec 5000.
13	Service and Inspect	1	Drive gears, pinion gears, and gear bearing	D2.4.1 <u>Open gearing lubrication</u>	Mobil Gearlube 375 NC
14	Service and Inspect	2	Swing drive, including - Hydraulic motor - Swing brake - Swing gear reducer	3.2.2 <u>Service and inspect</u>	Maintain Grade A cleanliness. See paragraph 3.1.7 in Std Spec 5000. Set the following valves in accordance with TP 3485C (hydraulic fluid must be at operating temperature): Swing Dual Counterbalance Valve – 450 psi pilot

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

#	TASK TYPE	QTY	COMPONENT OR ASSEMBLY	ADDITIONAL REQUIREMENTS	
				APPENDIX/PARA. FROM SFLC STD SPEC 5000	OTHER
					pressure (2,000 psi relief pressure) Renew swing drive gear oil (80W-90)
15	Service and Inspect	1	Control console, including: Control valve assembly • Inlet section • Swing section • Boom section • CT winch section • Winch section	3.2.2 <u>Service and inspect</u> C2.4 <u>Valves and manifolds</u> and applicable sub-paragraphs	Maintain Grade A cleanliness. See paragraph 3.1.7 in Std Spec 5000. Set the following valves in accordance with TP 3485C (hydraulic fluid must be at operating temperature): • Relief Valve (Console) – 2,900 psi
16	Service and Inspect	2	Accumulators	3.2.2 <u>Service and inspect</u> C2.6 <u>Gas-charged accumulators</u>	Maintain Grade A cleanliness. See paragraph 3.1.7 in Std Spec 5000. Accomplish hydrostatic test of the accumulator in accordance with Std Spec 0740 paragraph C2.2.5.1. Fabricate and install label plate with test date, test pressure and name of testing facility. • Hydrostatic test pressure – 2,750 psi Charge accumulator with nitrogen. • Accumulator precharge pressure – 1,300 psi
17	Service and Inspect	1	Hand pump assembly	3.2.2 <u>Service and inspect</u>	Maintain Grade A cleanliness. See paragraph 3.1.7 in Std Spec 5000.
18	Calibrate	2	Control console gauges	C2.5 <u>Gages</u>	N/A
19	Calibrate	2	HPU gauges	C2.5 <u>Gages</u>	N/A
20	Service and Inspect	1	HPU electric motor	N/A	Perform initial inspection in accordance with SFLC Std Spec 3020 section 3.3. Lubricate motor bearings and pump/motor shaft coupling.
21	Service and Inspect	1	Electric motor controller	N/A	Clean interior of controller cabinet.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

#	TASK TYPE	QTY	COMPONENT OR ASSEMBLY	ADDITIONAL REQUIREMENTS	
				APPENDIX/PARA. FROM SFLC STD SPEC 5000	OTHER
					Inspect interior components for burnt spots, fraying, overheating, damage, loose connections. Tighten any loose connections.
22	Service and Inspect	1	Hydraulic power unit (HPU) including: • Main hydraulic pump assembly • Solenoid operated pump control valve • Relief valve • Reservoir • Immersion heater	3.2.2 <u>Service and inspect</u> C2.4 <u>Valves and manifolds</u> and applicable sub-paragraphs	Maintain Grade A cleanliness. See paragraph 3.1.7 in Std Spec 5000. Clean breather filter. Drain and clean reservoir interior. Renew access cover gaskets. Clean suction strainer. Check immersion heater for continuity. Set the following valves in accordance with TP 2754 (hydraulic fluid must be at operating temperature): • Main System Relief Valve – 2,750 psi Set hydraulic pump compensator to 2,500 psi.
23	Service and Inspect	1	Return filter assembly	3.2.2 <u>Service and inspect</u>	Renew filter element. Maintain Grade A cleanliness. See paragraph 3.1.7 in Std Spec 5000.
24	Renew	1	Wire rope assembly	D2.2 <u>Wire rope assemblies</u>	Submit pull test certification documents supplied with wire rope assembly to COR.
25	Renew	1	Hydraulic fluid	C2.1.1 <u>Renewal</u>	2110-TH per MIL-PRF-17672
26	NDE	1	SPD pedestal	3.2.5 <u>NDE</u>	NDE all external welds of the pedestal weldment
27	Preserve	1	SPD pedestal	3.2.4 <u>Preservation</u>	SFLC Std Spec 6310. Renew access cover gaskets and fasteners.
28	Full Preserve	1	Single Point Davit	3.2.4 <u>Preservation</u>	Preserve 220 sq ft of damaged coatings on SPD as directed by Coast Guard Inspector in accordance with SFLC Std Spec 6310. Follow with 100%

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

#	TASK TYPE	QTY	COMPONENT OR ASSEMBLY	ADDITIONAL REQUIREMENTS	
				APPENDIX/PARA. FROM SFLC STD SPEC 5000	OTHER
					topcoat. See paragraph 3.2.4.3.2 in Std Spec 5000.
29	Groom and Lubricate	1	Single Point Davit	3.2.6 <u>Groom and lubricate</u>	N/A
30	Fabricate and Install	1	Label plate	B2.9 <u>Label plates</u>	N/A

3.3 Operational and Weight Test Plan. Contractor must submit, via a CIR, a Critical Lift Plan that includes arrangements/geometries of weight handling equipment (and all other data required by any pertinent local instructions) for approval.

3.3.1 Static Load Test. If a Change Request has been approved for repair or modification of structural members, the Single Point Davit assembly must be subjected to a static load test in accordance with SFLC Std Spec 5000 paragraph B2.7.1.2 (Static load test) except the test load must not be suspended from the davit hook. The test load must be applied using synthetic round-slings (or equivalent) wrapped around the davit structure in the vicinity of the davit head with the boom fully extended at maximum outreach (14 ft-6in).

3.4 Touch-up preservation. The Contractor must prepare and coat all new and disturbed exterior and interior surfaces, as applicable, to match existing adjacent surfaces in accordance with SFLC Std Spec 6310, (Touch-ups and minor coating repairs).

4. NOTES

This section is not applicable to this work item.

WORK ITEM 9: Sewage Discharge and Vacuum Pumps, Renew**1. SCOPE**

1.1 Intent. This work item describes the requirements for the Contractor to renew the sewage discharge and vacuum transfer pumps.

1.2 Government-furnished property.

MTI	ITEM DESCRIPTION	NSN/PN	QTY	ESTIMATED COST (\$/UNIT)
N	Sewage Discharge Pump	NSN: 4320-01-273-9350	2 ea.	\$4,719.00
N	Sewage Vacuum Transfer Pump	NSN: 4320-01-519-3163	2 ea.	\$4,719.00

2. REFERENCES**COAST GUARD DRAWINGS**

Coast Guard Drawing 618 WMEC 593-001, Rev C, Diagram - MSD System
 Coast Guard Drawing 618 WMEC 593-002, Rev F, Arrg't.MSD System
 Coast Guard Drawing 618 WMEC 593-050, Rev A, General Arrangement Marine Sanitation Device Compartment

COAST GUARD PUBLICATIONS

Coast Guard Technical Publication (TP) 3241A, SWBS 593, June 2011, Vacuum Sewage System
 Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022, General Requirements
 Surface Forces Logistics Center Standard Specification 3020 (SFLC Std Spec 3020), 2022, Overhaul AC Electrical Motors
 Surface Forces Logistics Center Standard Specification 6310 (SFLC Std Spec 6310), 2022, Requirements for Preservation of Ship Structures

OTHER REFERENCES

The Society for Protective Coatings (SSPC) Surface Preparation Specification No. 1 (SSPC-SP-1), 2015, Solvent Cleaning
 The Society for Protective Coatings (SSPC) Surface Preparation Specification No. 3, (SSPC-SP-3), 2018, Power Tool Cleaning

3. REQUIREMENTS

3.1 General. The Contractor must refer to the Coast Guard drawings and Tech Pub listed in Section 2 (References) for guidance in accomplishing this work item.

3.1.1 CIR.

None.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

WARNING

Raw sewage is a health hazard. Good personal hygiene by those servicing or in any way coming into contact with components in the Sewage System is necessary. PPE including rubber gloves, rubber boots, rubber coveralls and a face shield will help minimize personal contact with raw sewage.

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include, but are not limited to the following:

- Sewage contents
- Structural supports
- Sewage tanks
- Toilets
- Miscellaneous sewage piping and components
- Flexible hoses in sewage piping

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.2 Operational test, initial. Prior to commencement of work, the Contractor must witness Coast Guard personnel perform an initial operational test of all items or shipboard devices to be disturbed, used, repaired, or altered, to demonstrate existing operational condition. Submit a CFR.

3.3 Removal. The Contractor must remove the designated sewage pumps in accordance with Tech Pub 3241. Before removing the pumps, flush with seawater removing residual sewage from pumps and adjacent piping. While this work item does not require opening and entering the sewage tank, it does require sufficient cleaning of pumps and attached piping to lower levels of toxic, noxious and explosive gases to a safe level.

WARNING

It is imperative that hazardous gases are maintained at safe levels. Continue to monitor for hazardous gases while personnel are working in the area of the sewage collection tank (VCHT). Additional PPE may be necessary should hazardous gas approach maximum allowable levels.

3.4 Foundation preservation. The Contractor must wire brush or power tool clean the pump foundations and the area under the pump foundations to approximately 1 foot away from the foundations to remove loose paint and rust while pumps are removed. Feather all edges. Clean the areas in accordance with SSPC SP-3. Solvent wipe the areas in accordance with SSPC SP-1. Paint the prepared areas with one coat of epoxy paint to match the existing system as described in SFLC Std Spec 6310.

3.5 Installation. The Contractor must install the Government provided sewage and discharge pump assemblies in accordance with Tech Pub 3241. Renew all fasteners, flange gaskets and seals disturbed at pump/motor interfaces, as well as, gaskets and seals associated with other shipboard piping joints that have been disturbed as a result of performing this work item. Clean gasket mating surfaces before installing new gaskets. Verify flexible coupling(s) are properly aligned. Correct all discrepancies and submit CFR.

3.6 Leak test. After completing all authorized mechanical (i.e. threaded, bolted, etc.) joint repairs, the Contractor must test the sewage system's operation using the system fluid at normal operating pressure. Ensure zero visible leakage from or deformation of mechanical parts by repairing all leaks and discrepancies. Submit a CFR.

NOTE

System tightness test may be conducted with seawater. If so, discharge sea water from sewage tank to maximum extent possible using system pumps before declaring system ready for service.

3.7 Operational test, post repairs. After completion of work, the Contractor must thoroughly test, in the presence of the Coast Guard Inspector and demonstrate all items or shipboard devices that have been disturbed, used, repaired, altered, or installed to be in satisfactory operating condition. Submit a CFR.

3.8 Touch-up preservation. The Contractor must prepare and coat all new and disturbed surfaces to match existing adjacent surfaces in accordance with SFLC Std Spec 6310, (Touch-ups and minor coating repairs.)

4. NOTES

This section is not applicable to this work item.

WORK ITEM 10: Grey Water Holding Tanks, Clean and Inspect**1. SCOPE**

1.1 Intent. This work item describes the requirements for the Contractor to clean and inspect the following tank(s):

TABLE 1 – TANKS

TYPE OF TANK	LOCATION	CAPACITY - 95% (GALLONS)	LOW SUCTION (GALLONS)
Grey Water Tank	4-84-0-Q	360	20
Grey Water Tank (fwd)	3-32-0-A	150	10

1.2 Government-furnished property.

None.

2. REFERENCES**COAST GUARD DRAWINGS**

Coast Guard Drawing 618 WMEC 85-181, Rev G, Booklet of General Plans

COAST GUARD PUBLICATIONS

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022,
General Requirements

OTHER REFERENCES

ASTM International (ASTM) D1330, 2015, Standard Specification for Rubber Sheet Gaskets

3. REQUIREMENTS

3.1 General.

3.1.1 CIR.

None.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.3.1 Plug all inlet and outlet piping in the tank(s) to prevent contaminants from entering. Use plugs with an attached lanyard, ring or other system that will ensure plugs are not lost in the pipe openings.

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include, but are not limited to the following:

- Piping.
- Pump(s).

3.2 Plug log. The Contractor must keep a written record of all plugs put in any tank vents. A separate list must be kept for each tank being entered.

3.2.1 Ensure that all plugs are removed from each tank upon completion of work in the tank.

3.2.2 The plug log must be available to the Coast Guard Inspector when the inspector is performing his close-out inspection on each tank.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.3 Operational test, initial. Prior to commencement of work, the Contractor must witness Coast Guard personnel perform an initial operational test of all items or shipboard devices to be disturbed, used, repaired, or altered, to demonstrate existing operational condition. Submit a CFR.

3.4 Service disruption. When grey water is disrupted due to Contractor repairs, the Contractor must refer to SFLC Standard Spec 0000 par 3.2.11 to provide required temporary facilities.

3.5 Cleaning. The Contractor must accomplish the following for the tank(s) listed. The Contractor must refer to Coast Guard Drawing 618 WMEC 85-181 for guidance.

3.5.1 Content removal. Remove and dispose of all contents, fluids, and/or residues in accordance with all applicable Federal, state, and local regulations

3.5.2 Cleaning requirements. Remove manhole cover(s). Clean all tank structure's interior surfaces free of all foreign materials, sediment, and sludge. Remove all persistent residues, taking care not to damage the tank coating system. Remove cleaning media and residues continuously from the tank during the washing process. Remove any residual wash media and wipe up residual moisture with clean lint-free cloths. Collect, contain, and dispose of all wash media, residues, and cleaning materials in accordance with all Federal, state, and local regulations. Clean all tank vent lines to their termination points at the top of the stack. Remove and clean the eductors and level switches inside of the tank(s). Reinstall the eductors and level switches upon completion of tank cleaning. Use new gaskets and o-rings to install/reinstall all removed/disturbed components.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.6 Inspection. The Contractor must visually inspect all interior surfaces, including, but not limited to bulkheads, floor and overhead plating, structural members, manhole cover surfaces, fasteners and gasket seating surfaces. Submit the “Tank and Void Assessment Form” via CFR (see paragraph 4.2 of the Work Item titled “General Requirements”). Electronic PDF version of this form will be furnished by the COR upon request. Include the following, as applicable:

- Tank structural condition.
- Inaccessible areas.
- Condition of tank coating, including measurements taken, percentage, location, and type of coating failure (not applicable for stainless steel tanks).
- Tank level indicator (TLI), vacuum and/or float switch condition.
- Suction and discharge piping and vent line condition.
- Fastener material (stainless steel) and condition.
- Zinc anode condition (remaining percentage).

3.7 Control panel assembly. The Contractor must open and vacuum clean the control panel assembly. Inspect the control panel assembly for any indications of overheating or loose wiring or connections. Submit a CFR

3.8 Closing. The Contractor must notify the COR at least 24 hours prior to closing the tank(s) and ensure tank closure is accomplished in the presence of the Coast Guard Inspector. After satisfactory inspection by the Coast Guard Inspector, and completion of all authorized repairs, close the manhole cover(s) with new gasket material conforming to ASTM D1330.

3.8.1 Renew 100% of nylon insert/nylock nuts and washers.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.9 Operational test, post repairs. After completion of work, the Contractor must thoroughly test, in the presence of the Coast Guard Inspector and demonstrate all items or shipboard devices that have been disturbed, used, repaired, altered, or installed to be in satisfactory operating condition. Submit a CFR.

3.9.1 The Contractor must adjust the set point on each of the vacuum pressure switches (as applicable) to the set points noted previously.

3.9.2 The Contractor must verify operation of the low and high level switches/alarms and that the pumps cycle from lead to lag status during operation. Demonstrate proper operation of tank TLIs to prove satisfactory operating condition.

3.9.3 Upon completion of testing and, in the presence of the Coast Guard Inspector, the Contractor must pump tank(s) to the limit of the ship’s installed pumps.

4. NOTES

This section is not applicable to this work item.

WORK ITEM 11: Sewage Piping, Clean and Flush

1. SCOPE

1.1 Intent. This work item describes the requirements for the Contractor to clean the sewage piping system.

1.2 Government-furnished property.

None.

2. REFERENCES

COAST GUARD DRAWINGS

Coast Guard Drawing 618 WMEC 593-001, Rev C, Diagram-MSD System

Coast Guard Drawing 618 WMEC 593-002, Rev F, Arrg't. MSD System

COAST GUARD PUBLICATIONS

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022,
General Requirements

OTHER REFERENCES

ASTM International (ASTM) D1330, 2015, Standard Specification for Rubber Sheet Gaskets

3. REQUIREMENTS

3.1 General.

3.1.1 CIR.

None.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include, but are not limited to the following:

- Sewage pumps
- Toilets

3.2 Contamination prevention. The Contractor must take all precautions to prevent contamination of personnel and spaces in accordance with all applicable Federal, state, and local regulations.

3.3 Personnel qualification. The Contractor must ensure that personnel accomplishing this work are qualified and experienced in operating the pressurized water system and handling the chemicals. For each operator/cleaning technician, submit documentation of applicable experience and training obtained within the last twelve months along with the Cleaning Plan.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.4 Operational test - initial. Prior to commencement of work, the Contractor must witness Coast Guard personnel perform an initial operational test of all items or shipboard devices to be disturbed, used, repaired, or altered, to demonstrate existing operational condition. Submit a CFR.

3.5 Cleaning plan. Submit the written plan for chemical cleaning to the COR before work is to commence. The procedure must include products to be used, safety precautions, disposal requirements, sequence of events, etc. Submit a MSDS to the COR for all chemicals proposed for use. Changes to the chemical cleaning plan as written, need to be approved by the COR (and Facilities).

CAUTION

Although the Coast Guard prefers pressurized water as the cleaning fluid, the Contractor may propose chemical cleaning as an alternative, providing that the proposed chemical cleaning agent is environmentally safe, suitable for use in marine sewage piping application, and pre-approved by the COR.

The chemicals used in the cleaning (including cleaning chemicals, neutralizing compounds, and defoaming chemicals) must not cause any significant detrimental effects to the sewage piping system or any other system components. Due to the fact that system piping has historically been difficult to clean by pressure washing only, chemical cleaning is usually required to successfully complete the cleaning process.

3.5.1 Procedure requirements. The Contractor must ensure that the procedure includes the following:

- Methods of cleaning.
- All safety precautions required during cleaning operations.
- List of qualified personnel who will operate machinery or handle chemicals (see paragraph 3.3 (Personnel qualification) herein).
- Locations in the sewage piping where cleaning will take place, and any additional fittings necessary.
- Sequence of each location that ensures all piping sections will be cleaned and all foreign debris removed.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.5.2 Plan submittal. The Contractor must submit the written plan to the COR for approval at least 96 hours prior to commencing cleaning operations. Changes to the chemical cleaning plan as written, need to be approved by the COR (and local Facilities).

3.6 Clean and flush. The Contractor must clean and flush all sewage piping (approximately 1000 linear feet) as shown on Coast Guard Drawings 618 WMEC 593-001 and 593-002.

3.6.1 Pumps and valves. Replace system tank valve(s) with temporary spool piece(s) before cleaning. Visually inspect system pumps and valve(s); and submit a CFR. Upon completion of work, reinstall the removed tank valve(s) with new gaskets.

3.6.2 Cleaning. Continue cleaning until all of the following conditions are met:

- All visible calcium carbonate deposits, solid deposits and build-up are removed from pipe walls.
- Discharge water from the piping being cleaned is free of all visible scale and deposits.

3.6.3 Inspect the piping interior using a borescope in the presence of the COR, to verify that all solid deposits visible to the unmagnified eye have been removed. Continue the cleaning process until all visible solid deposits are removed from the pipe walls.

3.6.4 Flush twice the volume of the system cleaned with water to include 3 repeated pH tests between 6 and 8. The flushing water shall be collected and disposed by the Contractor.

3.7 Waste disposal. The Contractor must dispose of all cleaning fluids and debris in accordance with all applicable Federal, state, and local regulations. Remove all unused chemicals from USCG property immediately upon completion of work item. Do not drain any fluids (including fresh water) into any space, bilge, or exterior location.

3.8 Gasket renewal. The Contractor must reinstall all removed valves and fittings with new gasket material conforming to ASTM D1330.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.9 Operational test – post repairs. After completion of work, the Contractor must thoroughly test, in the presence of the Coast Guard Inspector and demonstrate all items or shipboard devices that have been disturbed, used, repaired, altered, or installed to be in satisfactory operating condition. Submit a CFR.

3.9.1 Leak test. After all system components are reinstalled, the Contractor must test all disturbed piping for leaks, as follows, and submit a CFR:

- Plug all system openings (except the highest) and fill system with water to the point of overflow. Ensure that the water level does not go down (without adding any water) for sufficient time to inspect the entire system (no less than 15 minutes).
- Closely monitor the system for leaks. Repair all leaks detected.
- Repeat test and inspection until no leaks are detected.

4. NOTES

This section is not applicable to this work item.

WORK ITEM 12: Grey Water Piping, Clean and Flush

1. SCOPE

1.1 Intent. This work item describes the requirements for the Contractor to clean the grey water piping system.

1.2 Government-furnished property.

None.

2. REFERENCES

COAST GUARD DRAWINGS

Coast Guard Drawing 618 WMEC 528-001, Rev L, Arr. Of Plumbing Sys & Deck Drains

Coast Guard Drawing 618 WMEC 528-002, Rev B, Diagram of Plumbing System & Deck Drains

COAST GUARD PUBLICATIONS

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022,
General Requirements

OTHER REFERENCES

None

3. REQUIREMENTS

3.1 General.

3.1.1 CIR.

None.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include, but are not limited to the following:

- Grey water pumps

3.2 Contamination prevention. The Contractor must take all precautions to prevent contamination of personnel and spaces in accordance with all applicable Federal, state, and local regulations.

3.3 Personnel qualification. The Contractor must ensure that personnel accomplishing this work are qualified and experienced in operating the pressurized water system and handling the chemicals. For each operator/cleaning technician, submit documentation of applicable experience and training obtained within the last twelve months along with the Cleaning Plan (see paragraph 3.5.6.2).

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.4 Operational test, initial. Prior to commencement of work, the Contractor must witness Coast Guard personnel perform an initial operational test of all items or shipboard devices to be disturbed, used, repaired, or altered, to demonstrate existing operational condition. Submit a CFR.

3.5 Piping hydrojet cleaning. The Contractor must perform the following work:

3.5.1 The Contractor must clean and flush all grey water piping (approximately 500 linear feet) as shown on Coast Guard Drawings 618 WMEC 528-001 and 528-002.

3.5.2 Prior to commencing work, coordinate with the Coast Guard Inspector. Determine required down times for affected piping system. Determine the feasibility/need for the piping system to be split to minimize system down time.

3.5.3 With the aid of ship's force, split the plumbing drain system fore and aft by closing isolation valves in the drainage system. Work on only one section of the plumbing drain system at a time to allow use of toilet and shower facilities in the other section of the system by the ship's duty section.

3.5.4 Using the referenced Coast Guard drawings as guidance, hydro blast the internal surfaces of all of the plumbing drain piping. Hydro blast pressure must be at least 2500 psig at the discharge nozzle in all piping to ensure removal of all salts and scale from piping internal surfaces.

NOTE

Ship's force will provide an assistant to the Contractor to show the Contractor the location of clean-out connections within the plumbing drain system.

3.5.4.1 Open each of the clean out connections as required to clean and hydro blast all of the internal piping within the system. Catch any fluid that drains from the clean out connections when it is opened and clean up any spills using bleach to disinfect the spill after cleaning.

3.5.4.2 It may be necessary for the Contractor to install additional clean-out connections to access all portions of the plumbing drain system. If additional clean-out connections are needed, a separate specification item in this specification package must be authorized to install additional clean-out connections.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.5.4.3 Empty and clean all connected grease traps, and dispose of waste in accordance with all Federal laws and regulations.

3.5.4.4 Hydro blast cleaning water may be collected in the ship's sewage system and disposed of via the ship's sewage shore tie connections.

3.5.4.5 Empty and clean all condensate drain piping, and dispose of waste in accordance with all Federal laws and regulations.

3.5.5 Clean until all of the following conditions are met:

- All visible calcium carbonate deposits, solid deposits, grease and build-up are removed from pipe walls.
- Discharge water from the piping being cleaned is free of all visible scale and deposits.

3.5.5.1 Inspect the piping interior using a borescope in the presence of the COR, to verify that all solid deposits visible to the unmagnified eye have been removed. Continue the cleaning process until all visible solid deposits are removed from the pipe walls.

3.5.6 In the event that hydroblasting alone does not clean piping to required conditions, Contractor must use chemical cleaning methods.

3.5.6.1 Ensure that chemical cleaners do not damage the environment, heat exchanger or the vessel.

3.5.6.2 Submit the written plan for chemical cleaning to the COR for approval 96 hours before work is to commence. The procedure must include products to be used, safety precautions, disposal requirements, sequence of events, etc. Submit a MSDS to the COR for all chemicals proposed for use. Changes to the chemical cleaning plan as written, need to be approved by the COR (and Facilities).

3.5.6.3 Chemical cleaning waste water disposal. Dispose of all cleaning fluids and debris in accordance with all applicable Federal, state, and local regulations. Remove all unused chemicals from USCG property immediately upon completion of work item. Do not drain any fluids (including fresh water) into any space, bilge, or exterior location.

- Sequence of each location that ensures all piping sections will be cleaned and all foreign debris removed.
- Flush twice the volume of the system cleaned with water to include 3 repeated pH tests between 6 and 8. The flushing water shall be collected and disposed by the Contractor.

3.6 Pumps and valves. The Contractor must replace system tank valve(s) with temporary spool piece(s). Visually inspect system pumps and valve(s); and submit a CFR. Upon completion of work, reinstall the removed tank valve(s) with new gaskets.

3.7 Gasket renewal. The Contractor must reinstall all removed valves and fittings with new gasket material conforming to applicable referenced drawings.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.8 Operational test, post repairs. After completion of work, the Contractor must thoroughly test, in the presence of the Coast Guard Inspector and demonstrate all items or shipboard devices that have been disturbed, used, repaired, altered, or installed to be in satisfactory operating condition. Submit a CFR.

3.8.1 Leak test. After all system components are reinstalled, the Contractor must test all disturbed piping for leaks, as follows, and submit a CFR:

- Plug all system openings (except the highest) and fill system with water to the point of overflow. Ensure that the water level does not go down (without adding any water) for sufficient time to inspect the entire system (no less than 15 minutes).
- Closely monitor the system for leaks. Repair all leaks detected.
- Repeat test and inspection until no leaks are detected.

4. NOTES

This section is not applicable to this work item.

WORK ITEM 13: Tanks, Grey Water Holding, Preserve, Partial – OPTION ITEM

1. SCOPE

1.1 Intent. This work item describes the requirements for the Contractor to prepare and preserve the following tank(s):

TABLE 1 – TANKS

TYPE OF TANK	LOCATION	CAPACITY - 95% (GALLONS)	LOW SUCTION (GALLONS)	% OF TANK COATING REPAIR
Grey Water	4-84-0-Q	360	20	33
Grey Water (fwd)	3-32-0-A	150	10	33

1.2 Government-furnished property.

None.

2. REFERENCES

COAST GUARD DRAWINGS

Coast Guard Drawing 618 WMEC 85-181, Rev G, Booklet of General Plans

COAST GUARD PUBLICATIONS

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022,
General Requirements

Surface Forces Logistics Center Standard Specification 6310 (SFLC Std Spec 6310), 2022,
Requirements for Preservation of Ship Structures

Surface Forces Logistics Center Standard Specification 8636 (SFLC Std Spec 8636), 2022,
Temporary Hull Accesses

OTHER REFERENCES

None

3. REQUIREMENTS

3.1 General.

3.1.1 CIR.

None.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.3.1 The Contractor must plug all inlet and outlet piping in the tank(s) to prevent contaminants from entering. Use plugs with an attached lanyard, ring or other system that will ensure plugs are not lost in the pipe openings. Maintain a plug accountability log outside the tank to prevent any of the installed temporary plugs from being lost inside the tank or forgotten inside at tank closure. Submit this log to the COR after completion of work item.

3.1.4 Interferences. The Contractor shall handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include, but are not limited to the below-listed:

- Piping.
- Pump(s).

3.2 Temporary access openings. Due to limited access to work areas, the Contractor may, with express permission of the KO (via submission of a CFR), cut access holes to facilitate accomplishment of the work specified herein. Perform all work required to open and close the access openings in accordance with SFLC Std Spec 8636.

NOTE

Requirements for tank opening and closing, content disposal, and inspection are covered in the clean and inspect item.

3.3 Substrate inspection. After completion surface preparation and before coating application, the Contractor must perform a visual inspection of the prepared substrate, and submit a CFR.

3.4 Surface preservation. The Contractor must accomplish the following tasks for the tanks listed in paragraph 1.1 (Intent):

3.4.1 Remove and retain the tank manhole cover(s).

3.4.2 The Contractor must prepare and coat the designated tank interior surfaces, using the system specified for "Tanks and Voids (Grey Water, Sewage, and CHT Tanks), Option II", in SFLC Std Spec 6310, Appendix B (Cutters and Boat Interior Paint Systems).

NOTES

1. A profile suitable for over coating would be similar to what is produced by abrading the coating with 100-grit paper.

3.4.2.1 The Contractor must prepare and coat all new and disturbed surfaces to match existing adjacent surfaces in accordance with SFLC Std Spec 6310, (Touch-ups and minor coating repairs.)

NOTE

Surfaces being preserved are considered “critical-coated surfaces”.

3.5 In-process quality control. The Contractor must abide by all the safety, preservation, and quality control requirements specified in SFLC Std Spec 0000, paragraph 3.2.4.2 (In-process QC measures for “critical-coated surfaces”).

4. NOTES

This section is not applicable to this work item.

WORK ITEM 14: Temporary Services, Heating and Cooling – OPTION ITEM

1. SCOPE

1.1 Intent. This work item describes the requirements for the Contractor to providing temporary heating and cooling services, in the spaces listed in Table 1.

TABLE 1: CONDITIONED SPACES

SPACE	COMPARTMENT	HEATING/COOLING DESIGN TEMPERATURE (F)	APPROX AREA (SQ. FT)
Radio	02-56-1-C	65/80	250
CIC	02-56-2-C	65/80	180
Control Booth	2-136-0-C	65/80	195
I.C. & Gyro	3-72-0-C	65/80	168
Wardroom	1-80-0-L	65/80	273
Crews Mess	1-121-0-L	65/80	527
C.P.O. Mess	1-93-0-L	65/80	183
Crews Berth'g	1-32-0-L	65/80	560
Crews Berth'g	1-52-0-L	65/80	465
Crews Berth'g	2-32-01-L	65/80	310
Crews Berth'g	2-52-01-L	65/80	464

1.2 Government-furnished property.

None.

2. REFERENCES

COAST GUARD DRAWINGS

Coast Guard Drawing 618 WMEC 401-001, Rev AP, I.C. & Gyro Room General Arrangement

Coast Guard Drawing 618 WMEC 601-003, Rev K, General Arrangement – Second and Third Decks

Coast Guard Drawing 618 WMEC 601-004, Rev K, General Arrangement – Main & 01 Deck

COAST GUARD PUBLICATIONS

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022,
General Requirements

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

Surface Forces Logistics Center Standard Specification 8635 (SFLC Std Spec 8635), 2022,
Temporary Services

OTHER REFERENCES

None

3. REQUIREMENTS

3.1 General.

3.1.1 CIR.

None.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences).

3.2 Temporary cooling. The Contractor must provide temporary heating and cooling for the spaces listed in Table 1, in accordance with Standard Spec 8635, and using Coast Guard Drawings 618 WMEC 401-001, 618 WMEC 601-003, and 618 WMEC 601-004 as guidance. The spaces must be conditioned within the heating and cooling temperatures shown in Table 1, and for the duration of any work item that requires the ship's heating or cooling system to be down. The doors to secure spaces cannot be left open in order to accommodate portable ducting. The Contractor must submit a CFR with detailed plan for providing temporary heating and cooling for approval to the COR 72 hours prior to Arrival Conference.

4. NOTES

This section is not applicable to this work item.

WORK ITEM 15: Whistle Timer, Replace

1. SCOPE

1.1 Intent. This work item describes the requirements for the Contractor to remove the Kahlenberg whistle timer model M-411 and replace it with the Kahlenberg whistle timer model M-522 in the pilothouse, (compartment 03-62-0-C).

1.2 Government-furnished property.

MTI	ITEM DESCRIPTION	NSN/PN	QTY	ESTIMATED COST (\$/UNIT)
N	Whistle Timer	NSN: 6645-01-564-0569 PN: M-522	1 ea.	\$1,326.00
N	Cable, Power, Electrical, Type DSGU-4***	NSN: 6145-01-202-2795 PN: M24643/15-02UN	245 ft.	\$325.85
N	Cable, Power, Electrical, Type TSGU-4***	NSN: 6145-01-201-9498 PN: M24643/16-02UN	125 ft.	\$207.50
N	Cable, Power, Electrical, Type FSGU-4***	NSN: 6145-01-210-2344 PN: M24643/17-02UN	30 ft.	\$54.30

***Government-furnished property, which is to be supplied by either the vessel or the C4IT Service Center.

2. REFERENCES

COAST GUARD DRAWINGS

Coast Guard Drawing 618 WMEC 401-004, Rev BC, Pilothouse Arrangement

Coast Guard Drawing 618 WMEC 443-001, Rev C, Elementary Wiring Diagram Whistle Control System CKT "W"

Coast Guard Drawing 618 WMEC 443-006, Rev A, Whistle Control System Install/Removal Wiring Diagram

COAST GUARD PUBLICATIONS

Coast Guard Technical Publication, 4039, SWBS 443, Whistle Timer, Models M-522 and M-411, Installation, operation and Maintenance Instructions

Surface Forces Logistics Center Standard Specification 0000, (SFLC Std Spec 0000), 2022, General Requirements

Surface Forces Logistics Center Standard Specification 3041, (SFLC Std Spec 3041), 2022, Shipboard Electrical Cable Test

Surface Forces Logistics Center Standard Specification 3042, (SFLC Std Spec 3042), 2022, Shipboard Electrical Cable Removal, Relocation, Splice, Repair and Installation

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

Surface Forces Logistics Center Standard Specification 6310, (SFLC Std Spec 6310), 2022,
Requirements for Preservation of Ship Structures

OTHER REFERENCES

None

3. REQUIREMENTS

3.1 General.

3.1.1 CIR.

None.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include, but are not limited to the following:

- Piping
- Insulation
- Cabling
- Foundation

3.1.5 Electrical requirements. The Contractor must accomplish all electrical work in accordance with SFLC Std Spec 3042 and test cables in accordance with SFLC Std Spec 3041.

3.2 Removal. The Contractor must accomplish all removals as shown on Coast Guard Drawing 618 WMEC 443-006 and using Coast Guard Drawings 618 WMEC 401-004 and 618 WMEC 443-001 as guidance.

3.3 Installation. The Contractor must accomplish the installation as shown on Coast Guard Drawing 618 WMEC 443-006 and using Coast Guard Drawings 618 WMEC 401-004, 618 WMEC 443-001 and TP 4039 as guidance.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.4 Operational test, post repairs. After completion of work, the Contractor must thoroughly test, in the presence of the Coast Guard Inspector and demonstrate all items or shipboard devices that have been disturbed, used, repaired, altered, or installed to be in satisfactory operating condition. Submit a CFR.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.5 Touch-up preservation. The Contractor must prepare and coat all new and disturbed surfaces to match existing adjacent surfaces in accordance with SFLC Std Spec 6310, (Touch-ups and minor coating repairs.).

4. NOTES

4.1 Standard Configuration Change Form. The Coast Guard Inspector or COR will complete the Standardized Configuration Change Form SFLC-ESD-47-Rev1 (available at link below or CG Portal -> SFLC -> SFLC Directives SFLC -> Forms Library -> SFLC-ESD

47_Rev1_Standardized_Configuration_Change) upon completion of this installation, and e-mail completed and signed form to D05-DG-SFLC-ESD-SSB-CMS-CDMM-MECPL@uscg.mil.

https://cg.portal.uscg.mil/units/sflc/SFLCDirectivesLibrary/SFLC-ESD-47_Rev1_Standardized_Configuration_Change.pdf

31410_CNJ_0821_210_270
REC_31410_210_270_210 WMEC 'A' Class (ALL) (0221)
S22_0014_31410_CKB_1225_618
S26_0004_31410_CKB_0126_618

WORK ITEM 16: Fan Room Decks, Preserve

1. SCOPE

1.1 Intent. This work item describes the requirements for the Contractor to preserve, paint and prime Fan Room (02-81-2-Q) and Fan Room (1-63-1-Q) decks.

1.2 Government-furnished property.

None.

2. REFERENCES

Coast Guard Drawing 618 WMEC 131-001, Rev M, 2nd & Main Deck Plating & Supports

Coast Guard Drawing 618 WMEC 136-001, Rev M, 01, 02 & Bridge Deck Plating & Supports

COAST GUARD PUBLICATIONS

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022,
General Requirements

Surface Forces Logistics Center Standard Specification 0740 (SFLC Std Spec 0740), 2022,
Welding and Allied Processes

Surface Forces Logistics Center Standard Specification 6310 (SFLC Std Spec 6310), 2022,
Requirements for Preservation of Ship Structures

OTHER REFERENCES

None.

3. REQUIREMENTS

3.1 General.

None.

3.1.2 Tech Rep.

Not applicable.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include, but are not limited to the following:

- Ducting
- Ventilation System

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.2 Operational test, initial. Prior to commencement of work, the Contractor must witness Coast Guard personnel perform an initial operational test of all items or shipboard devices to be disturbed, used, repaired, or altered, to demonstrate existing operational condition. Submit a CFR.

3.3 Substrate visual inspection. Upon completion of surface preparation and prior to application of primer coat (see 3.3 (Surface preservation)), the Contractor must perform a visual inspection of the prepared surfaces; submit a CFR.

3.3 Ultrasonic thickness (UT) measurement. The Contractor must take a total of 50 UT measurements in each fan room, for a total of 100 UT shots, in accordance with SFLC Std Spec 0740, Appendix C in locations designated by the Coast Guard Inspector and using Coast Guard Drawings 618 WMEC 131-001 and 618 WMEC 136-001 as guidance. Submit a CFR.

3.4 Surface preservation. The Contractor must prepare and coat 100 sqft per fan room for a total of 200 sqft of deck, to match existing adjacent surfaces, using the system specified for in SFLC Std Spec 6310, Appendix B (Cutter and Boat Interior Painting Systems).

3.4.1 Power tool clean to “bare metal” (SSPC-SP 11) with a minimum 1.0 mil anchor profile as the method of surface preparation.

3.4.2 Attach a suitable vacuum to the power tool equipment, to capture and contain all dust and paint debris.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.5 Operational test, post repairs. After completion of work, the Contractor must thoroughly test, in the presence of the Coast Guard Inspector and demonstrate all items or shipboard devices that have been disturbed, used, repaired, altered, or installed to be in satisfactory operating condition. Submit a CFR.

4. NOTES

This section is not applicable to this work item.

WORK ITEM 17: Deck and Bulkhead Plating, Renew

1. SCOPE

1.1 Intent. This work item describes the requirements for the Contractor to renew deck and bulkhead plating and associated covering located in the Laundry Room (1-20-0-Q) and Galley (1-146-0-Q) and to renew affected insulation in Engineers Workshop (2-140-1-Q).

1.2 Government-furnished property.

None.

2. REFERENCES

COAST GUARD DRAWINGS

Coast Guard Drawing 618 WMEC 120-002, Rev E, Misc Bhds Main Deck

Coast Guard Drawing 618 WMEC 131-001, Rev M, 2nd & Main Deck Plating & Supports

Coast Guard Drawing 618 WMEC 601-003, Rev K, General Arrangement – Second and Third Decks

Coast Guard Drawing 618 WMEC 601-004, Rev K, General Arrangement – Main & 01 Deck

Coast Guard Drawing 618 WMEC 634-001, Rev G, Deck Coverings

Coast Guard Drawing 618 WMEC 635-002, Rev J, Sheathing & Insulation

COAST GUARD PUBLICATIONS

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022, General Requirements

Surface Forces Logistics Center Standard Specification 0740 (SFLC Std Spec 0740), 2022, Welding and Allied Processes

Surface Forces Logistics Center Standard Specification 6310 (SFLC Std Spec 6310), 2022, Requirements for Preservation of Ship Structures

Surface Forces Logistics Center Standard Specification 6341 (SFLC Std Spec 6341), 2022, Install Interior Deck Covering Systems

OTHER REFERENCES

ASTM International (ASTM) F683, 2014, Standard Practice for Selection and Application of Thermal Insulation for Piping and Machinery

NAVSEA Drawing 804-5773931, Rev A, Acoustic & Thermal Insulation For Compartments Installation Details

3. REQUIREMENTS

3.1 General.

NOTE

Recommend sequencing this item with Work Item 21 Deck Covering, Interior, Wet, Renew and Work Item 22 Deck Drain Piping, Renew to avoid duplicating efforts.

3.1.1 CIR. The Contractor must submit a CIR for the inspections listed in the following paragraph:

- 3.2 Ultrasonic Thickness (UT) Measurement.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.4 Interferences. The Contractor shall handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include, but are not limited to the following:

- Washers and Dryers
- Deck Penetrations/Fittings
- Insulation
- Flooring
- Piping
- Wiring
- Galley Equipment
- Lockers and racks.

3.1.5 Surface preservation. The Contractor must prepare 47sqft of deteriorated Galley deck as designated by the Coast Guard Inspector.

3.1.5.1 Power tool clean to “bare metal” (SSPC-SP 11) with a minimum 1.0 mil anchor profile as the method of surface preparation.

3.1.5.2 Attach a suitable vacuum to the power tool equipment, to capture and contain all dust and paint debris.

3.2 Ultrasonic Thickness (UT) Measurement. The contractor must take a total of 25 UT measurements, in each location for a total of 50 UT shots, in accordance with SFLC Std Spec 0740, Appendix C as

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

designated by the Coast Guard Inspector and using the Coast Guard Drawings in Section 2 as guidance. Submit a CIR.

3.3 Operational test, initial. Prior to commencement of work, the Contractor must witness Coast Guard personnel perform an initial operational test of all items or shipboard devices to be disturbed, used, repaired, or altered, to demonstrate existing operational condition. Submit a CFR.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.4 Deck plating renewal. The Contractor must crop and renew deck plating indicated below, as designated by the Coast Guard Inspector using Coast Guard Drawings 618 WMEC 131-001, 618 WMEC 601-003 and 618 WMEC 601-004 as guidance.

- Laundry (1-20-0-Q) – 4sqft of 7.65# steel plating surrounding deck drain
- Galley (1-146-1-Q) – 5sqft of 7.65# steel plating.

3.5 Bulkhead plating renewal. The Contractor must crop and renew bulkhead plating indicated below, as designated by the Coast Guard Inspector using Coast Guard Drawings 618 WMEC 120

- Laundry (1-20-0-Q) – 2 sqft of 5.1# steel plating.

3.6 Deck covering installation particulars. The Contractor must perform all tasks specified in SFLC Std Spec 6341 and herein, to install a new covering system in the location(s) specified in Table 1 below. Use Coast Guard Drawings 618 WMEC 634-001 and 618 WMEC 655-001 as guidance.

NOTES

1. **The exposed deck surfaces are prepared and coated in accordance with SFLC Std Spec 6310. Refer to SFLC Std Spec 6341, Para 3.2.1.2 for additional information.**

TABLE 1 - DECKING SYSTEM

LOCATION	AREA (*SQFT)	DECK MTL (A/S**)	SYSTEM/ APPENDIX (SFLC STD SPEC 6341)	COVE BASE	SYSTEM COLOR	UNDERLAYMENT REQUIREMENT
Galley (1-146-1-Q)	25	S	Cosmetic polymeric epoxy covering MIL- PRF-24613 Type III (in accordance with SFLC Std Spec 6341 Appendix B)	N	See paragraph 3.5 (Deck covering color)	Renew.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

Laundry Room (1-20-0-Q)	25	S	Quarry Tile, 6x6, non-skid surface (in accordance with 627 WMEC 634-001) /SFLC Std Spec 6341 Appendix B	Y	See paragraph 3.5 (Deck covering color)	Renew.
----------------------------	----	---	---	---	---	--------

*Approximated.

**Note: A = Aluminum; S = Steel.

***See SFLC Std Spec 6341 for definition of cove base.

3.7 Deck covering color. The Contractor must submit a deck covering color chart to Coast Guard Inspector, for the purpose of color selection.

3.8 Insulation renewal. The Contractor must renew overhead insulation identified in Engineers Workshop (2-140-1-Q), as shown on Coast Guard Drawings 618 WMEC 131-001 and 618 WMEC 635-002.

3.8.1 Removal. Remove all existing insulation material.

3.8.2 Disposal. Dispose of all removed materials, in accordance with all applicable Federal, state, and local regulations.

3.8.3 Surface preservation. Prepare and coat all designated/exposed surfaces, including adjacent structural members, using the system specified for “Bulkheads and Overheads, Un-insulated Steel (Appearance not a factor, i.e., voids) and Insulated Steel, Option II”, in SFLC Std Spec 6310 in Appendix B (Cutter and Boat Interior Painting Systems).

NOTE

Power-tool cleaning to “Bare Metal”, in accordance with SSLC-SP 11, may be used as the surface preparation method, for the following situations:

- 1. Abrasive blasting is not permitted in location of work.**
- 2. Surfaces being preserved are considered too small to merit abrasive-blasting.**

3.8.4 Substrate inspection, visual inspection. Upon completion of surface preparation and prior to application of primer coat, the Contractor must visually inspect the prepared surfaces; submit a CFR.

3.8.5 Thermal insulation installation, unsheathed. The Contractor must install new un-faced thermal insulation material over plating surfaces and structural members as shown on NAVSEA Drawing 804-5773931. Coat the newly installed insulation using the system specified for “Insulation Surfaces, Fiberglass Sheet/Closed Cell PVC Foam” in SFLC Std Spec 6310, Appendix B (Cutter and Boat Interior Painting Systems).

3.9 Operational test, post repairs. After completion of work, the Contractor shall thoroughly test, in the presence of the Coast Guard Inspector and demonstrate all items or shipboard devices that have been disturbed, used, repaired, altered, or installed to be in satisfactory operating condition. Submit a CFR.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.10 Touch-up preservation, general. The Contractor must prepare and coat all new and disturbed surfaces to match existing adjacent surfaces in accordance with SFLC Std Spec 6310, (Touch-ups and minor coating repairs.)

3.11 Boundary test, generic. The Contractor shall verify the integrity of all boundaries affected by this work item using one of the methods described in SFLC Std Spec 0740, Appendix C. Submit a CFR.

4. NOTES

This section is not applicable to this work item.

S_53400_ESD_0921_SWIT
S23_0009_53400_CKB_1225_618
S25_0034_53400_CKB_1225_618
S25_0036_53400_CKB_1225_618

WORK ITEM 18: Steam System Valves and Piping, Renew

1. SCOPE

1.1 Intent. This work item describes the requirements for the Contractor to renew steam system valves as designated in Table 1, steam piping and insulation located in the Engine Room (4-108-0-E).

TABLE 1 – ENGINE ROOM STEAM SYSTEM VALVES

DESCRIPTION Size/ Type/Location	COAST GUARD BILL OF MATERIALS 618 WMEC 61	MATERIAL	CONNECTION/ RATED PRESSURE CLASS #	INDUSTRY STANDARD
2" Gate Valve (Boiler #2 Relief Piping)	Item 35	Carbon Steel	Welded / 2000 PSI	MSS SP-80
2" Gate Valve (Boiler #2 Relief Piping)	Item 35	Carbon Steel	Welded / 2000 PSI	MSS SP-80
1.5" Gate Valve	Item 36	Carbon Steel	Welded / 2000 PSI	MSS SP-80
1.25" Gate Valve	Item 37	Carbon Steel	Welded / 2000 PSI	MSS SP-80
2.5" Globe Valve (Boiler #1)	Item 31	Chrome Steel	Flanged / 750 PSI	MSS SP-80
2.5" Globe Valve (Boiler #2)	Item 31	Chrome Steel	Flanged / 750 PSI	MSS SP-80
2" Globe Valve (Boiler #2)	Item 32	Chrome Steel	Welded / 2000 PSI	MSS SP-80
1.25" Gate Valve (Deck Connection)	Item 186	Bronze	Flanged / 150 PSI	MSS SP-80

1.2 Government-furnished property.

None.

2. REFERENCES

COAST GUARD DRAWINGS

Coast Guard Bill of Materials 618 WMEC 61, Rev K, Arr. Stm., Feed & Conds. Sys. Piping

Coast Guard Drawing 618 WMEC 535-001, Rev N, Diagram Steam, Feed and Condensate System Piping

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

Coast Guard Drawing 618 WMEC 535-002, Rev N, Arr Stm Feed & Condensate System Piping

COAST GUARD PUBLICATIONS

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022, General Requirements

Surface Forces Logistics Center Standard Specification 0740 (SFLC Std Spec 0740), 2022, Welding and Allied Processes

Surface Forces Logistics Center Standard Specification 6310 (SFLC Std Spec 6310), 2022, Requirements for Preservation of Ship Structures

OTHER REFERENCES

American Society of Mechanical Engineers (ASME) B16.34, 2004, Valves-Flanged, Threaded, and Welding End

ASTM International (ASTM) F683, 2014, Standard Practice for Selection and Application of Thermal Insulation for Piping and Machinery

ASTM International (ASTM) F992, 2017, Standard Specification for Valve Label Plates

Manufacturers Standardization Society of the Valve and Fittings Industry (MSS), SP-58, 2018, Pipe Hangers and Supports – Materials, Design, Manufacture, Selection, Application and Installation

Manufacturers Standardization Society of the Valve and Fittings Industry (MSS) SP-61, 2003 Edition, Pressure Testing Of Steel Valves

Manufacturers' Standardization Society of the Valve and Fittings Industry (MSS) SP-80, 2008 Edition, Bronze Gate, Globe, Angle and Check Valves

3. REQUIREMENTS

3.1 General.

3.1.1 CIR.

None.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include, but are not limited to the following:

- Boilers
- Piping
- Insulation
- Steam

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.2 Fluid handling. The Contractor must drain and dispose of all residual fluids in the piping system in accordance with all Federal, state, and local rules and regulations.

3.3 Removal. The Contractor must remove each valve identified in Table 1 and immediately install blank flanges and gaskets over openings and secure each flange 180 degrees apart with at least two bolts.

3.4 Renewal. The Contractor must renew all valves identified in Table 1.

3.4.1 Equivalency. The Contractor must ensure all renewed valves, including Mil-Std valves, are commercial-standard type valves conforming to the applicable standard listed in Table 1. The Contractor must ensure each new valve is of identical material and equivalent to the valve it is replacing.

3.4.2 Inspection. The Contractor must visually inspect the piping and mounting arrangements and submit a CFR detailing any required modifications to accommodate the new valve(s).

3.5 Piping renewal particulars. The Contractor must accomplish the following tasks, as designated by the Coast Guard Inspector and using Coast Guard Drawings 618 WMEC 535-001 and 618 WMEC 535-002 as guidance:

- 15 linear feet of 1.5" steel blowdown piping for NR 2 Boiler, located in Engine Room (4-180-0-E).
- 12 linear feet of 1.25" steel piping located in the Engine Room (4-180-0-E).

3.5.1 Pipe hangers. Furnish, fit, and install new pipe hangers in accordance with MSS SP-58.

3.5.2 Pipe labeling. The Contractor must label affected piping as follows:

3.5.2.1 Stencil the following onto the pipe surfaces:

- Name of the piping system service.
- Destination, where feasible.
- Direction of flow, indicated by an arrow three inches long pointing away from the lettering (for reversible flow, point an arrow away from each end of the lettering).

3.5.2.2 Ensure all lettering and arrow(s) are as follows:

- In general, black color except white for dark-colored piping.
- Applied in conspicuous locations and preferably near control valves.

3.6 Installation. Upon completion of all authorized work, the Contractor must install all renewed valves with renewed gaskets.

3.6.1 Disposal. The Contractor must remove and dispose of all blank flanges and associated gaskets.

3.6.2 Secure. The Contractor must secure each valve installation with renewed bolting hardware.

3.6.3 Labeling. The Contractor must renew all missing and damaged valve label plates, and install new valve label plates on new valves, in accordance with ASTM F992.

3.7 Pipe flushing. The Contractor must flush all new and disturbed piping with clean fresh water until all debris is removed but no longer than five minutes. Ensure flushing fluid is directed to move scale and

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

foreign debris away from installed machinery to prevent possible damage upon operational testing. Submit a CFR documenting date and time of flushing process and level of pipe cleanliness.

3.7.1 Dispose of flushing fluid in accordance with all applicable Federal, state, and local regulations.

WARNING

Do not drain ANY Fluids (including fresh water) into any space, bilge, or exterior location.

3.8 Hydrostatic test. After all authorized repairs, the Contractor must hydrostatically test all new and disturbed piping and components of the steam system in accordance with SFLC Std Spec 0740, Appendix C, Hydrostatic Test. Ensure zero leakage from or permanent deformation of pressure-containing parts by repairing all leaks, deformations, and discrepancies. Submit a CFR.

3.9 Piping insulation installation. The Contractor must install 120 linear feet of new insulation materials over the exposed pipe surfaces at thicknesses appropriate to the application and temperature ranges specified in ASTM F683 Tables identified in Table 1 below and in accordance with details in NAVSEA Drawing 804-5959214:

- Associated pipe hangers
- Valves
- Fittings
- Flanges

CAUTION

Use glass cloth lagging only in high traffic areas where insulation is subject to damage.

TABLE 1 - PIPING SYSTEMS INSULATION INSTALLATION REFERENCES

PIPING SYSTEMS APPLICATION	TEMPERATURE RANGE	ASTM F683 TABLES
Interior gas, steam, hot water, and oil piping	125 to 1200 Deg. F	S1.1; S1.2; S1.4
Interior refrigerant, hot water, cold water, and chill water piping	-20 to +180 Deg. F	S1.1 and S1.5

3.9.1 Coat the newly installed insulation using the system specified for “Insulation Surfaces, Fiberglass Sheet/Closed Cell PVC Foam” in SFLC Std Spec 6310, Appendix B (Cutter and Boat Interior Painting Systems).

3.10 Touch-up preservation. The Contractor must prepare and coat all new and disturbed surfaces to match existing adjacent surfaces in accordance with SFLC Std Spec 6310, (Touch-ups and minor coating repairs.)

4. NOTES

This section is not applicable to this work item.

*S_5XXXX_PpngRnwl_SWIT_ESD_0423_SWIT
S23_0011_52100_CKB_1225_618
S24_0023_52100_CKB_0126_618*

WORK ITEM 19: Countermeasure Washdown Piping, Renew

1. SCOPE

1.1 Intent. This work item describes the requirements for the Contractor to renew designated Countermeasure Washdown (CMWD) piping located in the Sea Bag Locker (1-20-2-A) and Laundry (1-20-0-Q).

1.2 Government-furnished property.

None.

2. REFERENCES

COAST GUARD DRAWINGS

Coast Guard Bill of Materials 618 WMEC 8, Rev K, Arr Fireman, Sprink & Washdn Mn Dk & Abv

Coast Guard Drawing 618 WMEC 521-001, Rev H, Diagram Firemain Sprinkling & Washdown

Coast Guard Drawing 618 WMEC 521-002, Rev M, Arr of Firemain, Sprinkling & Washdown System Main Deck & Above

Coast Guard Drawing 618 WMEC 635-002, Rev J, Sheathing & Insulation

COAST GUARD PUBLICATIONS

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022, General Requirements

Surface Forces Logistics Center Standard Specification 0740 (SFLC Std Spec 0740), 2022, Welding and Allied Processes

Surface Forces Logistics Center Standard Specification 6310 (SFLC Std Spec 6310), 2022, Requirements for Preservation of Ship Structures

OTHER REFERENCES

None

3. REQUIREMENTS

3.1 General.

3.1.1 CIR.

None.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include but are not limited to:

- Insulation
- Shelving
- Ship's gear

3.1.5 Contamination prevention. The Contractor must take all precautions to prevent contamination of personnel and spaces in accordance with all applicable Federal, state, and local regulations.

3.2 Fluid handling. The Contractor must remove and dispose of removed fluids from the affected piping system, in accordance with all applicable Federal, state, and local regulations.

WARNING

Do not drain ANY fluids, including fresh water, into any space, bilge, or exterior location.

3.3 Piping renewal particulars. The Contractor must accomplish the following tasks, as designated by the Coast Guard Inspector and using Coast Guard Drawings 618 WMEC 521-001 and 618 WMEC 521-002 as guidance:

- Crop and renew 6 linear feet of 1" CuNi piping located in Sea Bag Locker (1-20-2-A) including 90° elbow (Line Item 19 on Coast Guard Bill of Materials 618 WMEC 8)
- Crop and renew 1 linear foot of 1" CuNi piping located in Laundry Room (1-20-0-Q)

3.3.1 Pipe hangers. Furnish, fit, and install new pipe hangers in accordance with MSS SP-58.

3.3.2 Pipe labeling. The Contractor must label affected piping as follows:

3.3.2.1 Stencil the following onto the pipe surfaces:

- Name of the piping system service.
- Destination, where feasible.
- Direction of flow, indicated by an arrow three inches long pointing away from the lettering (for reversible flow, point an arrow away from each end of the lettering).

3.3.2.2 Ensure all lettering and arrow(s) are as follows:

- In general, black color except white for dark-colored piping.
- Applied in conspicuous locations and preferably near control valves.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.3.4 Pipe flushing. The Contractor must flush all new and disturbed piping with clean fresh water until all debris is removed but no longer than five minutes. Ensure flushing fluid is directed to move scale and foreign debris away from installed machinery to prevent possible damage upon operational testing. Submit a CFR documenting date and time of flushing process and level of pipe cleanliness.

3.3.4.1 Dispose of flushing fluid in accordance with all applicable Federal, state, and local regulations.

WARNING

Do not drain ANY Fluids (including fresh water) into any space, bilge, or exterior location.

3.4 Testing. After all work has been completed, the Contractor must, in the presence of the Coast Guard Inspector, accomplish the following tasks, and submit a CFR:

3.4.1 Hydrostatic test. After all authorized repairs, the Contractor must hydrostatically test all new and disturbed piping and components of the affected piping system in accordance with SFLC Std Spec 0740, Appendix C, Hydrostatic Test. Ensure zero leakage from or permanent deformation of pressure-containing parts by repairing all leaks, deformations, and discrepancies. Submit a CFR.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.4.2 Operational test, post repairs. After completion of work, the Contractor must thoroughly test, in the presence of the Coast Guard Inspector and demonstrate all items or shipboard devices that have been disturbed, used, repaired, altered, or installed to be in satisfactory operating condition. Submit a CFR.

3.5 Touch-up preservation. The Contractor must prepare and coat all new and disturbed surfaces to match existing adjacent surfaces in accordance with SFLC Std Spec 6310, (Touch-ups and minor coating repairs.)

4. NOTES

This section is not applicable to this work item.

WORK ITEM 20: Engine Flywheel Disc Coupling, Renew**1. SCOPE**

1.1 Intent. This work item describes the requirements for the Contractor to renew the Thomas disc coupling on the No. 1 Main Diesel Engine.

1.2 Government-furnished property.

MTI	ITEM DESCRIPTION	NSN/PN	QTY	ESTIMATED COST (\$/UNIT)
N	***Thomas Disc Coupling	NSN: 3010-01-496-7051	1 ea.	

***Government-furnished property, which is to be supplied by either the vessel or the C4ISR Service Center.

2. REFERENCES**COAST GUARD DRAWINGS**

Coast Guard Drawing 618 WMEC 241-050, Rev A, Lufkin HSQ2724 Marine Gear Plan,
Installation – Output & Side Views

Coast Guard Drawing 618 WMEC 243-052, Rev -, Sectional Assembly Special No. 750 ST
Coupling

COAST GUARD PUBLICATIONS

Coast Guard Technical Publication (TP) 4648, Main Propulsion Plant (210' WMEC 'A' Class
only), SWBS 233, May 2024

Coast Guard Technical Publication (TP) 5453, Main Diesel Engine (MDE) – Clutch Assembly –
Model 28VC1000

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022,
General Requirements

Surface Forces Logistics Center Standard Specification 6310 (SFLC Std Spec 6310), 2022,
Requirements for Preservation of Ship Structures

OTHER REFERENCES

None.

3. REQUIREMENTS

3.1 General.

3.1.1 CIR.

Not applicable.

3.1.2 Technical Representatives. The Contractor must provide the services of a Qualified Technical Representative who is familiar with the Lufkin main reduction gear to accomplish the following on site:

- Advise on manufacturer's proprietary system information.
- Assist with the following installation and repair method(s): renewing the Thomas disc coupling.
- Ensure compliance with manufacturer's procedures and standards during system disassembly, inspection, and reassembly as applicable.

3.1.2.1 Ensure the Tech Rep has experience with the system/equipment stated above and demonstrated on their résumé.

3.1.2.2 Submit the name and résumé of the Tech Rep to the COR at the Arrival Conference.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include, but are not limited to the following:

- MDE
- Reduction gear
- Safety guards
- Shafting

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.2 Operational test, initial. Prior to commencement of work, the Contractor must witness Coast Guard personnel perform an initial operational test of all items or shipboard devices to be disturbed, used, repaired, or altered, to demonstrate existing operational condition. Submit a CFR.

3.2.1 MDE/MRG alignment check. The Contractor must determine existing alignment of quill shaft to MDE. Submit a CFR.

3.3 Coupling, renew. The Contractor must renew the No. 1 Main Diesel Engine flywheel Thomas Disc coupling, in accordance with TP 4648, Tab 7, Rexnord document 538-510 and using Coast Guard Drawings 618 WMEC 241-050, 618 WMEC 243-052 and TP 4648, Tab 7, Lufkin HSQ2724 as guidance.

3.3.1 Prior to beginning work, provide support for the quill shaft and clutch assembly.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.3.2 Disassemble clutch to the extent necessary to perform coupling hub removal and installation, using TP 4648, Tab 7, Lufkin HSQ2724 and TP 5453 as guidance.

3.3.2.1 Fabricate and install a temporary spacer bushing (as referenced in TP 4648, Tab 7, Lufkin HSQ2724 and Coast Guard Drawing 618 WMEC 241-050 and split as necessary) to hold the quill shaft concentric to the hollow high speed pinion.

3.3.2.2 Disassemble Thomas coupling and check the distance between end of quill shaft to the face of the counterbore in the flywheel, in accordance with Coast Guard Drawing 618 WMEC 241-050 note 6. This measurement should be $3-15/32'' +0, -1/64''$ (with the clutch spacing of $3/16''$ observed).

3.3.2.3 Measure parallelism and angularity of the coupling hub to flywheel. Acceptable tolerance for angular and parallel alignment are .001'' variation in distance between coupling/flywheel faces at the edges and .002'' eccentricity (TP 4648, Tab 7, Lufkin HSQ2724 Section II, paragraph 2.e).

3.3.3 Disassemble the coupling from the MDE flywheel.

3.3.4 Push the quill shaft back into the reduction gear.

3.3.5 Remove the coupling hub from the quill shaft.

3.3.6 Install the new coupling. Reassemble the coupling with plates. Check coupling contact percentage to the shaft

3.3.7 Bolt the coupling to the MDE flywheel.

3.3.8 Install the new coupling using TP 4648, Tab 7, Rexnord document 538-510 and Coast Guard Drawing 618 WMEC 243-052 as guidance. Ensure the clutch drum to clutch housing end plate gap of $3/16''$ is maintained when installing the coupling. Assemble the coupling with new disk pack.

3.3.9 Reassemble clutch using TP 4648, Tab 7, Lufkin HSQ2724 and TP 5453 as guidance.

3.3.10 After completion of the installation, verify the quill shaft alignment between the reduction gear and the MDE flywheel.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.4 Operational test, post repairs. After completion of work, the Contractor must thoroughly test, in the presence of the Coast Guard Inspector and demonstrate all items or shipboard devices that have been disturbed, used, repaired, altered, or installed to be in satisfactory operating condition. Submit a CFR.

3.5 Touch-up preservation. The Contractor must prepare and coat all new and disturbed surfaces to match existing adjacent surfaces in accordance with SFLC Std Spec 6310, (Touch-ups and minor coating repairs.)

4. NOTES

This section is not applicable to this work item.

*S_63410_0322_SWIT
S24_0006_63410_CKB_1225_618
S24_0007_63410_CKB_1225_618
S24_0008_63410_CKB_1225_618
S24_0009_63410_CKB_1225_618
S25_0047_63410_CKB_1225_618
S25_0048_63410_CKB_1225_618*

WORK ITEM 21: Deck Covering, Interior, Wet, Renew

1. SCOPE

1.1 Intent. This work item describes the requirements for the Contractor to renew wet and dry, interior deck covering system(s).

1.2 Government-furnished property.

None.

2. REFERENCES

COAST GUARD DRAWINGS

Coast Guard Drawing 618 WMEC 634-001, Rev G, Deck Coverings

COAST GUARD PUBLICATIONS

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022,
General Requirements

Surface Forces Logistics Center Standard Specification 6310 (SFLC Std Spec 6310), 2022,
Requirements for Preservation of Ship Structures

Surface Forces Logistics Center Standard Specification 6341 (SFLC Std Spec 6341), 2022, Install
Interior Deck Covering Systems

OTHER REFERENCES

None

3. REQUIREMENTS

3.1 General.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

NOTE

Recommend sequencing this item with Work Item 17 Deck Plating, Renew and Work Item 22 Deck Drain Piping, Renew to avoid duplicating efforts.

3.1.1 CIR.

None.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences).

3.2 Deck covering installation particulars. The Contractor must perform all tasks specified in SFLC Std Spec 6341 and herein, to install a new covering system in the location(s) specified in Table 1 below.

NOTES

- 1. The exposed deck surfaces are prepared and coated in accordance with SFLC Std Spec 6310. Refer to SFLC Std Spec 6341, Para 3.2.1.2 for additional information.**
- 2. Ensure the final surface condition of the deck is made "slip resistant" in accordance with manufacturer's installation procedures. Refer to SFLC Std Spec 6341, Para A2.1.2.2.**

TABLE 1 - DECKING SYSTEM

LOCATION	AREA (*SQFT)	DECK MTL (A/S**)	SYSTEM/ APPENDI X (SFLC STD SPEC 6341)	COVE BASE	SYSTEM COLOR	UNDERLAYMENT REQUIREMENT
Stateroom Head (2-72-0-L)	21	S	Cosmetic Polymeric Epoxy Resin, Type III (One- Step Epoxy System)/Ap pendix A	Y	See paragraph 3.4	Renew existing underlayment.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

Stateroom Head (2-72-2-L)	29	S	Cosmetic Polymeric Epoxy Resin, Type III (One-Step Epoxy System)/Appendix A	Y	See paragraph 3.4	Renew existing underlayment.
Stateroom Head (2-88-1-L)	31	S	Cosmetic Polymeric Epoxy Resin, Type III (One-Step Epoxy System)/Appendix A	Y	See paragraph 3.4	Renew existing underlayment.
Stateroom Head (2-88-2-L)	31	S	Cosmetic Polymeric Epoxy Resin, Type III (One-Step Epoxy System)/Appendix A	Y	See paragraph 3.4	Renew existing underlayment.
Chief's Head (2-99-0-L)	90	S	Cosmetic Polymeric Epoxy Resin, Type III (One-Step Epoxy System)/Appendix A	Y	See paragraph 3.4	Renew existing underlayment.
CO Stateroom Head (01-44-2-L)	35	S	Cosmetic Polymeric Epoxy Resin, Type III (One-Step Epoxy System)/Appendix A	Y	See paragraph 3.4	Renew existing underlayment.
Stateroom Head (01-87-1-L)	30	S	Cosmetic Polymeric Epoxy Resin, Type III (One-Step Epoxy System)/Appendix A	Y	See paragraph 3.4	Renew existing underlayment.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

Stateroom Head (01-55-0-L)	26	S	Cosmetic Polymeric Epoxy Resin, Type III (One-Step Epoxy System)/Appendix A	Y	See paragraph 3.4	Renew existing underlayment.
XO Stateroom Head (01-87-0-L)	25	S	Cosmetic Polymeric Epoxy Resin, Type III (One-Step Epoxy System)/Appendix A	Y	See paragraph 3.4	Renew existing underlayment.

*Approximated.

**Note: A = Aluminum; S = Steel.

***See SFLC Std Spec 6341 for definition of cove base.

3.3 Visual inspection. The Contractor must perform a visual inspection of all exposed deck surfaces, prior to priming deck surfaces. Submit a CFR.

3.4 Deck covering color. The Contractor must submit a deck covering color chart to Coast Guard Inspector, for the purpose of color selection.

4. NOTES

This section is not applicable to this work item.

WORK ITEM 22: Deck Drain Piping, Renew

1. SCOPE

1.1 Intent. This work item describes the requirements for the Contractor to renew designated Deck Drains and Deck Drain piping, located in the Galley (1-146-0-2) and Stateroom Head (2-72-0-L).

1.2 Government-furnished property.

None.

2. REFERENCES

COAST GUARD DRAWINGS

Coast Guard Bill of Materials 618 WMEC 88, Rev L, Arr of Plumbing Sys & Deck Drains
Coast Guard Drawing 618 WMEC 528-001, Rev L, Arr of Plumbing Sys & Deck Drains
Coast Guard Drawing 618 WMEC 528-002, Rev B, Diagram Of Plumbing System & Deck Drains

COAST GUARD PUBLICATIONS

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022, General Requirements
Surface Forces Logistics Center Standard Specification 0740 (SFLC Std Spec 0740), 2022, Welding and Allied Processes
Surface Forces Logistics Center Standard Specification 6310 (SFLC Std Spec 6310), 2022, Requirements for Preservation of Ship Structures

OTHER REFERENCES

American National Standards Institute/American Water Works Association (ANSI/AWWA) C652, 2019, Disinfection of Water-Storage Facilities

3. REQUIREMENTS

3.1 General.

None.

NOTE

Recommend sequencing this item with Work Item 17 Deck Plating, Renew and Work Item 21 “Deck Covering, Interior, Wet, Renew” to avoid duplicating efforts.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000. Known interferences include, but are not limited to, the following:

- Steam Table
- Sink(s)
- Work Table

3.2 Operational test, initial. Prior to commencement of work, the Contractor must witness Coast Guard personnel perform an initial operational test of all items or shipboard devices to be disturbed, used, repaired, or altered, to demonstrate existing operational condition. Submit a CFR.

3.3 Fluid handling. The Contractor must remove and dispose of removed fluids from the affected piping system, in accordance with all applicable Federal, state, and local regulations.

WARNING

Do not drain ANY fluids, including fresh water, into any space, bilge, or exterior location.

3.4 Piping renewal particulars. The Contractor must accomplish the following tasks, as designated by the Coast Guard Inspector and using Coast Guard Drawings 618 WMEC 526-001 and 627 WMEC 518-002 as guidance:

- Stateroom Head (2-72-0-L) below the sink.
 - 1 linear ft of 2” CuNi deck drain piping.
 - Deck drain assembly (Piece 85 on Coast Guard Bill of Materials 618 WMEC 88).
- Galley (1-146-0-Q).
 - 3 total linear ft of 2” CuNi deck drain piping.
 - 3 Deck drain assemblies (Piece 85 on Coast Guard Bill of Materials 618 WMEC 88).

3.4.1 Pipe hangers. Furnish, fit, and install new pipe hangers in accordance with MSS SP-58.

3.4.2 Pipe labeling. The Contractor must label affected piping as follows:

3.4.2.1 Stencil the following onto the pipe surfaces:

- Name of the piping system service.
- Destination, where feasible.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

- Direction of flow, indicated by an arrow three inches long pointing away from the lettering (for reversible flow, point an arrow away from each end of the lettering).

3.4.2.2 Ensure all lettering and arrow(s) are as follows:

- In general, black color except white for dark-colored piping.
- Applied in conspicuous locations and preferably near control valves.

3.4.3 Pipe flushing. The Contractor must flush all new and disturbed piping with clean fresh water until all debris is removed but no longer than five minutes. Ensure flushing fluid is directed to move scale and foreign debris away from installed machinery to prevent possible damage upon operational testing. Submit a CFR documenting date and time of flushing process and level of pipe cleanliness.

3.4.3.1 Dispose of flushing fluid in accordance with all applicable Federal, state, and local regulations.

WARNING

Do not drain ANY Fluids (including fresh water) into any space, bilge, or exterior location.

3.5 Testing. After all work has been completed, the Contractor must, in the presence of the Coast Guard Inspector, accomplish the following tasks, and submit a CFR:

3.5.1 Hydrostatic test. After all authorized repairs, the Contractor must hydrostatically test all new and disturbed piping and components of the steam system in accordance with SFLC Std Spec 0740, Appendix C, Hydrostatic Test. Ensure zero leakage from or permanent deformation of pressure-containing parts by repairing all leaks, deformations, and discrepancies. Submit a CFR.

3.5.2 Leak test. After completing all authorized mechanical (i.e. threaded, bolted, etc.) joint repairs, the Contractor must test the affected piping system's operation using the system fluid at normal operating pressure. Ensure zero visible leakage from or deformation of mechanical parts by repairing all leaks and discrepancies. Submit a CFR.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.5.3 Operational test, post repairs. After completion of work, the Contractor must thoroughly test, in the presence of the Coast Guard Inspector and demonstrate all items or shipboard devices that have been disturbed, used, repaired, altered, or installed to be in satisfactory operating condition. Submit a CFR.

3.6 Touch-up preservation. The Contractor must prepare and coat all new and disturbed surfaces to match existing adjacent surfaces in accordance with SFLC Std Spec 6310, (Touch-ups and minor coating repairs.)

4. NOTES

This section is not applicable to this work item.

WORK ITEM 23: Compartment(s), Interior, Lead Dust, Clean

1. SCOPE

1.1 Intent. This work item describes the requirements for the Contractor to clean lead dust in Flammable Liquid Stores (4-16-0-K), Storeroom (4-32-0-A), Handling Room (4-52-0-1-M) and Sewage Disposal Room (4-84-0-E).

1.2 Government-furnished property.

None.

2. REFERENCES

COAST GUARD DRAWINGS

Coast Guard Drawing 618 WMEC 111-001, Rev G, Shell Expansion Framing & CVK

Coast Guard Drawing 618 WMEC 191-001, Rev U, Solid Ballast Arrangement

COAST GUARD PUBLICATIONS

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022,
General Requirements

Surface Forces Logistics Center Standard Specification 6310 (SFLC Std Spec 6310), 2022,
Requirements for Preservation of Ship Structures

OTHER REFERENCES

ASTM International (ASTM) 6966, 2008, Standard Practice for Collection of Settled Dust
Samples Using Wipe Sampling Methods for Subsequent Determination of Metals

Code of Federal Regulations (CFR) Title 29, Part 1910, Jul 2008, Occupational Safety and Health
Standards

3. REQUIREMENTS

3.1 General.

3.1.1 CIR.

None.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures.

3.1.3.1 General. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.3.2 Specific. The Contractor shall abide by all lead and asbestos abatement compliance requirements, as specified in SFLC Std Spec 0000. Abide by the following additional safety precautions during the lead dust clean-up operation:

- Separate contaminated areas from other areas.
- Do not permit non-essential personnel in the work area.
- Work in one compartment at a time.
- Prevent dust from migrating to other areas, as follows:
 - Seal doors, hatches, and all other openings between the work area other areas with an airtight barrier, such as fire-rated polyethylene; seal both sides (inside the construction area, and inside the adjacent area) to provide a secondary dust barrier and prevent the doors and windows from being used (post alternative emergency exits, if applicable).
 - Ensure that the work area remain under negative pressure in relation to adjacent areas.

NOTE

Negative pressure means that more air is exhausted from the area than is supplied so that lead dust and asbestos particles are contained within the work area, and do not contaminate adjacent non-affected compartments. Exhaust air must be filtered with a suitable HEPA filter.

- Take, at a minimum, the following measures, to protect de-contamination workers:
 - Use a HEPA (high-efficiency particulate air) vacuum - never use a conventional vacuum. A HEPA vacuum removes 99.97% of particles that are less than 0.3 microns in size.
 - Never use compressed air; never dry sweep.
 - Workers must wear a respirator which is approved by NIOSH and has N100, P100 or R100 filters (the cartridges are usually purple); respirators must be fit-tested to insure proper seal, and employees must be medically screened and trained prior to wearing a respirator (see the OSHA Respirator Standard, 29 CFR 1910.134).
 - Workers must wear full-body protective clothing, head covering and shoes (or shoe covers).
 - Workers must not leave the work area without having gone through a proper decontamination process, to prevent spread of lead dust to un-affected areas.
 - Eating, drinking and smoking are prohibited in work areas.
 - Workers must wash hands and face before eating, drinking or smoking.
 - Workers must remove work clothes and shoes before leaving the work area, and seal work clothes in plastic.
 - Workers must shower and wash hair as soon as possible after leaving the work area.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

- Non-disposable work clothes must be washed separately from other clothes.

3.1.3.3 Remove protective covers, to allow for performance of lead dust cleaning and wipe sampling tasks, as specified in 3.2 (Clean-up particulars) and 3.3 (Clearance examination – post cleaning), respectively. Reinstall protective covers, after said tasks have been completed.

3.1.3.4 Remove and dispose of all protective covers, upon completion of work.

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences).

3.1.5 Certification requirements. The Contractor must ensure that all contractors and subcontractors performing cleanup or sampling must possess all applicable Federal and state certification licenses for lead work and lead sampling. Submit documentation of these certifications to the KO within 48 hours prior to commencing work.

3.2 Clean-up particulars. The Contractor must accomplish the steps provided below in the compartment(s) designated for clean up, in addition to any other location used as a temporary stowage location for the lead ingots using Coast Guard Drawings 618 WMEC 111-001 and 618 WMEC 191-001 as guidance.

3.2.1 Debris Removal. Remove all gross debris, paint chips, etc. using either a vacuum with a HEPA filter or by spraying the materials with water in a spray bottle and picking up chips or large pieces of lead contaminated debris by hand.

3.2.2 Vacuum Cleaning. Using a suitable HEPA vacuum, clean all affected surfaces, following the following guidelines:

- Begin that cleaning begins with high areas first – with overhead surfaces and bulkheads working downward.
- Vacuum all surfaces in the compartment.
- Work in the direction furthest from the entry door toward it.

3.2.3 Wet Cleaning. Following thorough HEPA vacuuming, wash all surfaces with a general all purpose cleaning detergent or a cleaner made specifically for lead following the same cleaning pattern (high to low/ furthest from and toward entrance). Change the cleaning solution as it becomes dirty. Rinse all areas with a fresh cloth/mop. Do not reuse contaminated mops and cloths. Use a three-bucket system for cleaning. (Detergent solution in first bucket/ mop ringer in second bucket/rinse water for mop in third). A wet, wipe and toss method is also acceptable and requires a large amount of clean rags placed into a bucket of detergent and water and a separate bucket with clean rags and rinse water. Use a detergent and water rag to wipe an area approximately 16 square feet and dispose of rag. Repeat the same procedure with a clean rinse rag and dispose of rag.

3.2.4 Vacuum Cleaning. Perform a HEPA vacuum again as specified in 3.2.2.

3.2.5 Waste Disposal. Properly dispose of lead contaminated materials, in accordance with all applicable Federal, state, and local regulations.

WARNING

1. Work Wet, Work Smart, and Work Clean. DO NOT GENERATE DUSTS. It is easier to effectively clean an area when dusts are not being generated to resettle on previously cleaned areas! Worker exposures may be high during wet sweeping.

2 A wet/dry HEPA unit is ideal for working with leaded dust clean up.

3. Lead-contaminated objects that are porous or materials that may suffer damage from water may not be able to be sufficiently decontaminated by these methods and should be discarded.

3.3 Clearance examination – post cleaning. The Contractor must accomplish the following tasks after completion of all cleaning operations:

3.3.1 Visual inspection. In the presence of the COR, conduct a visual inspection to ensure that no chips, dust, or cleaning material haze are present. Submit a CFR.

3.3.2 Wipe sampling. In accordance with ASTM 6966 and as designated by the Coast Guard Inspector conduct wipe sample clearance testing in ten locations for each designated compartment, to ensure there are no lead dust residues in excess of the below-listed concentrations. As designated by the COR, conduct clearance testing in two locations in any other location used as a temporary stowage location for the lead ballast ingots. Submit a CFR with sample results.

- 40 micrograms/square foot (mcg/ft²) - for berthing and/or food preparation areas.
- 200 micrograms/square foot (mcg/ft²) –for all other areas.

3.3.2.1 Ensure dust lead samples are analyzed by a laboratory certified by the National Lead Laboratory Accreditation Program (NLLAP) or the American Industrial Hygiene Association.

3.3.2.2 If laboratory analysis shows lead concentrations in excess of the thresholds specified above, then perform lead dust cleaning, and take subsequent wipe samples until the concentration of lead falls below the above standards.

NOTE

For a listing of certified laboratories, go to www.aiha.org.

3.3.2.3 The Contractor must be aware that the Coast Guard reserves the right to coordinate additional wipe clearance testing, at no cost to the contractor, to verify the sample results.

3.3.2.4 The Contractor must witness all additional wipe clearance testing conducted by the Coast Guard to verify where and how samples were collected – and thus, prevent contract disputes.

3.4 Lead Ingot Coating. The Contractor must coat 100% of exposed surfaces of lead ingots located in Flammable Liquid Stores (4-16-0-K) and Sewage Disposal Room (4-84-0-Q) as directed by the Coast Guard Inspector and in accordance with SFLC Std Spec 6310 Appendix C “High Build Epoxy”.

3.5 Touch-up preservation. The Contractor must prepare and coat all new and disturbed surfaces to match existing adjacent surfaces in accordance with SFLC Std Spec 6310, (Touch-ups and minor coating repairs.)

4. NOTES

This section is not applicable to this work item.

WORK ITEM 24: Ventilation Systems, Clean and Overhaul**1. SCOPE**

1.1 Intent. This work item describes the requirements for the Contractor to clean the ventilation system(s) identified in Table 1.

TABLE 1 – FAN UNITS

(ENTIRE OR PARTIAL)	SYSTEM DESIGNATION	TYPE	EXTENT OF CLEANING
Entire	1-160-2	Supply	Grease packed within fan unit and motor. All affected ducting for the galley (1-146-0-Q).
Entire	1-160-1	Exhaust	Grease packed within fan unit and motor. All affected ducting for the galley (1-146-0-Q).

1.2 Government-furnished property.

None.

2. REFERENCES**COAST GUARD DRAWINGS**

Coast Guard Drawing 618 WMEC 512-001, Rev D, Ventilation Equipment List

Coast Guard Drawing 618 WMEC 512-011, Rev J, Arrangement Ventilation & Air Conditioning Main Deck

COAST GUARD PUBLICATIONS

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022, General Requirements

Surface Forces Logistics Center Standard Specification 3020 (SFLC Std Spec 3020), 2022, Overhaul AC Electrical Motors

Surface Forces Logistics Center Standard Specification 5100 (SFLC Std Spec 5100), 2022, Clean Shipboard Ventilation Systems

OTHER REFERENCES

None

3. REQUIREMENTS

3.1 General.

3.1.1 CIR

None.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.3.1 Protective covering. The Contractor must provide protective covering in accordance with SFLC Spec 5100, subsection 3.1.3 Protective measures. Provide protective covering for all food preparation and serving surfaces in the immediate work area to prevent contamination.

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include, but are not limited to the following:

- Ducting screens
- Electric pre-heaters
- Hot/Chill water coils
- Overhead sheathing/panels
- Ventilation covers
- Piping
- Cabling

3.2 Operational test, initial. Prior to commencement of work, The Contractor must witness Coast Guard personnel perform an initial operational test of the designated fan and motor assemblies to demonstrate existing operational condition. Measure and record each fan's CFM output and compare readings against manufacturer's rated tolerances. Submit a CFR.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.3 Removal. The Contractor must remove designated fan and motor assemblies from the vessel and package it for delivery to and from a suitable repair facility, in accordance with ASTM D3951.

3.4 Overhaul requirements. The Contractor must accomplish the following tasks for supply and exhaust ventilation fans 1-160-1 and 1-160-2 and associated motor assemblies, using Coast Guard Drawings 618 WMEC 512-001 and 618 WMEC 512-011 as guidance.

3.4.1 Fan overhaul requirements. Clean the interior and exterior fan assembly surfaces, including housing, fan blade, and end bell surfaces by first using suction, then with a soapy water solution, and followed by a thorough rinsing of all metal surfaces. Ensure that there are no cleaning fluid residues or injurious effects on cleaned surfaces.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.4.1.1 Prepare and coat both fan casing surfaces using the coating system specified for “Machinery, Operating Temperatures Under 200°F, Unmachined Surfaces”, in SFLC Std Spec 6310, Appendix B (Cutters and Boats Interior Painting Systems). Select finish/top coat color to match existing adjacent surfaces.

3.4.1.2 After surface preparation and before surface coating, visually inspect the fan assembly surfaces including bearing surfaces for cracks, areas of distortion, and deterioration. Submit a CFR.

3.4.2 Motor overhaul requirements. Clean, inspect, and test designated motors in accordance with SFLC Std Spec 3020. Submit a CFR.

3.4.2.1 Preserve designated motor casings using the coating system specified for “Machinery, Operating Temperatures Under 200°F”, in SFLC Std Spec 6310, Appendix B (Cutters and Boats Interior Painting Systems). Select finish/top coat color to match existing adjacent surfaces.

3.4.2.2 If a Change Request has been released and authorized, accomplish each of following additional tasks

- Varnish-treat the motor
- Rewind the rotor
- Rewind the stator

3.5 Fan and motor assembly restoration. The Contractor must reassemble designated fan and motor assemblies and renew stainless steel hardware. Ensure angular misalignment of shaft couplings does not exceed a total indicator reading of 0.001 inch for each inch of radius of the coupling hub.

3.6 Dynamic balancing and documentation. The Contractor must dynamically balance the rotating elements along with associated equipment as a unit (i.e. fan blade and motor installed and in casing), in accordance with ISO 2953. Submit CFR with a written balance report.

3.7 Reinstallation. The Contractor must reinstall the fan/motor assemblies into its associated fan space using new rubber vibration dampers, gaskets, resilient mounts, fan connectors and rings (as applicable) in the ductwork. Restore all ductwork to original condition and configuration upon completion of dynamic balance. Reconnect electrical leads with nut and bolt lugs and wrap with electrical tape.

3.8 Cleaning. The Contractor must clean ventilation systems as identified and described in Table 1 in accordance with SFLC Std Spec 5100, and using Coast Guard Drawing (s) listed above as guidance.

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.9 Operational test, post repairs. After completion of work, the Contractor must thoroughly test, in the presence of the Coast Guard Inspector and demonstrate all items or shipboard devices that have been disturbed, used, repaired, altered, or installed to be in satisfactory operating condition. Submit a CFR.

4. NOTES

This section is not applicable to this work item.

WORK ITEM 25: Watertight Door, External, Renew**1. SCOPE**

1.1 Intent. This work item describes the requirements for the Contractor to renew the external watertight door identified in Table 1.

TABLE 1 - WATERTIGHT DOORS AND SCUTTLES

DESCRIPTION	LOCATION	DRAWING
QAWTD 1-77-2; 26" x 66" Diameter Quick-Acting Watertight Door, Steel, 8-Dog, Left Hinge	Passage (1-52-01-L) to Exterior	618 WMEC 167-001

1.2 Government-furnished property.

MTI	ITEM DESCRIPTION	NSN/PN	QTY	ESTIMATED COST (\$/UNIT)
N	QAWTD 1-77-2; 26" x 66" Diameter Quick-Acting Watertight Door, Steel, 8-Dog, Left Hinge (including associated coaming)	NSN: 2040-00-542-0201	1 ea.	8,958.71

2. REFERENCES**COAST GUARD DRAWINGS**

Coast Guard Bill of Materials 618 WMEC 327, Rev G, Watertight Doors, Hatches & Scuttles

Coast Guard Drawing 618 WMEC 167-001, Rev M, Schedule of Steel Doors, Hatches, Scuttles & Manholes

Coast Guard Drawing 618 WMEC 635-002, Rev J, Sheathing & Insulation

COAST GUARD PUBLICATIONS

Surface Forces Logistics Center Standard Specification 0000 (SFLC Std Spec 0000), 2022, General Requirements

Surface Forces Logistics Center Standard Specification 0740 (SFLC Std Spec 0740), 2022, Welding and Allied Processes

Surface Forces Logistics Center Standard Specification 6310 (SFLC Std Spec 6310), 2022, Requirements for Preservation of Ship Structures

OTHER REFERENCES

Commercial Item Description (CID) A-A-59316, 2016, Abrasive Materials; for Blasting
Military Specification MIL-A-22262B, March 1996, Abrasive Blasting Media Ship Hull Blast Cleaning
NAVSEA Drawing 167-7379842, Rev A, Procedure & Welding Sequence for Non-Ballistic, Watertight & Airtight Quick Acting or Individually Dogged Personnel Doors
The Society for Protective Coatings (SSPC)/NACE International (NACE) 2007, Joint Surface Preparation Standard SSPC-SP 10/NACE No. 2, Near-White Metal Blast Cleaning
The Society for Protective Coatings (SSPC) Surface Preparation Standard No. 11 (SSPC-SP 11), 2013, Power-Tool Cleaning to Bare Metal

3. REQUIREMENTS

3.1 General.

3.1.1 CIR.

None.

3.1.2 Tech Rep.

Not applicable.

3.1.3 Protective measures. The Contractor must furnish and install all protective measures in accordance with SFLC Std Spec 0000, paragraph 3.3.3 (Vessel component, space, and equipment protection).

3.1.4 Interferences. The Contractor must handle all interferences in accordance with SFLC Std Spec 0000, (Interferences). Known interferences include, but are not limited to, the following:

- Insulation
- Bulkhead
- Wiring
- IT equipment
- Piping
- Electrical panels

3.2 Renewal. The Contractor must crop, remove, and dispose of the doors and scuttles identified in Table 1 of this work item, including the associated coaming in accordance with SFLC Std Spec 0740 and using the Coast Guard drawing(s) listed under Section 2 (References) as guidance.

3.2.1 For watertight door renewals, inspect adjacent bulkhead structure for straightness prior to installation. Submit CFR with repair plan for any warped or twisted bulkhead structure resulting in a gap greater than 1/16" between the bulkhead plating and new door frame.

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

3.2.2 Install GFP doors and scuttles in place of those removed. When GFP doors and scuttles are not provided, the Contractor must fabricate and install a new door or scuttle. Use NAVSEA Drawing 167-7379842 and manufacturer instructions as guidance for installation.

3.2.3 Perform string test in accordance with Figure 5-A of NAVSEA Drawing 167-7379842. Submit CFR indicating satisfactory alignment.

3.2.4 Perform all necessary modifications not limited to relocation, fabrication and installation of a new securing device, and modifications to ensure all renewed items properly fit and function. At the direction of the Coast Guard Inspector, perform all necessary relocation and modification of securing latches.

3.2.5 Provide and install new gaskets and fasteners for each new installation identified in Table 1.

NOTES

- 1. Testing fitup of new door frame in structural cutout and balanced welding operations are crucial to ensuring proper alignment. Satisfactory operation of closure should be checked prior to, during, and after welding. Welding should be staggered around frame perimeter and on both sides of the closure to minimize distortion.**
- 2. Where possible, the door should be closed and dogged during welding.**
- 3. Geometric dimensioning and tolerance variances and minor hardware differences are to be expected with the Government-furnished closures. These variances and differences are not limited to the following: location and physical size of the hinge assemblies; location, physical size, and number of flush mounted pockets; location, size, and orientation of securing devices.**

3.3 Boundary test. Upon complete renewal of each structural closure, the Contractor must perform the following boundary tests in accordance with SFLC Std Spec 0740, Appendix C. Submit a CFR.

- Chalk test
- Water hose test

NOTE

Do not paint knife-edges, gaskets, or any moving parts; including dogs, nuts, wedges, spindles, yokes, packing, connecting rods and hinge pins.

3.4 Preservation. The Contractor must prepare and coat the surfaces of all installed items identified in Table 1 of this work item in accordance with Table 2 and as determined by the material to be preserved.

TABLE 2 – SURFACE PREPARATION AND COATING

	PREPARATION		COATING	
SURFACE	STEEL	ALUMINUM	STEEL	ALUMINUM
DOOR EXTERIOR/ R/	SSPC- SP10/NACE No. 2, using grit	Brush blast to bare metal with clean, fine aluminum oxide,	SFLC Std Spec 6310, Appendix A (Cutter and Boat Exterior Painting Systems) “Freeboard/ Superstructure/Mast” Freeboard/Superstruct	SFLC Std Spec 6310, Appendix A (Cutter and Boat Exterior Painting Systems) “Freeboard/

USCGC ACTIVE (WMEC-210A) DOCKSIDE AVAILABILITY FY2026

SCUTTLE TOP	conforming to MIL-A-22262 (1.5 to 2.5 mil anchor profile) -Or- SSPC-SP 11 (1.0 mil anchor profile)	garnet or equivalent inert material conforming to CI D A-A-59316, Type I & IV (1.0-1.5 mil anchor profile). -Or- Power tool clean, using non-metallic abrasive padding, to remove all coatings and contamination.	ure, Steel – Prone to Mechanical Damage or High Wear	Superstructure/Mast” Option I for Freeboard/Superstructure, Aluminum or Galvanized Steel
DOOR INTERIOR / SCUTTLE BOTTOM	SSPC-SP 11 (1.0 mil anchor profile)	Power tool clean, using non-metallic abrasive padding, to remove all coatings and contamination.	SFLC Std Spec 6310 , Appendix B (Cutter and Boat Interior Painting Systems) “Door, Joiner, Option I”	

3.4.1 Touch-up preservation. The Contractor must prepare and coat all disturbed surfaces to match existing adjacent surfaces in accordance with SFLC Std Spec 6310, paragraph 3.1.13 (Touch-ups and minor coating repairs.).

NOTE

Coast Guard personnel will operate all shipboard machinery and equipment.

3.5 Operational test, post repairs. After completion of work, the Contractor must thoroughly test (in the presence of the Coast Guard Inspector) and demonstrate all items or shipboard devices that have been disturbed, used, repaired, altered, or installed to be in satisfactory operating condition. Submit a CFR. The Contractor must demonstrate:

- Closures are properly secured to prevent accidental or unintentional movement.
- Securing latches adequately engage closures and positively lock into place without excessive force or manipulation by the operator.

3.6 Insulation, install. The Contractor shall install new insulation material on the interior side of the door to the same standard as the adjoining bulkhead, as specified on Coast Guard Drawing 618 WMEC 635-002. Coat the newly installed insulation using the system specified for “Insulation Surfaces, Fiberglass Sheet/Closed Cell PVC Foam” in SFLC Std Spec 6310, Appendix B (Cutter and Boat Interior Painting Systems).

4. NOTES

4.1 Damage control decals. Ship’s force will apply damage control decals.