

Q – Will the contractors be allowed to camp within the campground during construction?

A- Yes. While the campground is closed for construction the contractor will be allowed to use the campground. All in place campground rules will apply.

Q-When is the completion date?

A- 392 days from the notice to proceed.

Q- Will there be compaction requirements on the camping spurs?

A- Compaction requirements can be found in Section 323002.3.1.B

Q-What is the size of the new fiberglass tank?

A- The new underground fiberglass storage tank shall be 3,000 gallons.

Q- Is there an underground tank to be removed?

A- There is no underground tank to be removed. The above ground polyethylene tank is the only tank removal required.

Q- Is a new electrical service required?

A-Yes. Section 262210.1.2.D.1 Will be Amended to state:

1. Where work is to be performed by the power company that requires payment to the power company, payment will be made by the CONTRACTOR.

Q- Does the cattleguard need to be reset?

A- The cattleguard should be removed and placed adjacent to the entrance road for the Forest Service CM crew to pick up.

Q- Are the option items to be part of the bid?

A- All option items have been removed from the contract. The Specifications will be amended to remove them from the contract.

Q-The signs on plan drawing sheet C8.1 are included in the Base Item for signing. Does the FS still want the option signs?

A-Eliminate all signs and the road closure gate shown on plan drawing sheet C8.1.

Q- Does the sign-in sheet go to everyone?

A-Yes, it will be posted to SAM.gov

The below will be added to section 010150 – General Requirements

- Contractor must immediately report any dead or injured bats during project activities. Immediate report shall be made to the Contracting Officer's Representative, who shall notify the biologist.

Q-On page E5.2 it appears that the 100amp Panel L2 is fed by a 2pole 40amp breaker. Is this correct?

A-Yes, the table is correct.

Electrical panels are manufactured in standard BUS RATING sizes; 100 Amps, 225 Amps, 400 Amps, etc. In this case, a 100 Amp BUS RATING, which indicates "This panel can handle up to 100 amps safely."

The calculated load on this panel is 22.6 Amps. Therefore, we did not need to specify wiring that can handle 100 Amps. The 40 Amp MAIN BREAKER allows the wires to be sized appropriately while remaining protected from overload. The breaker will trip long before the ampacity of the wires is reached.

1. Please confirm whether asbestos or lead is present on this project, and if so, provide the relevant documentation.

There is not asbestos or lead paint present on this project.

2. Does this project require phasing?

No. The entire campground will be closed during construction. Once the campground is closed the contractor is expected to aggressively pursue completion of the work.

3. When do you anticipate on site work starting?

It is anticipated that work will begin late summer to early fall.

4. Are third party inspections and testing required?

Yes. Refer to sections 312250 and 321123 for density testing requirements.

5. Is permitting required?

Yes. All state and county permits are required.

6. Will the campground be closed to the public during construction?

Yes

7. Are soil boring reports available? If not, it will be assumed that excavation will be clear of rocks and obstructions.

Soil boring was not conducted. All excavations and trenching required is shallow. It is anticipated that rock will be encountered.

8. Is there a bulk water fill i.e. a hydrant or water source we can pump from for grading operations in close proximity?

Water for grading is the responsibility of the contractor. Bulk water is available in the City of Custer, SD.

9. Please provide staking data points for the project.

A control point is provided.

10. Are red, yellow, and blue tops required?

No. Construction tolerances can be found in the specifications. Red, yellow or blue tops do not need to be set if tolerances can be met by other methods.

11. Is an SWPPP required?

Yes

12. Are we to include pricing for Silt fence around the entire project?

Erosion control is to be provided as per section 312500 and the Contractor provided Storm Water Management Plan. Silt fence will not be required around the entire project. Pricing for erosion control is to be included in Base Item #1 General Requirements/Mobilization.

13. Is there a preferred model number for the pump house?

No

14. Is the contractor required to supply temporary power and water?

No. The campground will be closed for construction.