

SABINE DISTRICT OFFICE GEOTHERMAL HVAC REPLACEMENTS**- Schedule of Items -**

LOCATION	DESCRIPTION	QUAN	UNIT	COST	TOTAL
Sabine National Forest District Office 5050 TX-21, HEMPHILL, TX 75948	Units 1 and 4 Geothermal Heat Pumps: Remove and replace with new in-kind Trane brand or equal, 5 ton geothermal HVAC Heat Pump units in accordance with manufacturers requirements and to code standards, also with similar salient characteristics to meet or exceed that of the existing units, and connect to existing facilities, charge unit back to operating conditions, and bring back online to include charging water system, and any needed programming / computer controls. Installation shall include new programmable thermostats, and drain pans. Haul off and disposal of all debris and materials from demo and dispose off USFS property in accordance with state and federal laws	2	LS		
	(Option) Units 1 & 4 Circulation pumps: Remove and replace existing circulation pumps and replace with new pump equal to GeoFlo 2-pump pressurized flow center	2	LS		
	Total				