

EXHIBIT R - JMMU Target Designation Ref:

TAB D - Drainage (ditches, culverts & sump pumps)

		option task #9 (feet)	exclude grading (feet)	in base bid as part of target work (feet)			notes
drainage ditches							
Drainage Lane 3		446					
Drainage C30		121					
C36				636			is part of the base bid for work at this Cluster
C40		182					
BP44		616					
BP46		1,041					
MAT52		1,129					
MAT54		939					
MAT56		2,046					
MAT58		1,399					
MAT60		1,266					
SAT412		76					
SAT420 Exclude ditch graded in FY25			506				
SAT424		181					
SAT422		176					
SAT426		124					
SAT428		161					
SAT432		506					
SAT434		110					
SAT436		113					
SAT438		362					
SAT442		168					
SAT450		780					
SAT450a		835					
SAT452		191					
SAT454				405			is part of the base bid for work at this SAT
SAT456		414					
SAT 458 & 460				599			is part of the base bid for work at this SAT
SAT462		253					
SAT464		293					
SAT470		608					along a part of back side of MAT54
SAT484		224					
SAT486		485					
SAT496		222					
PC PJ2B		74					
TOTAL		15541	506	1640			

Drainage general note: all ditches to be regraded to V-ditch.

		option task #9 (feet)					notes
Culverts							
on lane 3, south of SAT456		38					south of SAT 456
J3E-B Culvert		918					Lane 3 in depression near East End of Lane.
J2E-B culvert		805					Lane 2, depression at East end of lane.
J1E-B Culvert		941					Lane 1, in depression near East end of lane.
J1E-A Culvert		58					Lane 1 at depression before East end of lane. Sheet CS-157 (pg 141 of 451) Area inlet on each end
J2E-A Culvert		58					Lane 2, depression at East end of lane. CS-156 (140 of 451) Area inlet on each end
J3E-A Culvert		64					Lane 3 in depression near East end of lane. sheet CS-171 (145 of 451). Area inlet on each end
J4D-A Culvert		56					Lane 4 in depression near East end of lane. Sheet CS-182 (150 of 451) contractor to verify if area inlet on north side.
SR-6 culvert		128					250-feet southeast of MAT54 Sheet SC-182 (150 of 451)
TOTAL		3066					

Culvert General Notes: Original drawing (Exhibit F) CS-208 missing contractor to field verify culvert size and area inlets.

Sumps

PC PJ4A	install new sump basin, pump, electrical to pump and plumbing. Install union at sump pump.
PC PJ5A	remove existing sump pump system, Remove 8-inches grade, install geotechnical fabric, install 6 inches ballast rock, install new sump basin, pump, electrical to pump and plumbing. Install union at sump pump.
PC PJ5B	remove existing sump pump system, Remove 8-inches grade, install geotechnical fabric, install 6 inches ballast rock, install new sump basin, pump, electrical to pump and plumbing. Install union at sump pump.
PC PJ7B	remove existing sump pump system, Remove 8-inches grade, install geotechnical fabric, install 6 inches ballast rock, install new sump basin, pump, electrical to pump and plumbing. Install union at sump pump.