

According to my original request for the Microbiology workstation project, vendor responses should not fall short of the necessary detailed information needed to properly evaluate whether the proposed workstations meet Microbiology's technical, biosafety, ergonomic, workflow, delivery, and installation requirements.

To ensure responses are complete, clear, and comparable, vendors should modify or clarify their submissions to address the full requirements below:

Microbiology Workstation Technical Requirements are the following:

General Laboratory Furniture Requirements

1. Work surfaces and applicable sink/cabinet areas must be constructed of stainless steel, phenolic resin, or equivalent laboratory-grade material.
2. Proposed materials must be non-porous, moisture-resistant, chemical-resistant, corrosion-resistant where applicable, and able to withstand routine hospital/laboratory disinfection.
3. Materials must support contamination control and help reduce bacterial, viral, and fungal contamination risk for testing personnel.
4. Vendor must clearly identify the proposed material for each workstation, countertop, sink top, cabinet, shelf, analyzer table, microscope table, and rolling cart.
5. Ordinary high-pressure laminate should not be proposed unless the vendor can document that it meets the required laboratory-grade chemical resistance, moisture resistance, and disinfection durability.

Room 1 Workstations

6. One L-shaped workstation approximately 72" L west side x 56" L north side x 26" D x 41" H.
7. One worktable approximately 60" L x 26" D x 41" H.
8. One worktable approximately 66" L x 26" D x 41" H.
9. Each Room 1 workstation/table must include a laboratory-grade work surface, lower shelf for storage, locking casters, and adequate floor clearance for cleaning.
10. Slide-out keyboard trays should be included for all applicable computer workstations/tables unless specifically excluded by Microbiology.
11. Wall-mounted shelving should be provided above all three Room 1 worktables.

12. Shelving should be adjustable and capable of being positioned flat or angled.
13. One 3-tier stainless steel rolling cart should be included for Room 1, with raised lip edges, push handle, adequate weight capacity, and swivel casters.

Room 2 Sink / Flammable Storage / Workstations

14. Room 2 must include a fixed sink/casework area with a laboratory-grade stainless steel, phenolic resin, or equivalent work surface.
15. Sink area should include double sinks to support Microbiology workflow and safe specimen/process handling.
16. Sink design must include appropriate faucet/plumbing coordination and must clearly state whether faucet, plumbing connection, drain connection, and utility tie-in are included or excluded.
17. The left corner area should accommodate a vendor-provided approved flammable storage cabinet.
18. Flammable storage cabinet must be reviewed by Safety/Facilities for code compliance, utility compatibility, ventilation/placement concerns, and safe access.
19. Vendor must specify flammable cabinet dimensions, rating, material, shelf configuration, and whether it is integrated into the casework or installed as a separate approved cabinet.
20. Room 2 should include one workstation approximately 20" L x 24" D x 36" H with half-depth lower shelf and clearance below for trash can or workflow needs.
21. Room 2 should include one workstation approximately 72" L x 24" D x 36" H with lower shelf, locking casters, and slide-out keyboard tray if used for computer entry.
22. Room 2 should include one analyzer workstation approximately 24" L x 24" D x 49" H with slide-out keyboard tray and two full-depth lower shelves for printer/storage needs.
23. One 3-tier stainless steel rolling cart should be included for Room 2 with raised lip edges, push handle, adequate weight capacity, and swivel casters.

Room 3 Microscope / Analyzer Area

24. Room 3 should include two microscope worktables, approximately 70" L x 36" D x 41" H each.

- 25. Microscope tables should have stainless steel, phenolic resin, or equivalent laboratory-grade work surfaces.
- 26. Each microscope table should include a full-depth lower shelf for storage and locking casters with adequate clearance for cleaning.
- 27. Room 3 should include one analyzer table approximately 21" L x 22" D x 35" H with full-depth shelves and locking casters.
- 28. Wall-mounted shelving should be provided above the microscope worktables.
- 29. Room 3 shelving should be adjustable and capable of being positioned flat or angled.

Room 4 Workstation / Analyzer Area

- 30. Room 4 should include one workstation approximately 72" L x 30" D x 41" H.
- 31. Room 4 workstation should include a laboratory-grade work surface, half-depth lower shelf for CPU tower/storage, locking casters, and slide-out keyboard tray.
- 32. Room 4 should include one analyzer worktable approximately 32" W x 36" D x 41" H.
- 33. Room 4 analyzer table should include a laboratory-grade work surface, half-depth lower shelf, locking casters, and slide-out keyboard tray.
- 34. Wall-mounted shelving should be provided above the Room 4 workstation areas.
- 35. Room 4 shelving should be adjustable and capable of being positioned flat or angled.

Keyboard Tray Requirement

- 36. Vendor must clearly identify which tables include slide-out keyboard trays.
- 37. Vendor must provide a separate itemized cost for adding slide-out keyboard trays to all remaining applicable workstations.
- 38. Microbiology preference is for keyboard trays to be included on all workstations where computer entry, analyzer operation, or documentation will occur.

Mobility / Cleaning / Ergonomic Requirements

- 39. Workstations should include locking casters where applicable.
- 40. Workstations should maintain adequate floor clearance, preferably 9" where specified, to support cleaning, movement, and infection control.

- 41. Workstation height and depth should support ergonomic use by laboratory staff.
- 42. Vendor should identify whether any height-adjustable option is available or whether all tables are fixed height.
- 43. Workstations should support safe separation of clean and dirty workflow areas where applicable.
- 44. Layout should support specimen processing, culture workup, microscope review, analyzer use, documentation, and supply access without excessive reaching or workflow congestion.

Shelving Requirements

- 45. Wall shelving must be properly secured and compatible with wall structure.
- 46. Vendor must identify whether wall blocking is required.
- 47. Vendor must coordinate wall-mounted shelving requirements with Facilities before installation.
- 48. Shelving should be laboratory-grade, cleanable, durable, and appropriate for Microbiology supplies.

Installation / Delivery / Clean-Up Requirements

- 49. Quote must include delivery to the jobsite.
- 50. Quote must include unloading of all materials.
- 51. Quote must include unpacking of all materials.
- 52. Quote must include movement of materials from receiving/staging area to the laboratory.
- 53. Quote must include assembly, placement, and installation of all workstations, casework, shelving, carts, analyzer tables, microscope tables, sink casework, and flammable storage components.
- 54. Quote must include removal of packing materials.
- 55. Quote must include daily and final post-installation clean-up.
- 56. Quote must clearly state whether dumpster use, trash removal, or disposal services are included.

- 57. Quote must clearly state whether off-hours, weekend, or after-hours installation is included or would result in additional charges.
- 58. Quote must include final field verification before fabrication.
- 59. Field verification must confirm room dimensions, wall conditions, utility locations, delivery path, door clearances, hallway turns, elevator/freight access, receiving dock access, staging space, and installation restrictions.
- 60. Vendor must coordinate with Facilities, Safety, Shipping/Receiving, and the assigned project/contracting representative for site logistics.

Utilities / Facilities / Safety Requirements

- 61. Vendor must identify all plumbing, electrical, wall anchoring, utility shut-down, or facility preparation requirements.
- 62. Vendor must clearly state whether plumbing connection, faucet installation, sink drain connection, electrical work, wall blocking, and utility tie-ins are included or excluded.
- 63. Vendor must identify whether any cutting, grinding, drilling, anchoring, or wall modification is required.
- 64. Vendor must identify whether safety training, PPE, infection control measures, or protection of existing laboratory equipment is required during installation.
- 65. Work must be coordinated to minimize disruption to active Microbiology operations.

Vendor Response Requirements

- 66. Vendor must provide revised drawings showing all requested changes.
- 67. Vendor must provide an itemized quote by room and by workstation.
- 68. Vendor must provide material specifications/cut sheets for all proposed surfaces, sinks, cabinets, shelving, carts, flammable storage, casters, and keyboard trays.
- 69. Vendor must clearly identify included versus excluded services.
- 70. Vendor must identify warranty terms, lead time, installation duration, and any assumptions that may affect cost.
- 71. Vendor must confirm that the quote includes delivery, unloading, unpacking, installation, assembly, placement, removal of packing materials, and clean-up.

72. Vendor must not assume Microbiology staff will unload, move, assemble, install, dispose of packing materials, or coordinate facility utility shut-downs.

At this time, vendor responses should be considered incomplete unless they clearly address the above requirements.